
INDEX OF SHEETS		
SHEET NO.	DESCRIPTION	
1	COVER	
2	LEGEND	
3	NOTES	
4	EXISTING CONDITIONS	
5	SOIL EROSION AND SEDIMENTATION CONTROL PLAN	
7	REMOVAL AND ACCESS PLAN	
8	CONSTRUCTION PLAN	
9	GRADING PLAN	
11	LANDSCAPE PLAN	
10	PLANT AND MATERIAL IMAGES	
12	LANDSCAPE DETAILS	
13 - 14	SITE DETAILS	

CHARTER TOWNSHIP OF CHESTERFIELD MACOMB COUNTY, MICHIGAN

BRANDENBURG PARK SHORELINE AND HABITAT RESTORATION




LOCATION MAP

GENERAL PROVISIONS

THE IMPROVEMENTS COVERED BY THESE PLANS SHALL BE DONE IN ACCORDANCE WITH THE PROPOSAL AND ACCOMPANYING SPECIFICATIONS FOR THIS PROJECT INCLUDING THE 2012 MICHIGAN DEPARTMENT OF TRANSPORTATION STANDARD SPECIFICATIONS FOR CONSTRUCTION AND 2011 MICHIGAN MANUAL OF UNIFORM TRAFFIC CONTROL DEVICES.


THE LOCATION OF ALL PUBLIC UTILITIES SHOWN ON THESE PLANS IS TAKEN FROM THE BEST AVAILABLE DATA. CHESTERFIELD TOWNSHIP WILL NOT BE RESPONSIBLE FOR ANY OMISSION OR VARIATION FROM THE LOCATIONS SHOWN. PURSUANT TO ACTS 173 & 174 OF THE P.A. OF 2013, AS A CONDITION OF THIS CONTRACT, NOTICE SHALL BE GIVEN TO MISS DIG PRIOR TO UNDERGROUND WORK TO BE PERFORMED IN ACCORDANCE WITH THIS CONTRACT, PHONE (800) 482–7171 (OR 811). UTILITY SERVICE CONNECTIONS ARE NOT SHOWN ON THE PLANS AND ARE NOT THE RESPONSIBILITY OF THE CHESTERFIELD TOWNSHIP.

THE ELEVATIONS SHOWN ON THESE PLANS REFERENCE THE INTERNATIONAL GREAT LAKES DATUM (IGLD 1985).









LOCATION AND SCOPE OF PROJECT

BRANDENBURG PARK IS LOCATED ON JEFFERSON AVENUE ABOUT $rac{1}{2}$ MILE SOUTH OF 23 MILE ROAD IN CHESTERFIELD TOWNSHIP, MACOMB COUNTY, MI. THE 17-ACRE PARK IS LOCATED ON THE NORTHWEST SHORELINE OF ANCHOR BAY. THE WORK TO BE DONE UNDER THIS CONTRACT INCLUDES THE FURNISHING OF ALL MATERIALS, EQUIPMENT, AND LABOR NECESSARY TO CONSTRUCT A LIVING SHORELINE, RUBBLE MOUND BREAKWATER AND VARIOUS HABITAT STRUCTURES.

GENERAL NOTES

- 1. THE IMPROVEMENTS COVERED BY THESE PLANS SHALL BE DONE IN ACCORDANCE WITH THE PROPOSAL AND ACCOMPANYING SPECIFICATIONS FOR THIS PROJECT INCLUDING THE 2012 MICHIGAN DEPARTMENT OF TRANSPORTATION STANDARD SPECIFICATIONS FOR CONSTRUCTION.
- 2. IT IS THE INTENTION OF THESE PLANS TO CONSTRUCT ALL WORK IN ACCORDANCE WITH THE CONTRACT DOCUMENTS, THE PLANS REFERENCED HEREIN, AND ANY APPLICABLE REQUIREMENTS OF THE FOLLOWING:
 - MICHIGAN DEPARTMENT OF ENVIRONMENTAL QUALITY,
 - GREAT LAKES COMMISSION,
 - NATIONAL OCEANIC AND ATMOSPHERIC ADMINISTRATION,
- WHERE THERE IS A CONFLICT BETWEEN ANY OF THE AFOREMENTIONED SPECIFICATIONS AND THE PERMIT REQUIREMENTS OF THE AGENCY CONTROLLING THE WORK ALLOWED ON SITE TO THE RESPECTIVE UTILITY OR RIGHTS-OF-WAY, THE MORE RESTRICTIVE SHALL GOVERN.
- 4. THE CONTRACTOR AND SUBCONTRACTORS SHALL ATTEND A PRE-CONSTRUCTION MEETING AT A TIME AND PLACE ARRANGED BY THE ENGINEER IN WHICH THE AFFECTED UTILITY COMPANIES AND GOVERNMENT AGENCY REPRESENTATIVES WILL BE PRESENT. ALSO, A PRE-CLEARING WALK-THROUGH WILL NEED TO BE ATTENDED BY THE CONTRACTOR.
- 5. AFTER A PRE-CONSTRUCTION MEETING IS HELD, THE CONTRACTOR SHALL NOTIFY THE CHESTERFIELD TOWNSHIP PUBLIC WORKS (586-949-0400), A MINIMUM OF THREE (3) WORKING DAYS PRIOR TO THE START OF CONSTRUCTION FOR INSPECTION. NO WORK CAN COMMENCE UNTIL ALL PERMITS HAVE BEEN OBTAINED AND THE CONTRACTOR HAS BEEN GIVEN AUTHORIZATION TO PROCEED.
- 6. ALL ELEVATIONS REFER TO CURRENT INTERNATIONAL GREAT LAKES DATUM OF 1985 (IGLD '85).
- ALL PROPERTIES OR FACILITIES IN THE SURROUNDING AREAS, PUBLIC OR PRIVATE, DESTROYED OR OTHERWISE DAMAGED BY THE CONTRACTORS OPERATIONS SHALL BE REPLACED OR REPAIRED TO THE SATISFACTION OF THE AUTHORITY HAVING JURISDICTION OF THE PROPERTY OR FACILITY BY THE CONTRACTOR AT THEIR OWN EXPENSE. UNDER NO CIRCUMSTANCES, SHALL HEAVY EQUIPMENT DRIVE ON THE EXISTING PAVED PARKING LOT.
- CONTRACTOR SHALL PROVIDE AND MAINTAIN ALL NECESSARY BARRICADES AND TRAFFIC CONTROL DEVICES REQUIRED BY CHESTERFIELD TWP, MACOMB COUNTY DEPARTMENT OF ROADS (MCDR), AND CURRENT EDITION OF THE MICHIGAN MANUAL ON UNIFORM TRAFFIC CONTROL DEVICES.
- 9. IF, IN THE OPINION OF THE ENGINEER, WORK HAS NOT PROGRESSED IN A REASONABLE AND TIMELY MANNER, THE ENGINEER SHALL HAVE THE RIGHT, WITH THE APPROVAL OF THE TOWNSHIP, TO DIRECT THE CONTRACTOR TO PROCEED WITH THE WORK OR ANY PORTION THEREOF IMMEDIATELY, IN THE EVENT THAT THE CONTRACTOR DOES NOT PROCEED WITH THE WORK IMMEDIATELY, AS DIRECTED BY THE ENGINEER. THE ENGINEER, UNDER THE DIRECTION OF CHESTERFIELD TOWNSHIP. MAY ORDER ANY OR ALL OTHER OPERATIONS OF THE CONTRACTOR. UNDER THIS CONTRACT, TO CEASE UNTIL THE FINAL CLEANUP AND RESTORATION WORK IS PROCEEDING IN AN ACCEPTABLE MANNER. SHOULD THE CONTRACTOR FAIL TO COMPLY WITH THESE PROVISIONS, THE TOWNSHIP MAY, WITH OR WITHOUT NOTICE, CAUSE THE REQUIRED RESTORATION AND CLEANUP TO BE DONE BY THE TOIWNSHIP OR OTHERS AND WILL DEDUCT THE COST OF SAID WORK FROM ANY MONEY DUE OR TO BECOME DUE THE CONTRACTOR UNDER THIS CONTRACT. THE PERFORMANCE OF SUCH WORK BY THE TOWNSHIP OR OTHERS SHALL SERVE IN NO WAY TO RELEASE THE CONTRACTOR FROM HIS GENERAL OR PARTICULAR LIABILITY FOR THE SAFETY OF THE PUBLIC OR THE WORK.
- 10. ALL ITEMS REFERRED TO AS "INCIDENTAL" OR "COST SHALL BE INCIDENTAL" SHALL BE INCLUDED IN THE UNIT PRICES LISTED IN THE CONTRACT DOCUMENTS. NO SEPARATE COSTS WILL BE ACCEPTED.

UTILITIES

THE FOLLOWING UTILITY COMPANIES HAVE FACILITIES WITHIN THE PROJECT LIMITS:

- 1. CHESTERFIELD TOWNSHIP 4. FOR TELEPHONE: ATT (FORMERLY SBC) 52216 SIERRA DRIVE 54 N. MILL ST, 4TH FLOOR CHESTERFIELD, MI 48047 ATT: DON CODDINGTON PONTIAC, MI 48342 PH: 586-949-0400 ATTN: LINDA DENNISUK PH: 248-456-8256
- 2. FOR ELECTRIC: 5. FOR GAS: DETROIT EDISON SEMCO ENERGY ONE ENERGY PLAZA, 518 SB 1411 THIRD ST, SUITE A PORT HURON, MI 48060 DETROIT, MI 48226 ATTN: ATTN: RYAN CAMERON PH: 313-235-5632 PH: 810-887-3085
- 3. FOR CABLE TELEVISION: 6. FOR FIBER OPTIC: ATT (FORMERLY SBC) ATT (FORMERLY SBC) 54 N. MILL ST, 4TH FLOOR 54 N. MILL ST, 4TH FLOOR PONTIAC, MI 48342 PONTIAC, MI 48342 ATTN: LINDA DENNISUK ATTN: LINDA DENNISUK PH: 248-456-8256 PH: 248-456-8256

THE CONTRACTOR SHALL BE EXCLUSIVELY RESPONSIBLE FOR DETERMINING AND VERIFYING THE LOCATION, DEPTH AND ELEVATION OF EXISTING UTILITIES, AND PROPOSED UTILITIES CROSSING THE CONSTRUCTION AREA PRIOR TO START OF CONSTRUCTION. CONTRACTOR SHALL NOTIFY ENGINEER IF ANY CONFLICTS ARE APPARENT OR IF LOCATIONS AND DEPTHS DIFFER SIGNIFICANTLY FROM THE PLANS. THE LOCATION OF ALL PUBLIC UTILITIES SHOWN ON THESE PLANS IS TAKEN FROM THE BEST AVAILABLE DATA. CHESTERFIELD TOWNSHIP WILL NOT BE RESPONSIBLE FOR ANY OMISSION OR VARIATION FROM THE LOCATIONS SHOWN. PURSUANT TO ACTS 173 & 174 OF THE P.A. OF 2013, AS A CONDITION OF THIS CONTRACT, NOTICE SHALL BE GIVEN TO MISS DIG PRIOR TO UNDERGROUND WORK TO BE PERFORMED IN ACCORDANCE WITH THIS CONTRACT, PHONE (800) 482-7171 OR 811 A MINIMUM OF THREE WORKING DAYS. EXCLUDING SATURDAYS, SUNDAYS & HOLIDAYS. THIS DOES NOT RELIEVE THE CONTRACTOR OF THE RESPONSIBILITY OF NOTIFYING OWNERS WHO MAY NOT BE PART OF THE "MISS DIG" ALERT SYSTEM. UTILITY LOCATIONS SHOWN ON THE PLANS ARE ONLY APPROXIMATE. THE CONTRACTOR SHALL BE EXCLUSIVELY RESPONSIBLE FOR VERIFYING THE LOCATION OR ALL UTILITIES.

GENERAL LANDSCAPE NOTES

- 1. CONTRACTOR SHALL NOT WILLFULLY PROCEED WITH CONSTRUCTION AS DESIGNED WHEN IT IS OBVIOUS THAT UNKNOWN OBSTRUCTIONS AND/OR GRADE DIFFERENCES EXIST. SUCH CONDITIONS SHALL BE IMMEDIATELY BROUGHT TO THE ATTENTION OF THE ENGINEER.
- 2. CONTRACTOR SHALL BE RESPONSIBLE FOR ANY COORDINATION WITH SUBCONTRACTORS AS REQUIRED TO ACCOMPLISH PLANTING OPERATIONS.
- 3. ALL WORK TO BE PERFORMED BY LICENSED AND INSURED CONTRACTORS AND EXPERIENCED WORKERS.
- 4. REFER TO DETAILS AND SPECIFICATIONS FOR ADDITIONAL INFORMATION.
- 5. THE CONTRACTOR SHALL KEEP ALL DRAINAGE FACILITIES (CATCH BASINS, YARD DRAINS, ETC.) AFFECTED BY HIS CONSTRUCTION OPERATIONS CLEAN AND FULLY OPERATIONAL AT ALL TIMES.
- CONTRACTOR SHALL REPAIR AT HIS OWN EXPENSE, ANY DAMAGE, WHETHER INSIDE OR OUTSIDE OF THE PROJECT LIMITS, TO UTILITY SYSTEMS, SURFACE PAVEMENTS, FIXTURES, STRUCTURES, AND/OR EXISTING TREES OR LANDSCAPING THAT ARE NOT SPECIFICALLY INDICATED TO BE REMOVED OR RELOCATED AS PART OF THE PROJECT CONSTRUCTION. IN THE EVENT THAT ANY EXISTING DRAINAGE STRUCTURES OR UTILITIES ARE DAMAGED AND THE SERVICES DISRUPTED, THE LINES SHALL BE IMMEDIATELY REPAIRED AND THE SERVICES RESTORED AS DIRECTED BY THE ENGINEER.
- 7. IN THE EVENT THAT DISCREPANCIES ARISE BETWEEN WHAT IS SHOWN ON THE DRAWINGS AND ACTUAL FIELD CONDITIONS THE ENGINEER SHALL BE NOTIFIED IMMEDIATELY FOR RESOLUTION.

LANDSCAPE LAYOUT NOTES

- 1. ALL DIMENSIONS SHOWN ARE IN FEET AND INCHES UNLESS OTHERWISE NOTED.
- 2. DO NOT SCALE DRAWINGS. UTILIZE DIMENSIONS INDICATED ON THE PLANS.
- 3. LAYOUT ALL CONSTRUCTION LINES AND VERIFY LAYOUT WITH THE ENGINEER PRIOR TO BEGINNING ANY CONSTRUCTION WORK.
- 4. STAKE TREES ON-SITE FOR FINAL APPROVAL BY ENGINEER PRIOR TO PLANTING.
- 5. REFER TO GENERAL NOTES AND PLANTING NOTES FOR ADDITIONAL INSTRUCTIONS.
- 6. FIELD VERIFY ALL PROPOSED AND EXISTING UTILITY LOCATIONS.
- 7. THE CONTRACTOR SHALL COORDINATE ALL WORK AND BE RESPONSIBLE FOR ALL METHODS, MEANS, SEQUENCE, AND PROCEDURES OF THE WORK.

PLANTING NOTES

- SECURE PLANT MATERIAL AS SPECIFIED ON PLANS. IN THE EVENT THAT PLANT MATERIALS SPECIFIED ARE NOT AVAILABLE, CONTRACTOR SHALL SUBMIT ALTERNATES TO ENGINEER FOR APPROVAL PRIOR TO SUBMITTING A BID. NO SUBSTITUTIONS FOR PLANT MATERIALS WILL BE ALLOWED WITHOUT PRIOR WRITTEN APPROVAL BY THE ENGINEER.
- 2. VERIFY THAT ALL PLANTING PRODUCTS, PLANT MATERIAL, AND PLANT QUANTITIES DELIVERED TO THE SITE MATCH WHAT IS INDICATED ON THE PLANS AND SPECIFICATIONS.
- PROTECT ALL PLANT MATERIAL DURING DELIVERY TO PREVENT DAMAGE TO ROOT BALLS, TRUNKS, BRANCHES AND THE DESICCATION OF LEAVES. PROTECT ALL PLANT MATERIAL DURING SHIPPING WITH SHADE CLOTH OR SHIP WITH ENCLOSED TRANSPORT. MAINTAIN PROTECTIONS AND HEALTH OF PLANT MATERIAL STORED ON SITE. HANDLE ALL TREES WITH NYLON STRAPS. NO CHAINS OR CABLES ALLOWED. REMOVE UNACCEPTABLE PLANT MATERIAL IMMEDIATELY FROM THE SITE.
- 4. ALL PLANT MATERIAL SHALL BE NURSERY GROWN, WELL FORMED, TRUE TO SPECIES, HARDENED OFF WITH VIGOROUS ROOT SYSTEMS. FULL CROWN AND CANOPIES. AND FREE FROM DISEASE. PESTS AND INSECTS, AND DEFECTS SUCH AS KNOTS, SUN SCALD, WINDBURN, LEAF DISCOLORATION, IRREGULAR BRANCHING OR INJURIES. ALL SHRUBS, LIVE STAKES AND PLUGS SHALL CONFORM TO THE SIZE STANDARDS SET FORTH IN 'AMERICAN STANDARDS FOR NURSERY STOCK'.
- 5. PROVIDE SOURCE INFORMATION AND PLANT SAMPLES OR PHOTOGRAPHS OF EACH PLANT SPECIFIED TO THE ENGINEER FOR COMPLIANCE REVIEW PRIOR TO SHIPMENT.
- 6. ALL PLANT MATERIAL DELIVERED TO THE SITE IS SUBJECT TO THE REVIEW AND ACCEPTANCE OF THE ENGINEER BEFORE, DURING AND AFTER INSTALLATION.
- 7. THE ENGINEER RESERVES THE RIGHT TO INSPECT AND/OR SELECT ANY AND ALL PLANT MATERIAL AT THE NURSERY PRIOR TO DELIVERY TO THE SITE.
- 8. TEST FILL ALL SHRUB PLANTING PITS WITH WATER PRIOR TO PLANTING, TO ASSURE PROPER SOIL PERCOLATION. PITS WHICH DO NOT ADEQUATELY DRAIN SHALL BE FURTHER EXCAVATED TO A DEPTH SUFFICIENT FOR DRAINAGE TO OCCUR AND/OR BACKFILLED WITH SUITABLE DRAINAGE GRAVEL. NO ALLOWANCES SHALL BE MADE FOR PLANT MATERIAL LOSS DUE TO IMPROPER DRAINAGE.
- 9. CONTRACTOR SHALL REPLACE DEAD OR DYING PLANT MATERIAL WITH SAME SIZE AND SPECIES AT NO ADDITIONAL COST TO OWNER.
- 10. ALL PLANT MATERIALS, INCLUDING RELOCATED PLANT MATERIAL, SHALL BE PLANTED IN A PROFESSIONAL MANNER TYPICAL TO THE INDUSTRY STANDARDS TO ASSURE COMPLETE SURVIVABILITY OF ALL INSTALLED PLANT MATERIALS AS WELL AS TO PROVIDE AN AESTHETICALLY APPROVED PROJECT. CONTRACTOR SHALL REFER TO THE PLANTING DETAILS FOR MINIMUM SIZE AND WIDTH OF PLANTING BEDS, MULCHING, AND OTHER PLANTING REQUIREMENTS.
- 11. LAWN AREAS TO PROVIDE A SMOOTH AND CONTINUAL GRADE.
- 12. SHRUBS SHALL HAVE A MINIMUM OF 4" DEPTH OF DOUBLE SHREDDED HARDWOOD MULCH AND SHALL BE CONSISTENT WITH PLANTING DETAILS AND SPECIAL PROVISIONS. LIVE STAKES AND PLANTING PLUGS SHALL NOT BE MULCHED. SHRUBS SHALL HAVE A TWO FOOT DIAMETER MULCH
- 13. ALL AREAS WITH PROPOSED PLANTS SHALL HAVE AN EROSION CONTROL BLANKET APPLIED TO SECURE SOILS WHILE PLANTINGS ESTABLISH.
- 14. ALL PLANTINGS IN THE UPLAND PLANTING AREA SHALL HAVE A 6" LAYER OF PLANTING MIX APPLIED. ALL OTHER AREAS SHALL UTILIZE EXISTING SITE SOILS FOR PLANTING. WHEN PLANTING SHRUBS, PLANT MATERIAL PITS SHALL BE BACKFILLED WITH EXISTING SITE SOILS DUG UP FROM PLANTING PITS. EXISTING SOILS USED FOR BACKFILL OF SHRUB PLANTINGS SHALL BE AERATED AND STIRRED PRIOR TO BACKFILLING, AS DESCRIBED IN THE PLANTING DETAILS AND SPECIAL

PLANTING NOTES CONTINUED

- 15. ALL PLANTING AREAS SHALL BE WEED FREE PRIOR TO PLANTING INSTALLATION.
- 16. REMOVE ALL PLANTING AND LANDSCAPE DEBRIS FROM THE PROJECT SITE AND SWEEP AND WASH CLEAN ALL PAVED AND FINISHED SURFACES IMPACTED BY THE LANDSCAPE INSTALLATION.
- 17. THE CONTRACTOR SHALL COORDINATE PLANTING PERIODS WITH INITIAL MAINTENANCE PERIODS TO PROVIDE THE REQUIRED MAINTENANCE FROM THE DATE OF PLANTING COMPLETION. ALL PLANTING SHALL OCCUR DURING ONE OF THE FOLLOWING PERIODS:
 - SPRING PLANTING: APRIL 15 JUNE 1
 - FALL PLANTING: SEPTEMBER 1 OCTOBER 15
- STAKE PLANTING: NOVEMBER 15 APRIL 15, UNLESS GROUND IS FROZEN
- 20. FERTILIZERS AND PESTICIDES SHALL NOT BE USED WITHIN PROJECT LIMITS.
- 21. ALL SHRUBS, LIVE STAKES AND PLANT PLUGS SHALL BE ARRANGED IN A WAY SO AS TO PROMOTE EVEN DISTRIBUTION OF SPECIES THROUGHOUT PROJECT SITE.
- 22. REFER TO GENERAL LANDSCAPE NOTES FOR ADDITIONAL INSTRUCTIONS.
- 23. SEE SHEET #12 FOR PLANTING DETAILS

AQUATIC PLANTING


- 1. STOCK SHALL NOT BE SHIPPED UNTIL THE PLANTING AREA HAS BEEN PREPARED. SHIPPING SHALL BE SCHEDULED TO RESULT IN A STORAGE TIME OF NO MORE THAN 24 HOURS.
- 2. TUBERS, ROOTSTOCK AND HERBACEOUS SEEDLINGS SHALL BE INDIVIDUALLY LABELLED OR LABELLED IN BUNDLES.
- 3. PLANTS SHALL BE STORED TO ENSURE VIABILITY. STORAGE PROCEDURES MAY INCLUDE THE OPENING OF STORAGE CONTAINERS, STORAGE IN WATER, AND/OR REFRIGERATION.
- 4. ALL PLANTS SHALL BE HEALTHY AND FREE OF FUNGAL AND BACTERIAL DISCOLORATION AND DEFORMITIES. PLANTS APPEARING TO BE UNHEALTHY WILL BE SUBJECT TO REJECTION BY THE
- 5. PLANTINGS TO BE PLACED IN WET OR SATURATED SOILS SHALL BE PRE-CONDITIONED BY
- BEING HELD UNDER SIMILAR CONDITIONS AT THE NURSERY PRIOR TO SHIPMENT TO THE SITE.
- 6. PRIOR TO AQUATIC PLANTING, THE CONTRACTOR SHALL NOTIFY THE ENGINEER AT LEAST SEVEN DAYS IN ADVANCE TO ASSIST IN LAYOUT OF AQUATIC PLANTS.
- 7. ALL AQUATIC PLANTING SHALL BE COMPLETED BETWEEN MAY 15 AND JUNE 30.
- 8. AQUATIC PLANTS SHALL BE PLANTED FIRMLY IN THE MUD AT THE APPROPRIATE WATER DEPTH FOR EACH SPECIES. TUBERS SHALL BE WEIGHTED AND PLANTED IN THE UPPER THREE INCHES OF SOIL. THE CONTRACTOR SHALL INSPECT THE PLANTING AT LEAST EVERY OTHER DAY DURING THE FIRST TEN DAYS AFTER COMPLETION. ANY AQUATIC PLANTS THAT BECOME DISLODGED OR FLOAT SHALL BE IMMEDIATELY RE-PLANTED.


SUGGESTED SEQUENCE OF CONSTRUCTION

- 1. MOBILIZE ALL EQUIPMENT AND MATERIALS TO THE SITE.
- 2. SET UP AND MAINTAIN ALL EROSION CONTROL MEASURES
- 3. REMOVE ALL ITEMS INDICATED ON THE REMOVAL PLAN.
- 4. CONSTRUCT ALL UPLAND FEATURES DURING THE SUMMER/FALL GROWING SEASON, INCLUDING ANY LANDSCAPING THAT TIME WILL ALLOW.
- 5. CONSTRUCT ALL IN-WATER STRUCTURES DURING THE WINTER MONTHS (OCTOBER 1 - MARCH 31).
- 6. CLEAN UP THE SITE, RESTORE ANY DAMAGE, AND DEMOBILIZE.



1			
	HORIZ DATUM VERT DATUM	IGLD '85	
	HORIZ DATUM	NAD 83/8	
	SCALE	٧:	
		H: 1"=40'	Z
			ATIO
	CITY/VILLAGE/TOWNSHIP	Chesterfield Twp	ESTOR
	CITY/VILL	Ches	ITAT RESTORATION
	COUNTY	Macomb	
	CADD	MPB	NE AN
)		∥P)RELI
	PROJ MGR	Valeria Novaes	WNSF KK SHC
	ENG	-	LD TO
	PROJ NUMBER	0355-19-0010	CHESTERFIELD TOWNSHIP BRANDENBURG PARK SHORELINE AND HAB NOTES
		0356	CHEST 3RANDI NOTES
	DATE		SR NC






SOIL EROSION CONTROL PLAN




ACCESS PLAN NOT TO SCALE



GRAVEL ACCESS APPROACH
PLAN

NOTE:
TEMPORARY ACCESS ROAD SHALL BE CONSTRUCTED IN A METHOD THAT
CAN BE INSTALLED, UTILIZED, AND REMOVED WITH MINIMAL IMPACT
TO THE PARK. OPTIONS INCLUDE GEOTEXTILE WRAPPED AGGREGATE,
CRANE-MATS, OR DURA-MATS.



GRAVEL ACCESS APPROACH
PROFILE

TEMPORARY EROSION CONTROLS MAINTENANCE PLAN

MEASURE MAINTENANCE SCHEDULE

RBIDITY CURTAIN

INSTALL AT START OF PROJECT PER PLAN. CURTAIN SHALL BE INSPECTED
DAILY AND SHALL CONFORM TO THE DETAIL ON SHEET #5. DAMAGED OR
DISPLACED SECTIONS SHALL BE RESTORED IMMEDIATELY. SEDIMENT SHALL

BE REMOVED AT THE END OF CONSTRUCTION.

SILT FENCE INSTALL AT START OF PROJECT PER PLAN. FENCE SHALL BE INSPECTED DAILY AND SHALL CONFORM TO THE DETAIL ON THIS SHEET. DAMAGED OR DISPLACED SILT FENCE SHALL BE RESTORED IMMEDIATELY. SEDIMENT

SHALL BE REMOVED WHEN ACCUMULATION IS EQUAL TO \(\frac{1}{2} \) THE HEIGHT OF THE FENCE.

STREET SWEEPING STREETS SHALL BE SWEPT AS DIRECTED BY THE ENGINEER OR TOWNSHIP

DUST CONTROL WATER SHALL BE APPLIED TO EXPOSED AREAS BY THE CONTRACTOR IN THE EVENT OF EXCESSIVE AIRBORNE DUST. DUST CONTROL SHALL BE

STOCK PILE AREAS PLACE STOCKPILES AND OTHER SPOIL PILES AWAY FROM THE DRAINAGE

SYSTEM TO MINIMIZE SEDIMENT TRANSPORT. IF THE STOCKPILE AND/OR SPOIL PILE MUST REMAIN ON—SITE OVERNIGHT, OR IF THE WEATHER CONDITIONS INDICATE THE CHANCE FOR PRECIPITATION, COVER THE PILE WITH WATER REPELLENT MATERIAL TO PREVENT EROSION AND INSTALL SILT FENCING AROUND THE BASE OF THE PILE TO PREVENT TRANSPORT OF SEDIMENT TO THE STORM WATER SYSTEM, OR APPLY OTHER CONTROL METHODS APPROPRIATE TO THE SIDE. CONTROL MEASURES TO GUARD AGAINST WIND EROSION MUST ALSO BE EMPLOYED, SUCH AS WETTING OR COVERING THE STOCKPILES. KEEP AS FEW STOCKPILES AS POSSIBLE

APPLIED AS DIRECTED BY THE ENGINEER OR TOWNSHIP PERSONNEL.

DURING THE COURSE OF THE PROJECT.

PROJECT SPECIFIC EROSION CONTROL NOTES

- THE PROJECT IS TO BE CONSTRUCTED IN BRANDENBURG PARK LOCATED IN SECTION 23, T.3N, R.14E, OF CHESTERFIELD TOWNSHIP, MICHIGAN.
- 2. ALL PROTECTIVE FENCING AND EROSION CONTROL MEASURES ARE TO BE INSTALLED ACCORDING TO PLANS AND SPECIFICATIONS CONTAINED HEREIN.
- 3. THE IMPERVIOUS AREA WILL NOT BE ALTERED, AS EXISTING PAVED SURFACES WILL BE RESTORED WITH PAVEMENT, AND EXISTING VEGETATIVE SURFACES WILL BE RESTORED WITH GRASS AND NATIVE SPECIES.
- 4. ANY SOILS TRACKED ONTO STREETS MUST BE REMOVED IMMEDIATELY FOLLOWING EACH TRACKING

PLACEHOLDER FOR QUANTITIES

OHM 3

ARCHITECTS ENGINEERS PLANNERS


34000 Plymouth Road
Livonia, MI 48150

OHM-ADVISORS.COM

P (734) 522-6711 | F (734) 522-6427

AND HABITAT RESTORATION


HERFIN CONSTITUTE THE ORIGINAL AND LINDLISHED WORK OF OHM AND THE SAME MAY NOT BE DIJPLICATED DISTRIBLITED OR DISCLOSE




ARCHITECTS ENGINEERS PLANNERS 34000 Plymouth Road Livonia, MI 48150 P (734) 522-6711 | F (734) 522-6427 OHM-ADVISORS.COM


Know what's **below.**Call before you dig.

CHESTERFIELD TOWNSHIP
BRANDENBURG PARK SHORELINE AI
REMOVAL AND ACCESS PLAN









Solidago riddellii

Verbena hastata

Temporary Grass Cover

Lolium multiflorum

Avena sativa

BRANDENBURG MATERIAL LIST

FINISH

Natural Boulders

Irregular Shaped Pieces

Irregular Shaped Pieces

BOULDER

FLAGSTONE

LEDGESTONE

NOTES

Heights vary between 3'-4'

Dry laid with crushed aggregate between stones

6" thickness, and approx 4-5' wide

0.50

1.00

1.00

Oz/acre Seeds/sq ft

80.00 24.79

320.00 7.35

40.00

Riddell's Goldenrod

Blue Vervain

Golden Alexander

Annual Ryegrass

Seed Oats

1.07

2.13

0.25

Know what's **below.** Call before you dig.


OF 14

RESTORATION

HABITAT

AND

ELINE



CHESTERFIELD TOWNSHIP
BRANDENBURG PARK SHORELINE AND HABITAT RESTORATION
LANDSCAPE DETAILS

ARCHITECTS ENGINEERS PLANNERS

34000 Plymouth Road Livonia, MI 48150

P (734) 522-6711 | F (734) 522-6427

OHM-ADVISORS.COM

