# CASCADE VALLEY METRO PARK VALLEY VIEW AREA PHASE 2 RESTORATION DESIGN

**1212 CUYAHOGA STREET** 

**AKRON, OHIO 44313** 

**MARCH 2020** 

# **BOARD OF PARK COMMISSIONERS:**

SUMMIT METRO PARKS
TINA UGHRIN, CHAIR
HERBERT NEWMAN
JOEL D. BAILEY
TONYA BLOCK
MARK A. SPISAK

LISA M. KING, RLA, CPRP-EXECUTIVE DIRECTOR

# PREPARED FOR:

Summit() Metro Parks

975 TREATY LINE ROAD AKRON, OHIO 44313 (330) 867-5511

# PREPARED BY:



Headquarters: 5070 Stow Road, Stow, OH 44224 800-940-4025 | EnviroScienceInc.com

DRAWINGS, SHEET 1-4, 7-29, 32-44 PREPARED BY:

ENVIROSCIENCE – ANGELINA D. HOTZ PE, ENV SP DATE

DRAWINGS, SHEETS 30-31 PREPARED BY:

GPD GROUP - MATTHEW A LASCOLA, PE DATE

DRAWINGS, SHEET 5-6 PREPARED BY:

GPD GROUP - STEVEN D. MULLANEY, PS DATE





# LOCATION MAP 1/4 MILE 0 1/8 1/4 1/2 N SCALE: 1"= 1/4 MILE



# **PROJECT DESCRIPTION:**

PROPOSED WORK CONSISTS OF PROVIDING EARTHWORK NECESSAR' TO CONSTRUCT FLOODPLAIN, WETLANDS, AND DRAINAGE IMPROVEMENTS. THE TOTAL PROJECT AREA DEFINED BY THE LIMITS OF DISTURBANCE IS APPROXIMATELY 57 ACRES.

ALL WORK AND MATERIALS SHALL COMPLY WITH THESE DRAWING AND BE SUPPLEMENTED BY THE ODOT 2016 CONSTRUCTION AN MATERIAL SPECIFICATIONS AND THE CITY OF AKRON AND SUMMI COUNTY ENGINEER REQUIREMENTS AS APPLICABLE.

# **DRAWING INDEX:**

TITLE SHEET	1
GENERAL NOTES, SPECIFICATIONS & LEGEND	2-4
EXISTING CONDITIONS MAP	5-6
KEY PLAN	7
OVERALL PLAN	8
DEMOLITION PLAN	9-10
GRADING PLANS	11-19
WETLAND GRADING PLAN	20
FUTURE PARK ROAD GRADING	21-22
CROSS SECTION KEY PLAN	23
CROSS SECTIONS	24-29
CULVERT PLAN & PROFILE	30
ACCESS ROAD PLAN & PROFILE	31-32
STANDARD DETAILS	33-35
PLANTING PLAN	36-39
STORMWATER POLLUTION PREVENTION PLAN	40-44

# **SUPPLEMENTAL DRAWINGS:**

DOMINION ENERGY - CUYAHOGA RIVER DIRECTIONAL DRILL PLAN

CASCADE VALLEY METRO PARK — PLAN AND PROFILE DRAWINGS (FUTURE PARK ROAD PLANS)

ACTIVE BALD EAGLE NEST PLAN



# **GENERAL NOTES**

### CIVIL NOTES:

# **GENERAL:**

THE CONTRACTOR SHALL CONTACT SUMMIT METRO PARKS (METRO PARKS) TO SCHEDULE A PRECONSTRUCTION MEETING. THE PRECONSTRUCTION MEETING SHALL BE HELD AT LEAST 48 HOURS (2-WORKING DAYS) PRIOR TO THE START OF CONSTRUCTION.

THE CONTRACTOR SHALL KEEP A LEGIBLE AND CURRENT COPY OF THE APPROVED PLANS AND BID SPECIFICATIONS ON SITE AT ALL TIMES.

THE BID SPECIFICATIONS AND CONTRACT DRAWINGS SHALL GOVERN THIS IMPROVEMENT. WITHIN THIS PROJECT ARE REFERENCES TO THE STATE OF OHIO, DEPARTMENT OF TRANSPORTATION, CONSTRUCTION AND MATERIALS SPECIFICATIONS (CMS), 2016, THE AKRON ENGINEERING BUREAU CONSTRUCTION AND MATERIAL SPECIFICATIONS, AND ADDITIONAL SPECIFICATION PROVIDED ON SHEET 4. THESE REFERENCES TO THE PROVIDED SPECIFICATIONS, ODOT, SUMMIT COUNTY AND AKRON SPECIFICATIONS SHALL GOVERN THIS IMPROVEMENT WHERE NOTED ON THE CONTRACT DRAWINGS OR REFERENCED IN THE TECHNICAL SPECIFICATIONS. OTHERWISE THE BID SPECIFICATIONS AND CONTRACT DRAWINGS WILL PREVAIL. PAY ITEMS SHALL COMPLY WITH THE CMS UNLESS NOTED ELSEWHERE.

UNLESS STATED IN THE PLANS OR BID SPECIFICATIONS, THE CONTRACTOR SHALL BE SOLELY RESPONSIBLE FOR COMPLYING WITH ALL FEDERAL, STATE, AND LOCAL REQUIREMENTS, INCLUDING SAFETY REQUIREMENTS. CONTRACTOR SHALL EXERCISE PRECAUTIONS AT ALL TIMES FOR THE PROTECTION OF ALL PERSONS, INCLUDING EMPLOYEES, PARK USERS AND PROPERTY.

UNLESS STATED IN THE PLANS OR BID SPECIFICATIONS, THE CONTRACTOR SHALL BE RESPONSIBLE FOR OBTAINING ALL PERMITS, PAYING ALL FEES, SCHEDULING AND OBTAINING ALL INSPECTIONS. THE CONTRACTOR IS ALSO RESPONSIBLE FOR SHOP DRAWING SUBMITTALS TO THE NECESSARY AGENCIES FOR PERMITS AND APPROVALS.

ALL ITEMS OF WORK CALLED FOR ON THE PLANS FOR WHICH NO SPECIFIC METHOD OF PAYMENT IS PROVIDED SHALL BE PERFORMED BY THE CONTRACTOR. THE COST OF SAME SHALL BE INCLUDED IN UNIT PRICES FOR THE VARIOUS RELATED ITEMS.

ANY MATERIAL OR ITEM OF WORK, WHICH HAS NO SPECIFICATION, SHALL BE APPROVED BY METRO PARKS. COST SHALL BE INCLUDED IN THE PRICES FOR THE VARIOUS RELATED ITEMS.

ANY DEFECTS IN CONSTRUCTION, INCLUDING MATERIALS OR WORKMANSHIP, SHALL BE CORRECTED BY REMOVAL AND REPLACEMENT OR OTHER APPROVED METHODS PRIOR TO ACCEPTANCE BY THE METRO PARKS. THE COST SHALL BE AT THE EXPENSE OF THE CONTRACTOR.

ANY MODIFICATIONS TO THE WORK AS SHOWN ON THESE APPROVED PLANS SHALL HAVE PRIOR WRITTEN APPROVAL OF THE METRO PARKS PRIOR TO PERFORMING THE WORK.

NORMAL WORKING HOURS ARE BETWEEN 7:00 A.M. AND 3:30 P.M. MONDAY THROUGH FRIDAY EXCLUSIVE OF HOLIDAYS. ANY WORK BEYOND THESE HOURS AND DAYS WILL ONLY BE ALLOWED UPON EXPLICIT APPROVAL OF METRO PARKS.

MATERIALS AND EQUIPMENT SHALL NOT BE STORED IN PUBLIC RIGHT OF WAYS OR WITHIN THE DRIP LINE OF EXISTING TREES TO REMAIN. ON-SITE STORAGE AREAS, NOT NOTED ON THE PLANS, MUST BE APPROVED BY METRO PARKS PRIOR TO PLACING ANY MATERIAL OR EQUIPMENT.

THE CONTRACTOR, CONTRACTOR'S EMPLOYEES, SUB-CONTRACTORS AND OTHER PERSONNEL AT THE SITE SHALL ACT APPROPRIATELY AND SHALL NOT USE PROFANE AND/OR OFFENSIVE LANGUAGE. THE CONTRACTOR IS RESPONSIBLE FOR THE BEHAVIOR OF THEIR EMPLOYEES AND SUBCONTRACTORS.

ALL EXCESS AND DEMOLISHED MATERIALS, SUCH AS BUT NOT LIMITED TO PIPE, ASPHALT, TIRES, METAL, RUBBISH, & OTHER DEBRIS SHALL BE HAULED FROM THE SITE AND PROPERLY DISPOSED OF LEGALLY. NO PAYMENT WILL BE MADE FOR HAULING MATERIALS FROM THE SITE. PAYMENT FOR HAULING AND DISPOSING OF MATERIALS SHALL BE INCLUDED IN THE UNIT PRICE FOR THE RELATED ITEM. EXISTING CONCRETE DEBRIS, FREE OF REBAR OR OTHER CONTAMINANTS, ON RIVER BANKS SHALL BE USED FOR FILL FOR THE EXISTING PONDS. CLEAN SOIL, TOP SOIL AND EXCAVATED MATERIAL SHALL BE HAULED AND PLACED IN SPOIL AREAS SHOWN ON THE PLAN (SEE SHEET 21–22). COST FOR HAULING AND SPOILING OF MATERIAL SHALL BE INCLUDED IN THE COST FOR EXCAVATION.

CONTRACTOR SHALL EMPLOY AN EXPERIENCED AND QUALIFIED SUPERINTENDENT, SATISFACTORY TO METRO PARKS. THE SUPERINTENDENT MUST BE IN ATTENDANCE AT THE JOB SITE AT ALL TIMES DURING THE PROGRESS OF WORK. THE SUPERINTENDENT SHALL NOT BE CHANGED WITHOUT THE CONSENT OF METRO PARKS.

# SURVEY/LAYOUT:

THE ELEVATION DATUM OF THE SURVEY IS NAVD 88, AND THE HORIZONTAL DATUM IS NAD83(2011), OHIO NORTH ZONE. ELEVATION CONTROL WAS ESTABLISHED SURVEY BY GPD GROUP, SEE SHEETS 5-6. CONTOUR LINES ARE BASED ON A COMBINATION OF GPD GROUP'S TOPOGRAPHICAL SURVEY DATA AND LIDAR DATA PROVIDED BY SUMMIT METRO PARKS. CONTRACTOR SHALL FIELD VERIFY ELEVATIONS AND ADVISE METRO PARKS OF ANY DISCREPANCIES

DO NOT SCALE FROM THESE DRAWINGS. WRITTEN DIMENSIONS SHALL GOVERN. CONTRACTOR SHALL VERIFY ALL DIMENSIONS ON THE GROUND AND REPORT ANY LAYOUT DISCREPANCIES IMMEDIATELY TO THE METRO PARKS.

THE CONSTRUCTION STAKING OF ALL SITE IMPROVEMENTS, INCLUDING THE CONSTRUCTION LIMITS, SHALL BE PERFORMED UNDER THE DIRECT SUPERVISION OF A SURVEYOR LICENSED IN THE STATE OF OHIO AT CONTRACTOR'S COST— INCLUDING INITIAL COST OF LAYOUT. AUTOCAD DRAWINGS WILL BE PROVIDED TO THE CONTRACTOR PRIOR TO CONSTRUCTION. THE CONTRACTOR SHALL NOTIFY METRO PARKS OF ANY DISCREPANCIES FOUND BETWEEN THE AUTOCAD DRAWINGS AND PRINTED DRAWINGS.

PRECISE LAYOUT SHALL BE STAKED AND APPROVED BY THE METRO PARKS 48 HOURS (2 WORKING DAYS) PRIOR TO THE START OF CONSTRUCTION.

GPS GUIDED CONSTRUCTION EQUIPMENT MAY BE USED ONLY IF APPROVED BY METRO PARKS. IF GPS GUIDED EQUIPMENT IS USED, METRO PARKS MAY REQUIRE CONTRACTOR TO PROVIDE REFERENCE STAKES FOR INSPECTION PURPOSES. COST OF REFERENCE STAKES SHALL BE INCLUDED IN THE PRICE FOR THE RELATED ITEM.

THE CONSTRUCTION LIMITS SHALL BE FIELD STAKED. WHEN SHOWN ON THE DRAWINGS, SILT FENCE OR ORANGE CONSTRUCTION FENCE SHALL BE PLACED ALONG THE CONSTRUCTION LIMITS TO PROTECT THE PUBLIC AND NATURAL RESOURCES FROM CONSTRUCTION ACTIVITY.

AREAS BEYOND THE CONSTRUCTION LIMITS SHALL NOT BE DISTURBED INCLUDING THE STOCKPILE OF ANY MATERIALS OR CONSTRUCTION TRAFFIC.

AREAS BEYOND THE CONSTRUCTION LIMITS, DISTURBED BY CONSTRUCTION ACTIVITY, SHALL BE RESTORED BY THE CONTRACTOR AT NO EXPENSE TO METRO PARKS. LIMITS OF EARTH DISTURBANCE SHALL BE CLEARLY INDICATED FOR EACH PHASE OF CONSTRUCTION PRIOR TO EARTH MOVING OPERATIONS.

THE CONTRACTOR SHALL REFERENCE ALL IRON PINS AND MONUMENTS IN DANGER OF DESTRUCTION BEFORE EXCAVATION. IF ANY PINS OR MONUMENTS ARE DISTURBED, A SURVEYOR, REGISTERED IN THE STATE OF OHIO, SHALL ACCURATELY RESET THEM AT THE CONTRACTOR'S EXPENSE. THE CONTRACTOR IS RESPONSIBLE FOR MAINTENANCE OR REFERENCING OF THE PRIMARY CONTROL POINTS. ANY POINTS DISTURBED DURING CONSTRUCTION SHALL BE RESET IF NECESSARY BY THE CONTRACTOR'S SURVEYOR AT NO EXPENSE TO THE METRO PARKS.

THE CONTRACTOR WILL THEN PROVIDE INFORMATION NECESSARY TO DEVELOP A FINAL SET OF "AS-BUILT" PLANS FOR THE PROJECT. THE CONTRACTOR SHALL PROVIDE A SET OF PLANS MARKED IN RED, CERTIFIED BY THE CONTRACTOR INCLUDING ALL FIELD CHANGES WHICH OCCURRED DURING CONSTRUCTION, AS DOCUMENTED BY ANY CHANGE ORDERS OR OTHERWISE. THE CONTRACTOR'S SURVEYOR WILL COMPLETE A SURVEY OF THE RESTORATION AREA, OBTAINING TOPOGRAPHIC INFORMATION THROUGHOUT ALL GRADED OR DISTURBED AREAS, EXCLUDING THE SPOIL AND FUTURE PARK ROADWAY AREAS. AS-BUILT SURVEY INFORMATION MUST ALSO INCLUDE BANK STABILIZATION LIMITS, WETLAND OUTLET ELEVATIONS AND EXTENTS, FINAL INSTALLATION LOCATIONS AND ORIENTATIONS OF ROCK SPURS AND BOULDER AND WOODY HABITATS. THE CONTRACTOR WILL THEN SUPPLY A FINAL AS-BUILT DRAWING SET, IN ADDITION TO THE RED LINE MARKED SET. AS-BUILT DRAWINGS SHALL BE PROVIDED FOR STORM SEWERS NOT CONSTRUCTED ACCORDING TO PLAN. ALL COST SHALL BE INCLUDED WITH VARIOUS RELATED ITEMS. FINAL CONTRACT PAYMENT WILL NOT BE MADE UNTIL "AS-BUILT" PLANS ARE RECEIVED AND APPROVED BY METRO PARKS.

CONTRACTOR SHALL REMOVE ALL CONSTRUCTION STAKES. COST SHALL BE INCLUDED IN THE PRICE FOR CONSTRUCTION STAKING.

# PROTECTION AND RESTORATION OF PROPERTY:

THE CONTRACTOR SHALL BE RESPONSIBLE FOR THE PRESERVATION OF ALL PUBLIC AND PRIVATE PROPERTY. ALL ROAD SURFACES, TRAILS, EASEMENTS, RIGHT-OF-WAYS, UTILITIES, STORM SEWERS, SANITARY SEWERS AND/OR APPURTENANCES, SIGNS, GUARD RAILING, MAIL AND/OR PAPER BOXES, DRIVE

CULVERTS, FENCES, TREES, LANDSCAPING, OTHER IMPROVEMENTS AND VEGETATION DISTURBED BY THE CONSTRUCTION OF ANY PART OF THESE IMPROVEMENTS ARE TO BE RESTORED BY THE CONTRACTOR. RESTORATION SHALL BE AS DIRECTED BY METRO PARKS OR THE LOCAL GOVERNING AGENCY AT THE CONTRACTOR'S EXPENSE.

CONTRACTOR SHALL KEEP ALL STREETS, LANES, AND PARKING AREAS ADJACENT TO THE PROJECT AREA CLEAN AND FREE FROM ANY DEBRIS, MUD AND/OR OTHER CONSTRUCTION EQUIPMENT AT ALL TIMES DURING CONSTRUCTION. CONTRACTOR SHALL REMOVE ANY DEBRIS AND MUD FROM PUBLIC STREETS AND METRO PARKS ROADS, TRAILS OR PARKING LOTS AT THE END OF EACH WORK DAY OR AS DIRECTED BY THE METRO PARKS.

THE CONTRACTOR SHALL IMMEDIATELY NOTIFY METRO PARKS OR IT'S REPRESENTATIVE IF SUSPECTED HAZARDOUS MATERIAL, MATERIALS THAT MAY CREATE A HEALTH RISK, ARCHEOLOGICAL ARTIFACTS OR BONES ARE DISCOVERED ON SITE.

### LITH ITIES.

THE CONTRACTOR IS RESPONSIBLE, PRIOR TO CONSTRUCTION, TO DETERMINE THE ACTUAL LOCATION AND ELEVATION OF ALL EXISTING UTILITIES WHETHER SHOWN ON THE PLANS OR NOT. THE CONTRACTOR SHALL CALL OUPS AT (800) 362-2764 AND OGPUPS AT (800) 925-0988 TWO FULL WORKING DAYS PRIOR TO THE START OF CONSTRUCTION. THE CONTRACTOR SHALL TAKE ALL NECESSARY PRECAUTIONS, AT NO ADDITIONAL EXPENSE TO THE PROJECT, TO AVOID DAMAGE TO EXISTING UNDERGROUND AND OVERHEAD UTILITY LINES DURING THE ENTIRE PROJECT. IN THE EVENT OF DAMAGE TO EXISTING PUBLIC AND/OR PRIVATE UTILITIES, THE AGENCY CONCERNED SHALL BE NOTIFIED IMMEDIATELY AND ALL REPAIR WORK SHALL BE EXECUTED IN ACCORDANCE WITH THE SPECIFICATIONS OF THE RESPECTIVE AGENCY AT NO ADDITIONAL EXPENSE TO THE PROJECT, INCLUDING ANY INSPECTION FEES OR MAINTENANCE CREWS.

WHERE EXISTING UTILITY POLES ARE IN CLOSE PROXIMITY TO WORK, THE CONTRACTOR SHALL COORDINATE HIS WORK EFFORTS WITH THOSE OF THE UTILITY COMPANIES SUCH THAT THE OPERATION OF THEIR EXISTING FACILITIES CAN BE MAINTAINED AND PROTECTED DURING THE TIME WORK IS GOING ON ADJACENT TO THE POLE.

THE CONTRACTOR SHALL PROVIDE PROTECTION OF EXISTING UTILITIES DURING CONSTRUCTION AS NEEDED TO PERFORM THE WORK SHOWN ON THE PLANS. THE LOCATION OF ALL KNOWN EXISTING UNDERGROUND UTILITY FACILITIES ARE SHOWN ON THE PLANS FROM DATA AVAILABLE AT THE TIME OF FIELD SURVEY IN ACCORDANCE WITH SECTION 153.64 OF THE OHIO REVISED CODE (O.R.C.). THE CONTRACTOR SHALL BE RESPONSIBLE FOR NOTIFICATION OF THE EXISTING UTILITY OWNERS AND UTILITY PROTECTION SERVICE LISTED BELOW IN ACCORDANCE WITH SECTION 153.64 OF THE O.R.C.. THE CONTRACTOR SHALL THOROUGHLY REVIEW THE SITE AND BECOME FAMILIAR WITH ALL UTILITIES (WATER, SANITARY, ELECTRIC, GAS, TELEPHONE, FIBER OPTIC, etc.) WITHIN THE LIMITS OF THE PROJECT, WHICH MAY INTERFERE WITH THE PROPOSED CONSTRUCTION. THE DETAILS AND DIMENSIONS SHOWN ON PLANS PERTAINING TO THE EXISTING FACILITIES HAVE BEEN OBTAINED FROM PLANS OF THE EXISTING FACILITIES AND DO NOT NECESSARILY REPRESENT AS—BUILT CONDITIONS. ALL PROJECT WORK HAS BEEN BASED UPON THE DETAILS AND DIMENSIONS PRESENTED ON THESE PLANS AND SPECIFICATIONS. UNEXPECTED UTILITY WORK SHALL BE CONTEMPLATED FOR COMPLETION AND PAID AS A PART OF THE PROJECT GENERAL ALLOWANCE

LISTED BELOW ARE ALL UTILITIES LOCATED WITHIN THE PROJECT CONSTRUCTION LIMITS TOGETHER WITH THEIR RESPECTIVE OWNERS. UTILITY INFORMATION IS PROVIDED BY SUMMIT METRO PARKS. THE CONTRACTOR SHALL VERIFY THAT NO OTHER UTILITIES ARE IMPACTED BY THE PROJECT.

# DESIGN OUPS TICKET REQUEST #: A711600691-00A, SUBMITTED 4/26/2017.

UTILITY OWNERS: <u>CITY OF AKRON WATER SUPPLY</u>: WATER DISTRIBUTION DIVISION, 1460 TRIPLETT BLVD., AKRON, OH 44306; 330–375–2227

CITY OF AKRON SEWER: SEWER MAINTENANCE FACILITY

2460 AKRON-PENINSULA RD., AKRON, OH 44313; 330-375-2666

# SPRINGER ENERGY

1450 CUYAHOGA STREET, AKRON, OH 44313 DAVID SPRINGER, 330—352—7553 HARRY HIMELRIGHT, 330—805—8494 SPRINGERENERGY@ICLOUD.COM

STRAWN OILFIELD SERVICES: DIVISION OF EVERFLOW EASTERN PARTNERS, LP 29093 S.R. 62, SALEM, OH 44460

GEORGE STRAWN II, FIELD MANAGER: 330-537-3863 (OFFICE), 330-727-1614 (CELL) GSTRAWN59@GMAIL.COM

# DOMINION ENERGY SERVICES, INC.

320 SPRINGSIDE DRIVE, SUITE 320, AKRON, OH 44333; 330-664-2783; 1-800-362-7557

# OHIO EDISON

1910 W. MARKET ST., BLDG 1, AKRON, OH 44313;
MICHAEL JANSON, ENGINEERING SERVICES, 330-830-7092

ALL ELEVATIONS, EX. UTILITIES AND STRUCTURES PROVIDED IN THE EXISTING CONDITIONS PLAN (SHEETS 5-6) ARE BASED ON A SURVEY PROVIDED BY:

GPD GROUP, 520 SOUTH MAIN STREET, SUITE 2531, AKRON OHIO 44311; (330)-572-2100

ADDITIONAL SURVEY DATA WAS PREVIOUSLY OBTAINED BY ENVIRONMENTAL DESIGN GROUP

THE METRO PARKS REPRESENTATIVE AND METRO PARKS ASSUME NO RESPONSIBILITY AS TO THE ACCURACY OF THE UNDERGROUND FACILITIES SHOWN

CONTRACTOR SHALL MAINTAIN ACCESS TO THE EXISTING GAS AND OIL WELLS THROUGHOUT CONSTRUCTION.

# DOMINION ENERGY OHIO:

IF DETERMINED NECESSARY BY SUMMIT METRO PARKS OR DOMINION EAST OHIO. THE DOMINION GAS LINE WILL BE PHYSICALLY LOCATED, BOTH HORIZONTALLY AND VERTICALLY PRIOR TO CONSTRUCTION. THE HORIZONTAL AND VERTICAL LOCATION OF THE DOMINION GAS LINE SHOWN ON THE PLANS IS BASED ON POINTS WHERE DEPTH OF PIPE WAS RECORDED BY DOMINION ENERGY. DEPTHS WERE TAKEN WITH A FIBERGLASS PROBE AND WERE MEASURED TO THE TOP OF PIPE. SEE SUPPLEMENTAL DRAWINGS FOR THE DIRECTIONAL DRILL PLANS FOR THE EXISTING 12" PIPELINE AND ARANDONED PIPELINE

IT IS THE CONTRACTOR'S RESPONSIBILITY TO MAINTAIN THE LATERAL AND SUBJACENT SUPPORT OF DOMINION ENERGY'S PIPELINE(S), IN COMPLIANCE TO 29 CFR, PART 1926, SUBPART P, (SAFE EXCAVATION& SHORING). ONE—FOOT MINIMUM VERTICAL AND HORIZONTAL CLEARANCE MUST BE MAINTAINED BETWEEN DOMINION ENERGY OHIO'S (DEO) EXISTING PIPELINE(S) AND ALL OTHER IMPROVEMENTS. EXTREME CARE SHOULD BE TAKEN NOT TO HARM ANY DEO FACILITY (PIPELINES, ETC.) OR APPURTENANCE (PIPE COATING, TRACER WIRE, CATHODIC PROTECTION TEST STATION WIRES & DEVICES, VALVE BOXES, ETC.) DEO FACILITIES MUST BE PROTECTED WITH A TARP DURING BRIDGE CONSTRUCTION. THE CONTRACTOR WILL BE RESPONSIBLE AND LIABLE FOR ENSURING THAT ALL DEO EXISTING FACILITIES, ABOVE AND BELOW GROUND, REMAIN UNDAMAGED, ACCESSIBLE AND IN WORKING ORDER. THE CROSSING OF DEO'S PIPELINE WITH ANOTHER STEEL FACILITY MAY CREATE A POTENTIAL CORROSION ISSUE FOR THE PROPOSED FACILITY AND THE EXISTING DEO FACILITY. PLEASE CONTACT DOMINION ENERGY OHIO'S CORROSION DEPARTMENT: DAVE CUTLIP (330–266–2121), RICK MCDONALD (330–266–2122), OR AL HUMRICHOUSER (330–478–3757).

# REMOVAL OF STRUCTURES AND OBSTRUCTIONS:

STRUCTURES, PAVEMENTS, BASE, AND OTHER ITEMS SHOWN ON THE DRAWINGS TO BE REMOVED SHALL BE REMOVED PER ODOT ITEM 202. PAVEMENT TO BE REMOVED SHALL HAVE A SMOOTH, FULL DEPTH SAW CUT. ITEMS TO BE SALVAGED FOR REUSE SHALL BE CAREFULLY REMOVED, STOCKPILED AND/OR HAULED TO A LOCATION AS DIRECTED BY METRO PARKS. COST OF PAVEMENT SAW CUT, SALVAGING, HAULING MATERIALS AND OTHER RELATED WORK SHALL BE INCLUDED IN THE PRICES FOR THE VARIOUS RELATED ITEMS.

# CLEARING AND GRUBBING:

AREAS TO BE GRADED SHALL BE CLEARED AND GRUBBED PER ODOT ITEM 201. TREE AND STUMP REMOVAL SHALL BE BID AS SEPARATE ITEMS AND ARE NOT INCLUDED IN THE CLEARING AND GRUBBING COST.

NO TREE REMOVAL WILL BE PERMITTED OUTSIDE THE LIMITS OF DISTURBANCE INDICATED ON THE PLANS UNLESS AUTHORIZED. SEE THE DEMOLITION PLAN FOR TREES REMOVED BY SUMMIT METRO PARKS. TREES WILL BE FELLED AND LEFT IN PLACE FOR THE CONTRACTOR TO RETRIEVE AS NEEDED FOR WOODY HABITAT STRUCTURES. NO ADDITIONAL TREES SHALL BE REMOVED WITHOUT CONSENT FROM SUMMIT METRO PARKS OR THEIR CONSTRUCTION REPRESENTATIVE. REMOVAL IS SUBJECT TO THREATENED AND ENDANGERED (T&E) BAT REQUIREMENTS. CLEARING MUST OCCUR AFTER SEPTEMBER 30TH PRIOR TO APRIL 1ST, OR AS SPECIFIED BY THE US FISH & WILDLIFE SERVICE (USFWS).

# EARTHWORK:

EXCAVATION, EMBANKMENT AND COMPACTION SHALL COMPLY WITH ODOT ITEM 203. ALL EARTHWORK, INCLUDING FURNISHING SUITABLE MATERIAL, NECESSARY TO ACHIEVE THE PLAN ELEVATIONS & GRADES, SHALL BE INCLUDED IN THE UNIT PRICE FOR EXCAVATION OR EMBANKMENT.

CONTRACTOR SHALL MAINTAIN UNIFORM AND POSITIVE SLOPES ON ALL GRADED SURFACES, WITH THE EXCEPTION OF THE TIER 1 AND 2 FLOODPLAINS. THE FLOOPPLAIN AREAS SHALL BE GRADED TO A FLAT ELEVATION.

EARTHWORK PERFORMED WITHIN THE SCOPE OF THIS PROJECT SHALL BE IN ACCORDANCE WITH THE GEOTECHNICAL ENGINEERING REPORT COMPLETED BY GPD GROUP, DATED MAY 22, 2019. THE CONTRACTOR SHALL BECOME FAMILIAR WITH THE EXCAVATION AND SITE PREPARATION SPECIFICATIONS DESCRIBED AND FOLLOW THEM THROUGHOUT THE WORK AT THIS SITE.

A COPY OF THE GEOTECHNICAL ENGINEERING REPORT MENTIONED ABOVE IS ATTACHED IN THE BID DOCUMENTS. ALSO INCLUDED IN THE BID DOCUMENTS ARE THE FOLLOWING GEOTECHNICAL INVESTIGATIONS PREVIOUSLY COMPLETED ON THE SITE:

SUBSURFACE EXPOLORATION REPORT: PREPARED BY PROFESSIONAL SERVICE INDUSTRIES, INC., DATED MARCH 20, 2018.

REPORT OF GEOTECHNICAL EXPLORATION: PREPARED BY SOLAR TESTING LABORATORIES, INC., DATED OCTOBER 19, 2017.

BLASTING IS NOT PERMITTED.

SUBGRADE SHALL BE APPROVED BY METRO PARKS PRIOR TO SPREADING TOPSOIL.

CONTRACTOR SHALL GRADE THE SITE TO THE ELEVATIONS SHOWN ON THE DRAWINGS. ANY EXCESS EXCAVATED MATERIAL SHALL BE SPOILED ON SITE AS DIRECTED BY METRO PARKS AND SHALL NOT BE HAULED FROM THE SITE. ALL EMBANKMENT MATERIAL SHALL BE EXCAVATED FROM THE ON-SITE BORROW AREAS SHOWN ON THE PLANS. THE SITE EARTHWORK SHALL BALANCE. THE COST OF ALL EXCAVATION, EMBANKMENT, ON-SITE BORROW AND ON-SITE SPOILS SHALL BE INCLUDED IN THE PRICE FORE THE VARIOUS RELATED ITEMS.

EXCESS SITE SOIL DISPOSED OF ON SITE SHALL BE DISPOSED OF IN AREAS IDENTIFIED ON THE PLANS. THE SOILS SHALL BE GRADED SMOOTHLY WITH A NATURAL APPEARANCE, SHALL NOT IMPEDE SURFACE DRAINAGE, AND SHALL BE CAPPED WITH TOPSOIL AND SEEDED.

### OPSOIL:

EXISTING TOPSOIL WILL BE STRIPPED AND STOCKPILED ONSITE PER ODOT ITEM 651. TOPSOIL SHALL BE RE-SPREAD (ODOT 652) TO ACHIEVE FINISH GRADE TO A DEPTH OF NO LESS THAN 5-INCHES, UNLESS SPECIFIED OTHERWISE IN THE PLANS. TIER 1 FLOODPLAIN AREAS SHALL RECEIVE TOPSOIL REPLACEMENT TO ACHIEVE FINISH GRADE. TIER 2 FLOODPLAIN AREAS SHALL NOT RECEIVE TOPSOIL REPLACEMENT. THE CONTRACTOR SHALL RECEIVE APPROVAL FROM SUMMIT METRO PARKS OR CONSTRUCTION REPRESENTATIVE THAT THE EXISTING FINISHED GRADE MATERIALS ARE SUITABLE. TIER 2 IS BEING LEFT WITHOUT TOPSOIL TO PROMOTE REFORESTATION AND LIMIT HERBACEOUS COMMUNITY GROWTH. PRIOR TO TOPSOIL INSTALLATION SUBGRADE SHALL BE DECOMPACTED TO A DEPTH OF 1 FOOT USING RIPPER ATTACHMENT. AFTER TOPSOIL INSTALLATION, AREAS SHALL BE PREPPED FOR SEED INSTALLATION USING A SKID STEER TILLER ATTACHMENT. NATIVE AND TEMPORARY SEED MIXES, AS SPECIFIED, SHALL THEN BE INSTALLED. PRIOR TO SEEDING ALL AREAS MUST BE INSPECTED AND APPROVED BY SUMMIT METRO PARKS CONSTRUCTION REPRESENTATIVE.

FOLLOWING SEED APPLICATION TOPSOILS SHALL BE PROTECTED WITH SUITABLE STRAW MULCH OR EROSION FABRIC DEEMED SUITABLE PER THE SPECIFICATIONS ON SHEET 4, TO WITHSTAND THE LEVEL OF RISK ASSOCIATED WITH POTENTIAL FLOODING, WIND OR OTHER RISK WITH THE POTENTIAL TO THREATEN TOPSOIL OR SEED VIABILITY.

TOPSOILS SHALL NOT BE COMPACTED. COMPACTED TOPSOIL OR AREAS DEEMED UNSUITABLE UPON INSPECTION SHALL BE MODIFIED TO SUITABLE GROWING CONDITIONS. TOPSOIL AND SUBGRADE MATERIAL SHOULD BE ABLE TO BE PENETRATED WITH LIGHT FORCE FROM A NORMAL SPADE SHOVEL.

### DRAINAGE:

THE CONTRACTOR SHALL MAINTAIN POSITIVE DRAINAGE BY ROUTING DRAINAGE FLOWS THAT ARE INTERRUPTED BY CONSTRUCTION.

THE CONTRACTOR SHALL NOTIFY METRO PARKS IF THE ELEVATION OF AN EXISTING CONDUIT OR EXISTING APPURTENANCE DIFFERS FROM THE PLAN ELEVATION. FIELD CHANGES TO CONDUIT SLOPE OR ELEVATIONS SHALL BE APPROVED BY METRO PARKS PRIOR TO INSTALLING THE CONDUIT.

AN NPDES PERMIT IS REQUIRED FOR THIS PROJECT. ALL CONDITIONS OF THE NPDES CONSTRUCTION STORM WATER GENERAL PERMIT SHALL BE MET DURING ALL STAGES OF CONSTRUCTION. THE LOCATION AND TIMING OF ALL EROSION AND SEDIMENT CONTROL ITEMS SHALL BE FIELD ADJUSTED TO PREVENT SIGNIFICANT IMPACT ON THE RECEIVING WATERS. IMPLEMENTATION OF THE STORM WATER POLLUTION PREVENTION PLAN SHALL CONTINUE THROUGHOUT THE DURATION OF THE PROJECT OR UNTIL SUCH TIME THAT THE UPSLOPE DISTURBED AREAS ARE STABILIZED.

EROSION CONTROL MATS SHALL BE INSTALLED WHERE STATED ON THE STORM WATER POLLUTION PREVENTION PLAN AND AS PER THE MANUFACTURER'S RECOMMENDATIONS. MATS SHALL BE MADE OF ALL NATURAL MATERIALS. MATS SHALL HAVE NETTING MADE OF JUTE YARN OR OTHER BIODEGRADABLE NATURAL FIBER. MATS CONTAINING NETS MADE WITH POLYPROPYLENE POLYMERIC PLASTIC OR OTHER NON-NATURAL MATERIALS SHALL NOT BE USED.

EROSION CONTROL ITEMS SHALL BE REMOVED BY THE CONTRACTOR AFTER ALL UPLAND AREAS HAVE BEEN STABILIZED. COST OF REMOVAL SHALL BE INCLUDED IN THE PRICE FOR THE RELATED ITEM.

# STORM SEWERS:

FIELD TILES, UNDERDRAINS, IRRIGATION LINES, AND OTHER CONDUIT 6—INCHES IN DIAMETER AND LESS, THAT ARE WITHIN THE LIMITS OF DISTURBANCE AND DISTURBED BY GRADING, SHALL BE REMOVED. THE REMOVAL IS INCIDENTAL TO EARTHWORK AND NO PAYMENT WILL BE MADE FOR THE REMOVAL OF THESE ITEMS. REMAINING SECTIONS OF FIELD TILES, UNDERDRAINS, IRRIGATION LINES, AND OTHER CONDUIT 6" IN DIAMETER AND LESS SHALL BE BE PLUGGED PER ODOT ITEM 202.

STORM SEWERS 8-INCHES AND LARGER, CATCH BASINS, AND OTHER DRAINAGE STRUCTURES TO BE REMOVED PER THE PLANS SHALL BE REMOVED PER ODOT ITEM 202. BACKFILLING AND COMPACTION SHALL BE INCLUDED IN THE COST OF THE REMOVAL OF THESE ITEMS. ADJACENT EXISTING PIPE 8" AND LARGER SHALL BE PLUGGED PER ODOT ITEM 202.

UNLESS NOTED ON THE DRAWINGS, ALL STORM SEWERS, BASIN OUTLETS AND BIO-SWALE/BASIN OUTLETS SHALL BE PVC-SD35; CORRUGATED HDPE PIPE WITH SMOOTH INTERIOR WALLS OR REINFORCED CONCRETE PIPE.

ALL STORM SEWERS SHALL BE PLACED OVER 4-INCHES OF BEDDING MATERIAL. BEDDING SHALL BE #57 CRUSHED LIMESTONE AND PLACED 12" ABOVE THE TOP OF PVC AND HDPE PIPE AND TO THE SPRING LINE OF CONCRETE PIPE.

ALL TRENCHES SHALL BE BACKFILLED AND COMPACTED. TRENCHES UNDER PAVED AREAS SHALL BE BACKFILLED WITH ODOT ITEM 304, CRUSHED LIMESTONE.

TRENCHING, BEDDING, BACKFILL AND COMPACTION SHALL BE INCLUDED IN THE COST FOR STORM SEWERS. BACKFILL MATERIAL SHALL BE PLACED IN 6-INCH LIFTS AND COMPACTED TO AT LEAST 95% OF MAXIMUM DENSITY. CARE SHALL BE TAKEN WHILE COMPACTING SUCH THAT CONDUITS, FITTINGS AND OTHER ITEMS ARE NOT DAMAGED.

# STORM SEWER TO BE ABANDONED IN PLACE

ENSURE THE PIPE IS DRY AND NOT ACTIVELY FLOWING. PLUG PIPES USING CEMENT-BASED DRY-PACK GROUT CONFORMING TO ASTM C1107, GRADE B OR C. FILL PIPES 8-INCHES DIAMETER OR SMALLER A MINIMUM OF 6-INCHES INTO THE PIPE. FOR PIPES LARGER THAN 8-INCHES PLACE GROUT A MINIMUM OF 12-INCHES INTO THE PIPE. COMMERCIALLY AVAILABLE PLUGS OR CAPS, SPECIFIC TO THE ABANDONED PIPE MATERIAL, CAN BE USED AS APPROVED BY METRO PARKS. BACKFILL PIPE ACCORDING TO GRADING PLAN ONCE COMPLETE.

# SEEDING AND MULCHING:

SEE SEEDING NOTES FOR SUPPLEMENTAL SPECIFICATIONS. AREAS SHALL BE SEEDED AND MULCHED PER ODOT 659. THE COST FOR SEEDING, MULCHING, FERTILIZATION, WATERING, INTER-SEEDING, MAINTENANCE, ETC. SHALL BE INCLUDED IN THE UNIT PRICE FOR SEEDING AND MULCHING.

SEED MIXTURES, PLANTINGS AND OTHER PROPOSED VEGETATION SHALL CONFORM TO THE SPECIFICATIONS NOTED ON THE PLANS AND NOTES, AND AS DIRECTED BY SUMMIT METRO PARKS.

# SEEDING NOTES:

THE SEED MIX SHALL BE A BLEND OF NATIVE AND TEMPORARY SEED. ALL DISTURBED AREAS, UNLESS NOTED ELSEWHERE, SHALL BE SEEDED AS PER THE PLANS AND SPECIFICATIONS. THE CONTRACTOR SHALL COORDINATE WITH SUMMIT METRO PARKS TO OBTAIN APPROVAL OF SEED MIX PRIOR TO ORDERING AND INSTALLING.

APPLICATION OF SEED IN TWO OPPOSITE DIRECTIONS TO ENSURE EVEN COVERAGE OF THE SEED AT A RATE GREATER THAN THE MANUFACTURER'S RECOMMENDATIONS.

- -RAKE SEED IN TOP 1/4-INCH OF SOIL BY DRAGGING WITH BACK SIDE OF LEAF RAKE.
- -HYDRO SEEDING METHOD MAY ALSO BE APPROVED BY THE METRO PARKS.
  -DRILL SEEDING METHOD MAY ALSO BE APPROVED BY THE METRO PARKS.
- ACCEPTABLE MULCHING METHODS:
- -APPLICATION OF STRAW BY HAND OR MECHANICAL OPERATIONS.
- -HYDRO MULCH.
- -PENN MULCH (PATCHING ONLY).

THIS ITEM SHALL INCLUDE COVER CROPS, MOWING, ADDITIONAL WATERING AS DIRECTED BY THE METRO PARKS.

SPECIALTY SEED MIXES: THE CONTRACTOR SHALL INCLUDE A COVER CROP OF OATS (AVENA SATIVA) SOWED AT A RATE OF 30-50 LBS/ACRE AS PART OF THE NATIVE SEED MIX APPLICATION, OR 100 LBS/ACRE IF USING FOR EROSION CONTROL ALONE.

# PLANTING:

THE LOCATION OF LIVE STAKE PLANTINGS SHOWN ON THE PLANS IS APPROXIMATE. LIVE STAKES SHALL BE INSTALLED BY THE CONTRACTOR AS SHOWN ON THE PLANS FOR REVIEW BY THE CONSTRUCTION REPRESENTATIVE OR METRO PARKS' LANDSCAPE ARCHITECT.

FOR ALL TREES INSTALLED AS PART OF THIS PROJECT, THE CONTRACTOR IS RESPONSIBLE FOR A 1—YEAR TREE REPLACEMENT WARRANTY. WARRANTY REPLACEMENT INSPECTION WILL BE PERFORMED BY THE SUMMIT METRO PARK WITH A CONTRACTOR'S REPRESENTATIVE 12 MONTHS FOLLOWING INSTALLATION. ANY TREES DEEMED TO BE REPLACED SHALL BE REPLACED IN KIND DURING A SUITABLE PLANTING PERIOD AT NO COST TO THE OWNER.

Summit Metro Park

 $|\mathcal{S}|$ 

 $\exists | \vec{a}$ 

# **GENERAL NOTES CON'T**

### STREAM & WETLAND RESTORATION PROJECT DESCRIPTION

THE VALLEY VIEW PHASE 2 RESTORATION PROJECT IS LOCATED WITHIN THE VALLEY VIEW AREA OF SUMMIT METRO PARKS. THE SITE, WHICH WAS PREVIOUSLY VALLEY VIEW GOLF COURSE PRIOR TO BEING PURCHASED BY SUMMIT METRO PARKS, IS LOCATED ALONG THE CUYAHOGA RIVER, DOWNSTREAM OF ITS CONFLUENCE WITH THE LITTLE CUYAHOGA RIVER, BETWEEN THE OHIO & ERIE CANAL TOWPATH TRAIL AND CUYAHOGA STREET IN AKRON, OHIO. THE PROJECT OBJECTIVES INCLUDE:

- INCREASED RIVER CAPACITY AND FLOODPLAIN RESTORATION VIA REMOVAL OF BERMS AND EXCAVATION OF A NEW FLOODPLAIN ALONG AN APPROXIMATELY 5000 LF STRETCH OF THE CUYAHOGA RIVER MAINSTEM.
- INSTALLATION OF IN-STREAM HABITAT FEATURES INCLUDING WOODY AND ROCK STRUCTURES TO IMPROVE HABITAT AND SPAWNING CONDITIONS FOR FISH.
- REFORESTATION OF APPROXIMATELY 50 ACRES OF RESTORED FLOODPLAIN AND 5000 LINEAR FEET OF THE CUYAHOGA RIVER.

### RESTORATION CONSTRUCTION GENERAL SEQUENCE

RESTORATION CONSTRUCTION WILL FOLLOW THE GENERAL SEQUENCE OF:

- SECURE NECESSARY PERMITS
- MOBILIZE;
- INSTALL EROSION AND SEDIMENT CONTROLS;
- CONSTRUCT TEMPORARY ACCESS ROADS AND STAGING AREAS; INSTALL PERIMETER SEDIMENT CONTROLS AROUND STAGING AREA;
- TREE AND VEGETATION CLEARING AND GRUBBING; VEGETATION WILL BE CLEARED DURING APPROPRIATE TIMEFRAME FROM OCTOBER 1ST TO MARCH 31ST;
- . SITE LAYOUT
- INITIATE WATER CONTROL PROCEDURES AS NECESSARY; ANY DEWATERING REQUIRED MUST BE COMPLETED IN ACCORDANCE WITH OEPA GUIDELINES FOR CONSTRUCTION STORMWATER DISCHARGE;
- STRIP AND STOCKPILE TOPSOIL TO AREAS DESIGNATED ON PLAN ONLY
- INSTALL EROSION AND SEDIMENT CONTROLS AS AREAS BECOME DISTURBED;
- BEGIN EARTHMOVING CUT AND FILL ACTIVITIES ON WETLAND AND FLOODPLAIN AREAS TO ACHIEVE SUBGRADE;
- IMPORT ROCK MATERIAL AND INSTALLATION TO ACHIEVE FINISH GRADES;
- INCORPORATE WOODY AND BOULDER HABITATS, BRUSH LAYERING, STANDING DEADWOOD, ETC. INTO PROJECT COMPONENTS;
- PLACE AND RESPREAD TOPSOIL TO FINISH GRADE;
- CONDUCT MILESTONE WALK THROUGH (SEE NOTE THIS SHEET);
- SEED (TEMPORARY AND FINAL), STABILIZE, AND INSTALL EROSION CONTROL FABRIC AND SWPPP BMP'S AS AREAS REACH FINAL GRADE OR REMAIN UNWORKED;
- INSTALL PLANTINGS AT APPROPRIATE SEASONAL TIMEFRAME;
- REMOVE TEMPORARY EROSION AND SEDIMENT CONTROLS ONCE 70% STABILIZATION OF DISTURBED AREAS HAS BEEN ACHIEVED;
- DEMOBILIZE FOLLOWING SITE APPROVAL BY METRO PARKS

### <u>PERMITS</u>

THE FOLLOWING PERMITS APPLY TO THIS PROJECT:

OHIO EPA NPDES CONSTRUCTION GENERAL PERMIT, NO. 3GC09618\*AG.

FLOODPLAIN PERMIT, CITY OF AKRON

NATIONWIDE PERMIT (NWP) 27, U.S. ARMY CORPS OF ENGINEERS (USACE).

USFWS INCIDENTAL TAKE PERMIT, #MB70957D (REFER TO SUPPLEMENTAL DRAWING FOR REQUIREMENTS).

## QUALITY ASSURANCE AND QUALITY CONTROL

FIELD OBSERVATION/CONSTRUCTION OVERSIGHT WILL BE CONDUCTED BY SUMMIT METRO PARKS CONSTRUCTION REPRESENTATIVE. A SUMMIT METRO PARKS EMPLOYEE OR ITS DESIGNATED REPRESENTATIVE SHALL BE CONSULTED WITH PRIOR TO THE CONSTRUCTION AND PLACEMENT OF RESTORATION FEATURES. CONTRACTOR SHALL COORDINATE WITH THE CONSTRUCTION REPRESENTATIVE FOR EVALUATION OF GRADING, ANY TEMPORARY STREAM CROSSINGS, SUBGRADES, SUBSTRATES INCLUDING BANK RUN, GRAVELS, COBBLES AND BOULDERS, AND ANY BOULDER AND WOODY HABITAT STRUCTURES AND PLANTINGS.

THE CONSTRUCTION REPRESENTATIVE SHALL DETERMINE THE ACCEPTABILITY OF ALL STREAM CONSTRUCTION AND ITS PROCEDURES. THERE WILL BE CONSTANT REVIEW OF ALL MATERIALS, CONSTRUCTION PRACTICES, AND THE QUALITY AND QUANTITY OF ALL PHASES OF THE RIVER RESTORATION PORTION OF THE PROJECT. THE CONSTRUCTION REPRESENTATIVE SHALL HAVE AUTHORITY TO REQUEST STREAM FEATURE ADJUSTMENTS AS MAY BE NECESSARY TO BEST MEET THE RESTORATION OBJECTIVES. EVALUATION OF CONSTRUCTED GRADES WILL DETERMINE APPROVAL. ALL RESTORATION ELEMENTS SHALL NOT BE CONSIDERED COMPLETE UNTIL APPROVED BY THE CONSTRUCTION REPRESENTATIVE.

THE CONTRACTOR SHALL PRESERVE ALL CORNERSTONES, IRON PINS, AND CONCRETE MONUMENTS, OR ANY TYPE OF LAND MONUMENT. THE CONTRACTOR SHALL HAVE ALL MONUMENTS IN THE PROXIMITY OF THE WORK REFERENCED. THE CONTRACTOR SHALL REPLACE DESTROYED OR DAMAGED MONUMENTS AND SHALL FURNISH A CERTIFICATION BY A REGISTERED SURVEYOR THAT THE MONUMENTS HAVE BEEN RESTORED.

ALL MATERIALS MUST COMPLY WITH THE SPECIFICATIONS ON THE PLANS. MATERIALS THAT DO NOT MEET THE SPECIFICATIONS SHOWN ON THE PLANS SHALL BE REMOVED FROM THE SITE BY THE CONTRACTOR AT NO COST TO METRO PARKS. SHOP DRAWINGS, TICKETS, PACKING SLIPS AND OTHER INFORMATION SHALL BE SUBMITTED TO METRO PARKS FOR REVIEW.

# WATER MANAGEMENT

THE CONTINUATION OF STREAM FLOW FROM UPSTREAM TO DOWNSTREAM BEYOND THE PROJECT LIMITS MUST BE MAINTAINED AT ALL TIMES. TEMPORARY DAMMING TO COMPLETELY STOP FLOW IS PROHIBITED. TEMPORARY DAMMING TO FACILITATE BYPASS PUMPING IS PERMITTED. CHANNEL DIVERSION IS NOT EXPECTED TO BE NECESSARY. IF NECESSARY FOR CULVERT INSTALLATION AT EXISTING FORD (SEE SHEETS 30-31), BYPASS PUMPING IS PERMITTED AS LONG AS PROPER EROSION AND SEDIMENT CONTROL BMP'S ARE FOLLOWED. MAINTAIN FLOW THROUGH EXISTING DRAINAGE INFRASTRUCTURE UNTIL RESTORATION IS COMPLETE. AN ALLOWANCE WILL BE PROVIDED FOR BYPASS PUMPING IF DEEMED NECESSARY BY THE CONTRACTOR, CONSTRUCTION REPRESENTATIVE, AND OWNER.

DRAINAGE INFRASTRUCTURE SHALL BE REMOVED OR DISABLED ACCORDING TO DEMOLITION PLAN UPON COMPLETION OF STREAMBANK, FLOODPLAIN, AND WETLAND RESTORATION.

IN RIVER WORK, SUCH AS BANK STABILIZATION ROCK INSTALLATION SHALL ATTEMPT TO MINIMIZE WORKING IN FLOWING WATER BY COFFERING OR DIVERSION OF WATER AWAY FROM THE ACTIVE WORK AREA AS MUCH AS POSSIBLE. IN RIVER WORK ASSOCIATED WITH BOULDER AND WOODY HABITAT PLACEMENT, THESE MEASURES ARE NOT NECESSARY.

# FLOODPLAIN SUBGRADE

THIS WORK SHALL INCLUDE ALL LABOR, MATERIAL, AND EQUIPMENT NECESSARY TO PRODUCE FLOODPLAIN GRADES AS DETAILED IN THE PLANS. THIS SHALL INCLUDE EARTHWORK CONSTRUCTION WITHIN THE NEW FLOODPLAIN CORRIDOR PER GRADING PLAN, AND CROSS—SECTIONS. FLOODPLAIN GRADING SHALL BE PERFORMED TO ESTABLISH STABLE EARTHEN BANK ALONG THE EXISTING STREAM BY EITHER EXCAVATION OR FILL. IF EARTHEN FILL IS NECESSARY, FILL SHALL BE PLACED IN MINIMUM 9" LOOSE LAYER LIFTS AND COMPACTED MECHANICALLY (E.G., WITH MACHINE BUCKET) FOR FLOODPLAIN CREATION. EARTHEN FILL SHALL BE COMPACTED SO THAT IT IS FIRM AND STABLE AND THERE IS NO PRESENCE OF SOIL PUMPING OR SINKING. REFER TO LIMITS OF PROPOSED FLOODPLAIN CONSTRUCTION SHOWN ON PLAN, PROFILE AND CROSS—SECTIONS. OVERCOMPACTION IS NOT DESIRABLE BECAUSE IT WILL LIMIT PLANT GROWTH AND ROOT DEVELOPMENT. IF SUBGRADES IN FLOODPLAIN AREAS ARE DEEMED TO BE OVERCOMPACTED BY CONSTRUCTION REPRESENTATIVE, THEN AREA SHALL BE SCORED BY MECHANICAL MEANS USING EXCAVATOR, DOZER OR SKID STEER TO LOOSEN SOIL PRIOR TO APPLICATION OF TOPSOIL TO ACHIEVE FINISH GRADE. THIS INCLUDES ALL HAUL ROADS THAT ARE WITHIN THE RESTORATION AREA.

THE CONTRACTOR SHALL LEAVE EXISTING BANK VEGETATION UNDISTURBED TO THE MAXIMUM EXTENT POSSIBLE. IF BANKS ARE DISTURBED TO ACCESS STREAM FOR WOODY OR BOULDER HABITAT INSTALLATIONS, THE CONTRACTOR SHALL REGRADE THE BANKS TO ITS PREVIOUS EXISTING CONDITION (INCLUDING DE-COMPACTION), REPLACE VEGETATION AND PROTECT WITH EROSION FABRIC.

# TIER 1 FLOODPLAIN

TIER 1 FLOODPLAIN IS DEFINED AS THE LOWEST TIER FLOODPLAIN. THIS AREA IS FREQUENTLY FLOODED BY 1.1-1.5 YR MAGNITUDE STORMS. SAND DEPOSITION AND DEEP FLOODWATERS ARE ANTICIPATED OVER THESE AREAS. PROTECTION OF WORK FOR BOTH SUBGRADE AND FINISH GRADES ARE REQUIRED. SEE STANDARD DETAIL SHEETS FOR INSTALLATION LOCATIONS OF EROSION FABRIC. THE CONTRACTOR WILL BE RESPONSIBLE FOR ANY LOSS OF SOIL PRIOR TO SWPPP APPROVED STABILIZATION. AREA SHALL BE SEEDED WITH BOTH ANNUAL COVER CROP OF OATS AND NATIVE FLOODPLAIN / RIPARIAN SEED MIX. TOPSOIL WILL BE REPLACED IN TIER 1 FLOODPLAIN AREAS AT A MINIMUM DEPTH OF 5-IN.

### TIER 2 FLOODPLAIN

TIER 2 FLOODPLAIN IS DEFINED AS A FLOODPLAIN AT A HIGHER ELEVATION THAN TIER 1, TYPICALLY 1.5-2.0FT HIGHER IN ELEVATION. THIS AREA WILL BE FLOODED BUT NOT AS FREQUENTLY AS TIER 1. THIS ELEVATION IS ASSOCIATED WITH ~1.5 - 2YR OR GREATER MAGNITUDE STORMS. TO PROMOTE WOODY TREE RECRUITMENT AND LIMIT COMPETITION FROM HERBACEOUS SPECIES, TOPSOIL IS NOT TO BE REPLACE ON THIS TIER. HOWEVER, A MINIMUM OF 12 INCHES OF LOOSE NON-COMPACTED SOIL SHALL REMAIN. HARDPAN OR COHESIVE CLAY LAYERS SHALL NOT BE LEFT AS FINISH GRADE. CONSULTATION WITH OWNER AND CONSTRUCTION REPRESENTATIVE IS NECESSARY TO VERIFY SUITABLE MATERIAL TO BE LEFT IN PLACE. AREA IS TO BE SEEDED WITH ANNUAL COVER CROP OF OATS AND NATIVE GRASS MIX FOR REFORESTATION.

### WETLAND GRADING

EXISTING GROUND ELEVATION MAY BE SUITABLE TO ACHIEVE FINISH GRADES PER PLAN WITH MINIMAL OR NO GRADING. IF MINOR GRADING (3 – 6 INCHES) TO CREATE MICROTOPOGRAPHY OR DEPRESSIONS WILL RESULT IN A FINAL TOPSOIL DEPTH GREATER THAN 6 INCHES WITHOUT STRIPPING, MINOR GRADING WITHOUT STRIPPING/STOCKPILING MAY BE PERFORMED. AREAS THAT REQUIRE MORE THAN MINIMAL GRADING AS DESCRIBED ABOVE SHALL FOLLOW THIS GENERAL SEQUENCE. TOPSOIL SHALL BE STRIPPED AND STOCKPILED FOR ALL PROPOSED WETLANDS THAT REQUIRED GRADING. TOPSOIL SHALL BE EVALUATED FOR APPROPRIATE CHARACTERISTICS BY ENVIRONMENTAL REPRESENTATIVE. TOPSOIL NOT SUITABLE FOR WETLAND DEVELOPMENT SHOULD BE AMENDED OR SOIL SHOULD BE IMPORTED FROM ELSEWHERE ON SITE. SUBGRADE EXCAVATION SHOULD THEN BE PERFORMED AND SUBSOIL SHOULD BE SPOILED IN APPROPRIATE LOCATIONS. FINISH GRADE ELEVATIONS SHALL BE ESTABLISHED WITH A MINIMUM OF 5 INCHES OF TOPSOIL. MICROTOPOGRAPHY, RUTS ( <0.5 FT DEPTH), AND IMPERFECTIONS IN BOTH THE SUBGRADE AND FINISH GRADES ARE DESIRABLE.

### TRASH AND DEBRIS

TRASH AND DEBRIS INCLUDING BUT NOT LIMITED TO TIRES, BROKEN CONCRETE, GLASS, METAL, AND PLASTICS SHALL BE REMOVED BY THE CONTRACTOR WHEN ENCOUNTERED. IN AREAS WHERE BROKEN CONCRETE IS ALREADY PRESENT ON STREAMBANKS AND WHERE PROPOSED BANK STABILIZATION IS PLANNED, CONCRETE SHALL BE LEFT IN PLACE IF IT IS ALREADY LOCATED AT THE CORRECT SUBGRADE ELEVATION. THE EXISTING CONCRETE SHALL THEN BE COVERED WITH IMPORTED MATERIAL TO REACH FINISHED GRADE PER THE BANK STABILIZATION SPECIFICATION. NO CONCRETE SHALL BE VISIBLE IN FINISHED GRADE.

ALL TIRES ENCOUNTERED ON SITE SHALL BE REMOVED. ALL CONCRETE CONTAINING REBAR ENCOUNTERED DURING CONSTRUCTION SHALL BE REMOVED. ALL MATERIALS SHALL BE HAULED FROM SITE AND PROPERLY DISPOSED OF BY THE CONTRACTOR. COST FOR HAULING AND DISPOSAL SHALL BE INCLUDED IN THE LUMP SUM COST FOR THE TRASH AND DEBRIS REMOVAL.

### PRECONSTRUCTION VIDEO RECORDING

THE CONTRACTOR SHALL RECORD AN AUDIOVISUAL RECORDING OF THE PROJECT LIMITS AND ADJACENT AREAS, ESPECIALLY ALONG THE EXISTING CURB NEAR THE CONSTRUCTION ENTRANCE (CUYAHOGA ST.), EXISTING CATCH BASINS/CULVERTS, AND PROPERTIES WHERE EXISTING CONDITIONS MAY BE DISTURBED. THE FILE SHALL BE OF DIGITAL FORMAT AND BE PROVIDED TO THE OWNER PRIOR TO MOBILIZATION. COST TO BE INCLUDED IN COST FOR MOBILIZATION/DEMOBILIZATION.

### RIVERBED SUBSTRATE

THE WENTWORTH SCALE IS USED TO DEFINE SUBSTRATE SIZES AS MEASURED ALONG THE MEDIAN AXIS OF THE SUBSTRATE. THE BROAD RANGES FOR SAND, GRAVEL, COBBLE AND BOULDERS ARE SHOWN IN TABLE 1 BELOW:

TABLE 1 - SUBSTRATE MATERIAL TYPE AND SIZE RANGES			
MATERIAL TYPE SIZE RANGE			
BOULDER	GREATER THAN 10 INCHES		
COBBLE	2.5 INCHES TO 10 INCHES		
GRAVEL	2 MM TO 2.5 INCHES		
SANDS	0.063 MM TO 2 MM		
SILTS AND CLAYS	LESS THAN 0.063 MM		

THE WENTWORTH SCALE MATERIAL SUB-GRADATIONS AND SIZE RANGES FOR GRAVELS AND COBBLES ARE SHOWN IN TABLE 2 BELOW:

TABLE 2 - GRAVEL AND COBBLE MATERIAL SUB-GRADATIONS AND SIZE RANGES				
MATERIAL SUB-GRADATIONS	SIZE RANGE (MM)	SIZE RANGE (INCHES)		
VERY FINE GRAVEL	2-4	0.08-0.15		
FINE GRAVEL	4-8	0.15-0.31		
MEDIUM GRAVEL	8-16	0.31-0.63		
COARSE GRAVEL	16-32	0.63-1.26		
VERY COARSE GRAVEL	32-64	1.26-2.52		
SMALL COBBLE	64-90	2.52-3.54		
MEDIUM COBBLE	90-128	3.54-5.04		
LARGE COBBLE	128-180	5.04-7.09		
VERY LARGE COBBLE	180-256	7.09-10.08		

SEE SHEET 4 FOR ROCK MATERIAL SPECIFICATIONS AND PAY ITEMS.

# PROTECTION OF WORK

IT IS NECESSARY FOR THE CONTRACTOR TO PROTECT BOTH THE WORK AREA AND THE COMPLETED WORK DURING THE CONSTRUCTION PROCESS. DUE TO THE POTENTIAL FOR LARGE FLOOD EVENTS, THE CONTRACTOR WILL BE RESPONSIBLE FOR REPAIRS BOTH SMALL AND LARGE IF WORK IS NOT ADEQUATELY PROTECTED. INSTALLED TOPSOIL, STREAMBANKS, STREAM SUBSTRATES AND PLANTED VEGETATION ARE OF PARTICULAR IMPORTANCE.


TOPSOIL SHALL BE PROTECTED UNTIL GRASS OF SUFFICIENT HEIGHT, THICKNESS AND COVERAGE IS PRESENT TO MEET SWPPP SPECIFICATIONS AND PROTECT TOPSOIL FROM WASHING AWAY. AREAS DETERMINED TO BE AT RISK DURING CONSTRUCTION AND ARE NOT SPECIFICALLY CALLED OUT ON PLANS DUE TO PRESENCE OF SWALES, MICROTOPOGRAPHY OR SIMILAR CONDITION THAT ELEVATES RISK OF THE AREA SHOULD BE BROUGHT TO THE ATTENTION OF THE CLIENT AND/OR THE CONSTRUCTION REPRESENTATIVE TO DISCUSS APPROPRIATE PROTECTION MEASURES. FAILURE TO PROPERLY PROTECT TOPSOIL BEFORE STABILIZATION WILL REQUIRE RE—INSTALLATION OF TOPSOIL AT THE COST OF THE CONTRACTOR. IN GENERAL, ANY AREA THAT IS SUSCEPTIBLE TO FLOODING OR FLOWING WATER SHOULD BE INSPECTED AND ANY MINOR MODIFICATIONS/REPAIRS TAKEN AS PROTECTIVE MEASURES, SUCH AS ADDITIONAL STAPLING OF EROSION CONTROL BLANKETS, ARE REQUIRED AND EXPECTED. STREAMBANKS ARE IMPORTANT TO ENSURE THAT INTEGRITY AND SHAPE IS MAINTAINED. TOPSOIL AND EROSION FABRIC ASSOCIATED WITH STREAMBANKS SHOULD BE SCRUTINIZED TO ENSURE THEY ARE ADEQUATELY PROTECTED AND STABLE. TECHNIQUES SUCH AS USING ADDITIONAL STAKES/PINS/LONGER PINS ON STREAMBANK SECTIONS THAT ARE MORE SUSCEPTIBLE TO EROSIVE FORCES, SUCH AS ON AN OUTSIDE MEANDER BENDS, ARE GOOD MEASURES.

### MILESTONE WALK THROUGH

A FINAL WALK THROUGH FOR EACH MAJOR PROJECT COMPONENT WILL BE COMPLETED BY THE CONSTRUCTION REPRESENTATIVE AND SUMMIT METRO PARKS. EACH MAJOR PROJECT COMPONENT WILL BE CONSIDERED COMPLETED ONLY AFTER THE FINAL WALK THROUGH AND ANY ASSOCIATED PUNCH LIST ITEMS ARE CORRECTED AS REQUIRED PER THE DRAWINGS AND SPECIFICATIONS.

- THE MAJOR MILESTONES FOR THIS PROJECT ARE:
- EXCAVATION OF TIER 1 AND TIER 2 SUBGRADE FLOODPLAINS. EACH AREA THE CONTRACTOR HAS MOBILIZED TO PERFORM FLOODPLAIN EXCAVATION SHALL BE APPROVED BEFORE MOBILIZING TO A NEW AREA OF THE FLOODPLAIN SUCH THAT ADJUSTMENTS CAN BE MADE AS NECESSARY.
- BANK STABILIZATION ROCK INSTALLATION AREAS
- PLACEMENT AND INSTALLATION OF BOULDERS, WOODY HABITAT STRUCTURES AND ROCK SPURS. EACH AREA THE CONTRACTOR HAS MOBILIZED TO PERFORM STRUCTURES SHALL BE APPROVED BEFORE MOBILIZING TO A NEW AREA OF THE RIVER SUCH THAT ADJUSTMENTS CAN BE MADE AS NECESSARY.
- INSTALLATION OF CULVERT FOR ACCESS DRIVE AT EXISTING FORD
- FINISH GRADES OF TIER 1 FLOODPLAINS; FINISH GRADES OF TIER 2 FLOODPLAINS TO DETERMINE SUITABLE MATERIAL
- BACKWATER OXBOW CHANNEL TO EXISTING POND C (STATION 13+00)
- WETLAND OUTLET FINISHED GRADES (STATION 12+00)
- FINAL SPOIL PLACEMENT OF EXCAVATED MATERIAL

THE CONTRACTOR CAN PERFORM AREAS AT THEIR DISCRETION, BUT SHALL RECEIVE APPROVAL FROM THE OWNER PRIOR TO DEMOBILIZATION. A SURVEYOR SHOULD PROVIDE AS-BUILT ELEVATIONS UPON OR PRIOR TO WALK THROUGH APPROVAL. THREE DAYS NOTICE SHALL BE GIVEN PRIOR TO THE APPROVAL WALK THROUGH OR ANY MAJOR MILESTONE.



# **SPECIFICATIONS**

### ITEM SPEC - BANK RUN (SAND/GRAVEL) - FURNISHED AND PLACED, AS PER PLAN

AGGREGATE FOR THIS ITEM SHALL BE A NATURAL MATERIAL COMPOSED OF A MIXTURE OF HARD, DURABLE PARTICLES OR FRAGMENTS OF STONE OR GRAVEL AND SAND, SOME COBBLES, AND SMALL AMOUNTS OF SILT, CLAY OR OTHER SIMILAR BINDING MATERIAL, AND SHALL BE FREE OF EXCESSIVE OR DETRIMENTAL AMOUNTS OF CLAY, CLAY LUMPS, LOAM, ROOTS, VEGETABLE MATTER, RUBBISH, WOOD, MULCH, OR OTHER NON-STABLE MATERIALS. CONCRETE OR CRUSHED CONCRETE IN ANY FORM SHALL NOT BE USED. LIMESTONE SHALL NOT BE USED. ADDITIONAL DESCRIPTION PROVIDED BELOW. SEE TABLE 3 FOR THE APPROXIMATE BANK RUN MATERIAL COMPOSITION PER STRUCTURE TYPE.

BANK RUN MATERIAL IS DEFINED AS NON CRUSHED SAND AND GRAVEL SUBSTRATE MATERIAL WHICH SHALL BE UNWASHED/UNSORTED RAW MATERIAL FROM A LOCAL SAND & GRAVEL OPERATION WITHIN THE WATERSHED OR GEOLOGY. THIS MATERIAL IS SUITABLE FOR CHOKING AND BEDDING BOULDERS FOR BANK STABILIZATION STRUCTURES AND ROCK KEYS. IF MATERIAL IS OUTSIDE SPECIFICATIONS TOLERANCE, MATERIAL CAN BE APPROVED BY THE CONTRACTOR IN COORDINATION WITH CONSTRUCTION REPRESENTATIVE. ALTERNATIVE APPROVED MATERIAL WILL BE BIASED TOWARDS LESS FINES AND MORE COARSE MATERIAL. LIMESTONE SHALL NOT BE USED. SITE VISITS TO THE ACTUAL SAND & GRAVEL OPERATION SHOULD BE ARRANGED WITH THE CONSTRUCTION REPRESENTATIVE TO EVALUATE THE PROPOSED MIX PRIOR TO DELIVERY OF MATERIALS TO THE SITE.

### ITEM SPEC - GRAVEL/COBBLE - FURNISHED AND PLACED, AS PER PLAN

DEFINED AS A MIXTURE OF GRAVEL AND COBBLE WITH A WIDE RANGE OF DIMENSIONS/SIZES AS DETAILED BELOW. THE SIZE VARIABILITY IS PARAMOUNT TO HAVE APPROPRIATE FUNCTION AND STABILITY OF THE STRUCTURES. IT IS UP TO THE CONTRACTOR AND THE CONSTRUCTION REPRESENTATIVE TO WORK TOGETHER TO APPROVE THE APPROPRIATE GRAVEL/COBBLE MIX. SITE VISITS TO THE ACTUAL SAND & GRAVEL OPERATION SHOULD BE ARRANGED WITH THE CONSTRUCTION REPRESENTATIVE TO EVALUATE THE PROPOSED MIX PRIOR TO DELIVERY. MATERIAL SHALL BE FROM A LOCAL SAND & GRAVEL OPERATION. LIMESTONE SHALL NOT BE USED. CONCRETE OR CRUSHED CONCRETE IN ANY FORM SHALL NOT BE USED. MATERIAL RANGES FROM 2.5-INCHES TO 10-INCHES, BROKEN DOWN AS FOLLOWS:

2.5 - 4-INCHES: 40%

4 - 10-INCHES: 60%

A WELL-GRADED DISTRIBUTION OF GRAVEL AND COBBLE SHOULD CONTAIN THE PERCENTAGE RANGE FOR EACH MATERIAL SUB-GRADATION RANGE LISTED IN TABLE 3 BELOW:

TABLE 3 - MATERIAL SI	TABLE 3 - MATERIAL SUB-GRADATION RANGE: ODOT SIZING						
STRUCTURE ID BANK RUN COBBLE/GRAVEL TYPE A+ TYPE A TYPE B TYPE C							TYPE D
BOULDER HABITAT	SEE DETAIL SHEET 34 FOR GRADATION OF EACH BOULDER HABITAT						
ROCK KEYS*	5% 5% 45% 45%						
BANK STABILIZATION*/ ROCK TOE PROTECTION*	5%	5%		25%	45%	20%	
ROCK SPUR*	10%			25%	30%	20%	15%
ROCK LINED WETLAND OUTLET (ROCK MAT)* 5% 5% 25% 45% 20%							

\* ALL ROCK KEYS, BANK STABILIZATION/ROCK TOE, AND ROCK SPURS SHALL BE CHOKED WITH APPROPRIATE MATERIALS. USE A MIXTURE OF BANK RUN AND COBBLE/GRAVEL TO FILL VOIDS IN ROCK KEYS, ROCK SPURS, AND BANK STABILIZATION/ROCK TOE PROTECTION STRUCTURES BELOW THE ORDINARY HIGH WATER MARK (OHWM). ABOVE THE OHWM SOIL CAN BE USED TO FILL/CHOKE VOIDS AND TO HELP PROMOTE VEGETATION.

PRIOR TO INSTALLATION THIS MIX WILL BE VERIFIED BY THE CONSTRUCTION REPRESENTATIVE AT THE SUPPLIERS PLACE OF OPERATION OR ON-SITE BY PERFORMING A RANDOM PARTICLE ANALYSIS ON THE PROPOSED MIX BY SPREADING THE MIX OUT ON A 10 FT BY 25 FT AREA.

## ITEM SPEC - BOULDER MATERIAL - FURNISHED AND PLACED, AS PER PLAN

DEFINED AS ANGULAR IN SHAPE AND COMPRISED OF SANDSTONE, GRANITE, OR SIMILAR HARD MATERIAL. LIMESTONE IS PERMITTED ONLY IF NOT VISIBLE AND TOPPED BY OTHER MATERIAL. FRIABLE MATERIAL OR LOW QUALITY SANDSTONE IS NOT ACCEPTABLE. CONCRETE OR CRUSHED CONCRETE IN ANY FORM SHALL NOT BE USED IN THE FINISHED GRADE MATERIALS OR IMPORTED TO THE SITE. ANGULAR MATERIAL IS PREFERRED BECAUSE IT INCREASES THE INTERLOCKING ABILITY OF THE STONE AND IS LESS LIKELY TO ROLL OR MOVE. MATERIAL SHALL BE FROM A LOCAL SAND & GRAVEL OPERATION.

BOULDERS ARE SUITABLE FOR SPECIFIC HABITAT. BANK STABILIZATION. ROCK KEY AND ROCK SPUR STRUCTURES OR STRATEGICALLY POSITIONED ON THE RIFFLE, RUN OR POOL AREAS TO FUNCTION AS ROUGHNESS ELEMENTS. BOULDERS ARE MEASURED ACROSS THEIR MEDIAN AXIS. LIMESTONE CAN BE USED IN STREAMBED AREAS AS WELL AS ROCK CHANNEL PROTECTION AROUND CULVERTS AND SCOUR POOLS, AS LONG AS IT IS NOT VISIBLE ABOVE BASE FLOW WATER ELEVATION. OTHERWISE MUST BE TOPPED BY NATIVE SANDSTONE, SUBSTRATE OR GRANITE MATERIAL OTHER MATERIAL.

TABLE 4: BOULDER SIZES: ODOT ITEM 601		
TYPE	SIZE RANGE (INCHES)	
TYPE A	18" TO 30"	
TYPE B	12" TO 24"	
TYPE C	6" TO 18"	
TYPE D	3" TO 12"	

# TEMPORARY STABILIZATION AND NATIVE SEED INSTALLATION

GRAIN RYE (Secale cereale) OR OATS (Avena sativa) AT A RATE OF 30-50 LBS PER ACRE SHALL BE INSTALLED TO ALL DISTURBED AREAS (OR 100 LBS/ACRE IF USING FOR EROSION CONTROL ALONE). NATIVE SEED MIXES ARE TO BE INSTALLED AT THE SPECIFIED RATE IN THE APPROPRIATE AREAS (REFER TO THE PLANTING PLAN SHEETS 36 THROUGH 39). ALL NATIVE SEED IS TO BE INSTALLED BY HAND SEEDING METHOD DUE TO VARIABILTY OF SEEDS WITHIN MIX. CONTRACTOR IS TO ESTIMATE SEEDING AREA AND WEIGH SEED IN APPROPRIATE QUANTITIES TO ENSURE APPLICATION AT THE CORRECT RATE. A STARTER FERTILIZER IS NOT REQUIRED UNLESS SITE-SPECIFIC SOIL TESTS DEEM A DEFICIENCY IN ONE OR MORE SOIL COMPONENTS. AT THAT TIME, A FERTILIZER RATE WILL BE APPLIED AS NECESSARY TO PROMOTE A HEALTHY NATIVE COMMUNITY. FOLLOWING TEMPORARY AND NATIVE SEED INSTALLATION, SEED IS TO BE LIGHTLY RAKED INTO SOIL. COVER SOIL WITH APPROPRIATE EROSION PROTECTION PER AREA.

# ITEM SPEC - EROSION CONTROL FABRIC FOR GENERAL PURPOSE - STRAW FABRIC, AS PER PLAN

FABRIC FOR GENERAL EROSION CONTROL SHALL BE AMERICAN EXCELSIOR COMPANY STRAW-COCONUT FIBRENET OR APPROVED EQUAL, FOR FLOW RATES UP TO 6.0 FPS AND SHEAR STRESS OF 1.85 LBS/SQ FT. MATS SHALL BE MADE OF ALL-NATURAL MATERIALS. MATS SHALL HAVE NETTING MADE OF JUT YARN OR OTHER BIODEGRADABLE NATURAL FIBER. MATS CONTAINING NETS MADE WITH POLYPROPYLENE, POLYMERIC PLASTIC, OR OTHER NON-NATURAL MATERIALS SHALL NOT BE USED. THIS FABRIC SHALL BE USED ON CUT SLOPES ABOVE THE FLOODPRONE AREAS TO CONTROL POTENTIAL EROSION AREAS THAT DO NOT HAVE CONCENTRATED FLOW, SUCH AS THE FLOODPLAIN TIER 1 AREAS. SEE THE STORMWATER POLLUTION PREVENTION PLAN AND STANDARD DETAIL SHEETS FOR LOCATION AND INSTALLATION OF EROSION FABRIC.

PRIOR TO INSTALLATION, THE AREA UNDER THE FABRIC SHALL BE SEEDED AS DESCRIBED IN NOTE 4 ABOVE. ALL OTHER AREAS SHALL BE SEEDED AND MULCHED, STANDARD REVEGETATION. EROSION FABRIC SHALL BE INSTALLED PER THE MANUFACTURERS INSTRUCTIONS AND IN ACCORDANCE WITH ODOT ITEM 671.

# <u>ITEM SPEC - TEMPORARY STREAM CROSSING</u>

THREE LOCATIONS HAVE BEEN IDENTIFIED ON THE PLANS FOR TEMPORARY STREAM CROSSINGS. THE CONTRACTOR SHALL PROTECT SURROUNDING AREAS FROM SCOUR, AND SHOULD ANY SCOUR OCCUR IT MUST BE RESTORED TO ORIGINAL GRADE AT THE CONTRACTOR'S EXPENSE. THESE ARE PERMITTED AREAS WITH THE USACE AS LOCATIONS WHERE CONSTRUCTION EQUIPMENT WILL CROSS THE STREAM THE CONTRACTOR SHALL CONSTRUCT A STABLE CROSSING FROM ONE OF TWO OPTIONS.

TIMBERMAT CROSSING: USING VARIOUS COMBINATIONS AND CONFIGURATIONS OF TIMBERMATS PLACED PARALLEL AND ACROSS CHANNELS CAN BE USED AS A CROSSING(S). A SUITABLE ROCK MATTRESS CAN BE USED AS A FOUNDATION.

STEEL PIPE / ROCK CROSSING: A ROCK MATTRESS ROCK CHANNEL PROTECTION TO PROTECT THE STREAM BED AND BANKS. MATERIAL SHALL CONSIST OF NATURAL RIVER ROCK FROM SAME APPROVED AGGREGATE SOURCE FOR PROJECT. INSTALL TEMPORARY CULVERT PIPING IN ACCORDANCE WITH THE STANDARD TEMPORARY STREAM CROSSING DETAIL. UPON COMPLETION OF WORK, THE CONTRACTOR SHALL REMOVE PIPING AND REUSE AS APPROVED BY THE CONSTRUCTION REPRESENTATIVE OR REMOVE MATERIAL FROM THE PROJECT SITE.

ALL LABOR. EQUIPMENT AND MATERIAL FOR THE THREE IDENTIFIED STREAM CROSSINGS SHALL BE INCLUDED IN THE LUMP SUMP COST FOR THE SPECIAL ITEM TEMPORARY STREAM CROSSINGS.

### 7. POND IN-FILL AND COMPACTION

ALL EXISTING PONDS PROPOSED FOR FILL ACTIVITIES SHALL BE IN-FILLED AND GRADED IN A DRAINED DOWN CONDITION. WATER SHALL BE PUMPED FROM THE PONDS INTO AN ADJACENT WETLAND OR AS DIRECTED BY SUMMIT METRO PARKS OR THEIR CONSTRUCTION REPRESENTATIVE. WATER SHALL NOT BE PUMPED DIRECTLY INTO THE CUYAHOGA RIVER. SOILS SHOULD BE PLACED INTO THE PONDS TO WITHIN +/- 6 INCHES FROM THE SPECIFIED FINISHED GRADE FILL ELEVATION. THE VARIABILITY OF THE FILL HEIGHT TO THE TOP OF THE PONDS WILL BE INSPECTED AND APPROVED BY SUMMIT METRO PARKS OR THEIR CONSTRUCTION REPRESENTATIVE.

GROUNDWATER SEEPAGE SHALL BE MAINTAINED DURING FILL ACTIVITIES TO ENSURE PROPER COMPACTION. A COMPACTION STANDARD IS NOT REQUIRED OTHER THAN PLACED FILL BEING ABLE TO SUPPORT WEIGHT OF NECESSARY CONSTRUCTION EQUIPMENT AND THAT FILL AREAS DO NOT POSE A HAZARD TO ANYONE OR WILDLIFE DUE TO IMPROPER COMPACTION LEADING TO SINKING/ENTRAPMENT. TYPICAL COMPACTION USING 6-9 INCH LIFTS WILL HELP ENSURE THIS GOAL IS ACHIEVED BUT CONTRACTOR SHOULD KEEP IN MIND THIS IS TO ACHIEVE A NATURAL COMPACTION AND NOT FOR A BUILDING FOUNDATION. OVER COMPACTION IS NOT DESIRED SUCH THAT PLANTS GROWTH IS INHIBITED. IN PARTICULAR THE TOP 2-3FT OF SOIL SHOULD NOT BE OVER COMPACTED AND REMAIN LOOSE ENOUGH SUCH THAT A NORMAL SHOVEL SPADE CAN BE FULLY DEPRESSED UNDER THE WEIGHT OF AN AVERAGE PERSON. MICROTOPOGRAPHY AND VARIABLE FINISHED GRADE IS DESIRABLE.

# 8. BOULDER HABITATS (#1 – #10)

BOULDERS SHALL BE INSTALLED ACCORDING TO THE SPECIFICATIONS AND DETAILS BY NUMBERS (1-10) REFERENCED IN SHEET 34. BOULDER HABITATS ARE DESIGNED TO PROVIDE FISH AND MACROINVERTEBRATE HABITAT THROUGH FLOW VARIABILITY, LOCALIZED SCOUR AND IMPROVED SUBSTRATE STABILITY. THE LARGEST BOULDER CALLED OUT IN THE HABITAT DETAIL SHALL BE INSTALLED UPSTREAM OF THE OTHER BOULDERS. BOULDER HABITATS CAN VARY SLIGHTLY FROM THE ORIENTATION DETAIL BUT THE NUMBER AND SIZE CLASSES SHOULD REMAIN CONSISTENT.

THE COST FOR THIS ITEM IS INCLUDED UNDER ITEM SPEC - BOULDER MATERIAL.

THE CONTRACTOR SHALL ONLY USE ACCESS PATHS AND TEMPORARY CROSSING LOCATIONS IDENTIFIED IN THE PLANS TO ACCESS THE BOULDER HABITAT LOCATIONS.

### 9. <u>ITEM SPEC - WOODY HABITATS (#1 - #6)</u>

WOODY HABITATS ARE DESIGNED TO ENHANCE THE FISH AND MACROINVERTEBRATE HABITAT AS WELL AS PROVIDE BANK PROTECTION WHERE APPLICABLE. EACH HABITAT HAS A DIFFERENT INSTALLATION METHOD AND PURPOSE DETAILED IN SHEET 33. WOOD SELECTION IS IMPORTANT TO ENSURE THAT THE WOODY HABITAT FUNCTIONS AS INTENDED AND DOES NOT ADVERSELY AFFECT THE RIVER CURRENTS. IMPORTANT POINTS FOR WOOD SELECTION INCLUDE THE DIAMETER OF WOOD AND THE UNIQUE CHARACTERISTICS/VARIABILITY OF THE PIECE.

PRIOR TO INSTALLATION, EACH SITE SHOULD BE EVALUATED WITH RESPECT TO WATER DEPTH, INSTALLATION ANGLE, LOCAL CURRENT VELOCITIES/DIRECTION, AND STREAMBANK COMPOSITION AT THE TIME OF INSTALLATION TO FINALIZE THE DETAILS OF WOOD SELECTION. IT IS VERY IMPORTANT FOR THESE HABITAT STRUCTURES TO BE FUNCTIONAL AS HABITAT. THEREFORE, A MAJORITY IF NOT ALL THE WOOD DEPENDING ON HABITAT TYPE SHALL BE SUBMERGED DURING BASE FLOW. ANCHORING THE WOOD IS VERY IMPORTANT AND METHODS ARE OUTLINED IN EACH DETAIL FOR ANCHORING.

THE WOOD SHALL ONLY BE NATURAL MATERIAL FROM DOWNED TREES HARVESTED AT THE SITE OR FROM A LOCAL SOURCE WITHIN SUMMIT COUNTY. UNDER NO CIRCUMSTANCE SHALL 2'X4'S, TREATED OR UNTREATED PROCESSED LUMBER BE USED FOR ANY WOODY MATERIAL OR WOODY PINS. IN ADDITION TO WOODY PINS AND PARTIALLY BURYING LOGS, SUPPLEMENTAL BOULDERS CAN BE USED TO HELP HOLD WOOD IN PLACE.

FINAL LOCATION, AND PLACEMENT/ORIENTATION OF WOODY HABITAT STRUCTURES ARE TO BE COORDINATED AND APPROVED WITH THE CONSTRUCTION REPRESENTATIVE OR SUMMIT METRO PARKS.

THIS ITEM SHALL INCLUDE LABOR, EQUIPMENT AND MATERIALS TO CONSTRUCT WOODY HABITAT STRUCTURES AS PER PLAN. THE CONTRACTOR SHALL ONLY USE ACCESS PATHS AND TEMPORARY CROSSING LOCATIONS IDENTIFIED IN THE PLANS TO ACCESS THE WOODY HABITAT LOCATIONS.

# 10. ROCK SPUR HABITAT

ROCK SPUR HABITAT IS A FEATURE THAT IS DESIGNED TO AFFECT BASE AND SMALLER FLOOD FLOW EVENTS TO CREATE FLOW VARIABILITY, LOCALIZED SCOUR AND PROTECTED BACKWATER HABITATS. THE ORIENTATION ANGLE, SLOPE OF ROCK, ROCK COMPOSITION AND HEIGHT OF THE ROCK ARE THE IMPORTANT INSTALLATION FACTORS. THE ORIENTATION ANGLE IS EVALUATED WITH RESPECT TO THE STREAMBANK. ROCK SPUR ANGLE SHALL BE IN THE RANGE OF 20-30 DEGREES FROM PERPENDICULAR TO THE STREAMBANK IN AN UPSTREAM ORIENTATION. THIS IS DESIGNED TO MOVE FLOW AWAY FROM THE STREAMBANK. THE SLOPE OF THE ROCK FROM THE BASE TO THE END SHALL BE IN THE RANGE OF 3-5% AND SHALL BE CALCULATED AT THE SITE OF INSTALLATION AND VERIFIED VIA SURVEY. SEE DETAIL ON SHEET 34 FOR SPECIFICATIONS ON LENGTH. WIDTH AND ROCK COMPOSITION. LIMESTONE CAN BE USED IN THE SUBGRADE COMPOSITION.

THE COST FOR THIS ITEM IS INCLUDED UNDER ITEM SPEC - BOULDER MATERIAL

THE CONTRACTOR SHALL ONLY USE ACCESS PATHS AND TEMPORARY CROSSING LOCATIONS IDENTIFIED IN THE PLANS TO

# ACCESS THE ROCK SPUR HABITAT LOCATIONS.

# 11. BANK STABILIZATION

BANK STABILIZATION ARE AREAS WHERE ANGULAR BOULDERS AND RIP-RAP ARE NEEDED DUE TO EROSION AND BANK INSTABILITY. BANK STABILIZATION INSTALLATION SHALL BEGIN FROM THE LOWEST ELEVATION AND PROGRESS UPWARD IN ELEVATION. A FOUNDATION TOE SHALL BE INSTALLED TO PROTECT AGAINST SCOUR. THE TOE SHALL BE THE FURTHEST LIMIT OF ROCK IDENTIFIED ON PLANS AND CONSIST OF THE LARGEST DIAMETER MATERIAL IN THE IDENTIFIED SIZE CLASS.

ONCE THE FOUNDATION TOE IS ESTABLISHED THE BANK STABILIZATION SHALL PROGRESS IN LIFTS EQUAL TO THE C AXIS OR "LAYING" AXIS OF THE MATERIAL SPECIFIED. IN BETWEEN LIFTS IT IS VERY IMPORTANT TO CHOKE VOIDS AND SPACES WITH BANK RUN & SAND AND GRAVEL MATERIAL, INCLUDING CAREFULLY CHOKING MATERIAL UNDERWATER . THIS MATERIAL CAN CONSIST OF APPROVED ON-SITE MATERIAL ENCOUNTERED DURING EXCAVATIONS. WORK WILL NOT BE CONSIDERED ACCEPTABLE IF VOIDS AND SPACES ARE NOT FILLED DURING INSTALLATION IN LIFTS. SAND AND GRAVEL MATERIAL ONLY SHALL BE USED AS CHOKE MATERIAL TO THE BANKFULL ELEVATION AT THE CORRESPONDING STATION OF WORK. CHOKE MATERIAL ABOVE BANKFULL ELEVATION IF APPLICABLE CAN USE APPROVED SUBSOIL OR TOPSOIL.

THE FINISH GRADE APPEARANCE OF ALL BANK STABILIZATION AREAS SHALL BE NATURAL DURABLE SANDSTONE, GRANITE, DOLOMITE ETC. OTHER THAN LIMESTONE. LIMESTONE OF MATCHING SUFFICIENT BOULDER SIZE CAN BE USED IN THE SUBGRADE, KEYS, FOUNDATION TOE OR FULLY SUBMERGED AREAS WITH NO POSSIBILITY OF EXPOSURE.

THE START AND END POINTS OF BANK STABILIZATION AREAS SHALL BE BLENDED INTO THE EXISTING GRADES SO THAT ROCK MATERIAL IS FLUSH TO THE ADJACENT EXISTING BANK. THESE TIE IN LOCATIONS TO EXISTING GRADE SHALL BE COORDINATED AND APPROVED BY THE CONSTRUCTION REPRESENTATIVE.

WOODY HABITAT #1 IS OFTEN IDENTIFIED IN BANK STABILIZATION AREAS. WOODY HABITAT SHALL BE INTEGRATED INTO THE BANK STABILIZATION LIFTS. THE FINISHED LOCATION OF THE WOODY HABITAT SHALL BE IN FRONT OF THE BANK STABILIZATION ROCK BUT ANCHORED INTO THE LIFTS OF STABILIZATION ROCK. NON-FUNCTIONAL WOOD COMPLETELY BURIED BY ROCK OR NOT INSTALLED PROPERLY IS NOT ACCEPTABLE. WOODY HABITAT FEATURES ARE PAID FOR SEPARATELY FROM THE BANK STABILIZATION ITEMS.

ROCK KEYS ARE VANES OF ROCK 4-FT WIDE BY 4-FT IN DEPTH DESIGNED TO PREVENT FLANKING OF BANK STABILIZATION AND/OR OTHER STRUCTURES OR STREAM GEOMETRY. ROCK KEYS ARE TO FOLLOW THE EXISTING OR PROPOSED TOPOGRAPHY IN THE AREA. THEREFORE THE 4FT DEPTH WILL BE FROM FINISH OR EXISTING GRADE. FOR EXAMPLE IF THE STREAMBANK SLOPES UPWARD THEN THE ROCK KEY WILL SLOPE CORRESPONDINGLY SLOPE UPWARD. LIMESTONE CAN BE USED FOR ROCK KEYS BECAUSE THE MATERIAL IS BURIED. IF KEY MATERIAL WILL BE VISUALLY EXPOSED THEN SANDSTONE OR NON-LIMESTONE MATERIAL SHALL BE USED.

# 13. <u>ITEM SPEC - PLANTING LIVE STAKES, AS PER PLAN</u>

SEE SHEETS 36-37 FOR LIVE STAKE INSTALLATION NOTES, LOCATIONS, SPECIES, QUANTITIES AND PLANTING METHODS. SEE LIVE STAKE PLANTING DETAIL AND INSTALLATION SPECIFICATIONS ON SHEET 34.

# 14. ITEM SPEC - PLANTING TREES, 3 GAL CONTAINER WITH PROTECTION, AS PER PLAN

SEE SHEETS 36-37 FOR TREE INSTALLATION NOTES, LOCATIONS, SPECIES, QUANTITIES AND PLANTING METHODS. SEE THE PLANTING PLAN TO DETERMINE WHICH TREES SHALL BE INSTALLED WITH PROTECTION, SEE DETAIL ON SHEET 35.

# 15. <u>TEMPORARY CONSTRUCTION FENCING</u>

THE CONTRACTOR SHALL INSTALL TEMPORARY CONSTRUCTION FENCING AS SHOWN IN THE PLANS. THIS ITEM INCLUDED IN THE COST FOR TEMPORARY SOIL EROSION & SEDIMENT CONTROL AND INCLUDES LABOR, EQUIPMENT AND MATERIAL TO FURNISH AND INSTALL TEMPORARY ORANGE CONSTRUCTION FENCING TO PROTECT TREES OR AREAS NOT TO BE DISTURBED. SEE SWPPP, SHEETS 41-42 FOR PROPOSED LOCATIONS. SEE DETAIL ON SHEET 44.


# **LEGEND**


	EX BOLLARD	V/////	PAVEMENT TO
	EX SIGN	<u> </u>	BE REMOVED EX TREES TO
	EX CATCH BASIN		BE REMOVED
	EX MANHOLE (STM		LIMITS OF DISTURBANCE PROTECTION FENCE
V	WAT OR SAN) EX HYDRANT	⟨C1⟩	CURVE DATA
0	IP/DRILL HOLE SET	501)	COORDINATE POINT
©	IP/DRILL FND		PROP CONTOUR 1'
Δ	, HUB SET	780	PROP CONTOUR 5'
Τ	EXIST GUY WIRE	19.12	PROP SPOT ELEVATION
þ	EX LIGHT POLE	~	PROP SURFACE FLOW
- φ	EX POWER POLE		PROP ROCK CHANNEL PROTECTION/WETLAND OUTLET
F	EX UTILITY POLE		PROP ROCK CHECK DAM
WF	EX WELL COLLECTOR GAS LINE		PROP SILT FENCE
GG	EX GAS LINE (SALES)		PROP TIER 1 FLOODPLAIN EXPANSION
PETRO	EX GAS LINE (DEO)		PROP TIER 2 FLOODPLAIN EXPANSION
—— OHE—	EX OVER HD ELEC	<b>*</b> * *	PROP WETLAND
—— —— SAN ——	EX SANITARY SEWER	· · · · · · · ·	
— — STM —	EX STORM SEWER		PROP POND IN-FILL
— т —	EX TELEPHONE	<del></del>	PROP STORM/UNDER DRAIN TO BE REMOVED
	EX WATER LINE		EX UNDERDRAIN/FIELD TILE/IRRIGATION LINE
$\{ \cdot \}$	EX TREES		PROP BANK STABILIZATION
778	EX CONTOUR 1'		PROP ROCK KEY
	EV CONTOUR E'		
	EX CONTOUR 5'	—— — G ——	12" GAS PIPELINE
	FIELD SURVEY LIMITS	—— G ——	(DEO)
<del></del>		——————————————————————————————————————	(DEO)  PROPERTY LINE
	FIELD SURVEY LIMITS	——————————————————————————————————————	(DEO)


|||S||H H


N/A 03/


 $\geq$ 












- 1. SEE SHEETS 2 4 FOR GENERAL NOTES.
- 2. SEE SHEET 4 FOR LEGEND.
- SEE SHEETS 11-19 FOR GRADING PLANS.
- 4. SEE SHEET 20 FOR PROP. WETLAND GRADING.
- 5. SEE STANDARD DETAILS, SHEETS 33—35 FOR BANK STABILIZATION AND ROCK KEY DETAILS.
- 6. REFER TO ACTIVE EAGLE NEST PLAN IN SUPPLEMENTAL DRAWINGS FOR WORK RESTRICTIONS AND REQUIREMENTS.


Summit © letro Parks





- 1. SEE SHEETS 2 4 FOR GENERAL NOTES.
- 2. SEE SHEET 4 FOR LEGEND.
- 3. TREES DESIGNATED AS REMOVED BY OTHERS HAVE BEEN FELLED AND LEFT AT THE LOCATION SHOWN IN THE PLANS. THE CONTRACTOR SHALL RETRIEVE TREES FROM THESE LOCATIONS FOR USE IN WOODY HABITAT CREATION.
- 4. EXISTING BRIDGE, CONCRETE APPROACHES AND ABUTMENTS TO BE REMOVED PER ODOT 202.03. EXISTING PIERS TO BE REMOVED TO AN ELEVATION OF ONE FOOT BELOW PROPOSED GROUND SURFACE. ALL MATERIALS SHALL BE HAULED FROM THE SITE AND PROPERLY DISPOSED OF BY THE CONTRACTOR. COST FOR HAULING AND DISPOSAL SHALL BE INCLUDED IN THE LUMP SUM COST FOR THE BRIDGE REMOVAL.
- 5. THE CONTRACTOR SHALL INSTALL ORANGE CONSTRUCTION FENCE AT THE DRIP LINE AROUND TREES TO BE SAVED. SEE THE SWPPP FOR DETAILS AND THOSE AREAS TO BE PROTECTED DURING CONSTRUCTION.


NORTH


GRAPHIC SCALE IN FEET































- 1. SEE SHEETS 2 4 FOR GENERAL NOTES.
- 2. SEE SHEET 4 FOR LEGEND.
- 3. SEE CROSS SECTION SHEETS FOR DETAILED GRADING AND PROPOSED ELEVATIONS.
- 4. SEE DETAILS, SHEETS 33-35 FOR BANK STABILIZATION AND ROCK KEY DETAILS
- CONTRACTOR SHALL PROTECT TREES NEAR WORK AREAS WITH PROTECTIVE FENCE. SEE SWPPP SHEETS FOR LOCATIONS AND DETAIL.


	PROP. WOODY HABITAT FEATURE SEE SHEETS 33-34 FOR HABITAT DETAILS.	TOTAL THIS SHEET
1	OUTSIDE MEANDER LOG/BRANCH HABITAT	0
2	SHALLOW BANK LOG HABITAT	0
3	STREAMBED SMALL LOG DEBRIS	0
4	DEADFALL AND FLOODPLAIN TREE	0
5	STANDING DEAD TREE	10
6	STREAMBED LOG/BOULDER HABITAT	0




Summit@ Aetro Parks













 SEE CROSS SECTION SHEETS, 24 – 29 FOR DETAILED GRADING.

CROSS SECTION COORDINATES						
STA.	1.6	<u> </u>	CENTER		RIGHT	
3171.	N	E	N	E	N	E
12+00	533140.57	2234169.74	533470.76	2234187.34	533559.98	2234188.01
14+00	533092.21	2234242.48	533435.57	2234382.49	533619.03	2234460.14
16+00	533094.03	2234474.28	533359.62	2234567.47	533664.94	2234682.67
18+00	533041.44	2234666.39	533311.27	2234761.18	533596.04	2234844.20
20+00	532906.29	2234752.52	533238.98	2234945.68	533397.39	2235030.44
22+00	532846.83	2234930.76	533131.73	2235114.46	533257.80	2235195.75
24+00	532762.98	2234945.23	532997.94	2235262.98	533085.50	2235352.25
26+00	532767.36	2235042.61	532834.88	2235376.96	532914.44	2235524.58
28+00	532751.57	2235038.86	532646.88	2235396.93	532525.27	2235546.33
30+00	532714.28	2234981.78	532543.38	2235233.39	532323.42	2235318.49
32+00	532622.57	2234963.34	532493.59	2235039.92	532260.39	2235178.40
34+00	532542.52	2234596.86	532344.81	2234912.96	532233.15	2235138.99
36+00	532316.70	2234502.40	532166.26	2234822.85	532085.05	2234984.62
38+00	532125.46	2234448.42	531986.41	2234735.38	531920.99	2234870.36
40+00	531822.47	2234546.61	531798.24	2234670.06	531769.35	2234817.26
42+00	531559.56	2234551.80	531601.68	2234686.73	531644.45	2234823.76
44+00	531340.03	2234619.93	531412.66	2234751.17	531485.29	2234882.42
46+00	531165.04	2234716.77	531237.67	2234848.01	531315.60	2234970.63
48+00	530996.23	2234863.69	531076.07	2234965.55	531168.60	2235083.60
50+00	530848.82	2235082.33	530951.77	2235118.70	531126.08	2235180.58
52+00	530781.18	2235306.68	530907.19	2235311.49	531102.05	2235318.94
54+00	530786.61	2235531.72	530923.03	2235509.94	531097.96	2235481.57
56+00	530806.79	2235678.11	530954.12	2235706.32	531113.97	2235736.92
58+00	530760.54	2235847.32	530884.20	2235892.38	531030.00	2235927.62








NOTES: 4. EXISTING VEGETATION ON STREAMBANKS BELOW PROPOSED FLOODPLAIN EXCAVATION 1. SEE SHEETS 2 - 4 FOR GENERAL NOTES. ELEVATIONS SHOULD REMAIN UNDISTURBED TO THE MAXIMUM EXTENT POSSIBLE. GRAPHIC SCALE IN FEET HORIZONTAL & VERTICAL 2. PROPOSED GRADES SHOWN ON THE CROSS SECTIONS ARE FINISHED GRADE ELEVATIONS. 5. REFER TO DETAIL SHEET 35 FOR BANK STABILIZATION AREAS. SEC OF 4 3. A MINIMUM OF 5" OF TOPSOIL IS REQUIRED IN TIER 1 FLOODPLAIN AREAS. NO CROSS TOPSOIL IS TO BE REPLACED IN TIER 2 FLOODPLAIN AREAS. 28+00.00 EX GRAVEL ACCESS DRIVE TO REMAIN -EX ABANDONED GAS LINE 790.0 790.0 OFF: 185.32 ELEV: 773.39 BLEND TO EXISTING \_OFF: -118.05 780.0 780.0 BLEND TO EXISTING OFF: -357.70 ELEV: 757.00 1"=20'-0" 03/23/20 BLEND TO EXISTING CUYAHOGA RIVER C/L \_\_\_\_ELEV: 756.60 - PROP. BANK OFF: -198.25 \_\_\_\_ELEV: 757.00 ALIGNMENT 770.0 STABILIZATION 2 **C**ELEV: 756.58 BLEND TO EXISTING OFF: -47.03 OFF: -205.25 OFF: -350.64 ELEV: 754.25 ELEV: 754.25 ELEV: 753.19 760. OFF: -85.57 OFF: 34.74 ELEV: 753.19 740.0 PROP. TIER 1 - PROP. TIER 2 EX GRAVEL ACCESS DRIVE TO FLOODPLAIN \_ FLOODPLAIN BE REMOVED -OFF: 20.84 730.0 \_\_\_ELEV: 745.22 N/A -370 -360 -350 -340 -330 -320 -310 -300 -290 -280 -270 -260 -250 -240 -230 -220 -210 -200 -190 -180 -170 -160 -150 -110 -100 -90 -80 -70 -60 -50 -40 -30 -20 -10 0 1020 30 40 50 70 80 90 100 110 120 130 140 150 160 170 180 190 ( 30+00.00 790.0 EX ABANDONED GAS LINE: CONSTRUCTION OFF: 116.44 PROP. TIER 1 ACCESS ROAD -ELEV: 750.21' OFF: 60.00 FELEV: 764.00 780.0 FLOODPLAIN -ELEV: 757.98 7' COVER FROM EX OFF: 70.98 CUYAHOGA RIVER C/L 4.5' COVER FROM PROP -ELEV: 757.98 OFF: 125.78 ALIGNMENT BLEND TO EXISTING OFF: -227.45\_ √ELEV: 764.00 OFF: 47.27 770.0 OFF: -75.50 ELEV: 753.74 ELEV: 754.50 ELEV: 756.96 OFF: -220.07 \_\_ ELEV: 754.50 OFF: -48.36 760.0 \_\_\_ELEV: 753.26 OFF: 195.94 OFF: -71.78 \_\_ELEV: 764.50 PROP. TIER 2 ELEV: 753.26 EX ABANDONED GAS LINE 740.0 FLOODPLAIN 🚽 – EX ABANDONED GAS LINE: OFF: 95.03 ELEV: 747.73' \_\_\_ELEV: 749.38 9' COVER FROM EX 730.0 5' COVER FROM PROP DESIGN -300 -290 -280 -270 -260 -250 -240 -230 -220 -210 -200 -190 -180 -170 -160 -150 -140 -130 -120 -110 -100 -90 -80 -70 -60 -50 -40 -30 -20 -10 0 10 20 30 90 100 110 120 130 140 150 160 170 180 190 200 210 220 230 PARKS PROP. TIER 1 FLOODPLAIN 32+00.00 METRO PA BLEND TO EXISTING
OFF: 132.16
ELEV: 760.00 BLEND TO EXISTING PROP. TIER 1 OFF: -92.96 ELEV: 757.32 CUYAHOGA RIVER C/L OFF: −50.11 ELEV: 753.48 ALIGNMENT 760.0 - PROP. BANK STABILIZATION 3 SUMMIT VIEW PH \_OFF: 210.00 \_OFF: 244.19 OFF: 46.71 OFF: 78.07 | ELEV:| 761.00 \_\_ELEV: 764.00 ELEV: 753.48 EX ABANDONED 740.0 GAS LINE OFF: -81.44 OFF: -120.02\_ TELEV: | 753.48 ELEV: 748.74 CROSS SECTION LOCATIONS OFF: -37.82 ELEV: 748.30 EX 12" GAS PIPELINE OFF: −93.02 ✓ ELEV: 701.74 <u>-150 -140 -130 -120 -110 -100 -90 -80 -70 -60 -50 -40 -30 -20 -10</u> 34+00.00 BLEND TO EXISTING
OFF: -88.96
ELEV: 755.72 BLEND TO EXISTING OFF: 84.78 OFF: 92.56 ELEV: 756.00 \_OFF: -82.90 ∫ELEV: 753.70 OFF: 38.73 \_OFF: -44.91 ELEV: 753.70 ELEV: 753.70 \_\_ ELEV: 753.70 PROP. BANK CUYAHOGA RIVER C/L STABILIZATION 3 ALIGNMENT OFF: -359.32 EX ABANDONED GAS LINE OFF: 131.44 OFF: 146.98 0FF: 210.00\_ PROP. TIER 1 ELEV: 757.00 ELEV: 760.00 ELEV: 764.00 FLOODPLAIN \_ Summit © Metro Parks \_ELEV: 748.46 PROP. TIER 1 OFF: 140.51 OFF: 176.63 ΦFF: 235.37 \\_OFF: −31.79 ELEV: 747.13 FLOODPLAIN \_/ ELEV: 758.00 ELEV: 761.00 ELEV: 764.00 OFF: -333.82 VELEV: 701.74  $\tilde{z}$  - 370 - 360 - 350 - 340 - 330 - 320 - 310 - 300 - 290 - 280 - 270 - 260 - 250 - 240 - 230 - 220 - 210 - 200 - 190 - 160 - 150 - 140 - 130 - 120 - 110 - 100 - 90 - 80 - 70 - 60 - 50 - 40 - 30 - 20 - 10 0


1. SEE SHEETS 2 - 4 FOR GENERAL NOTES.


- 2. PROPOSED GRADES SHOWN ON THE CROSS SECTIONS ARE FINISHED GRADE ELEVATIONS.
- 3. A MINIMUM OF 5" OF TOPSOIL IS REQUIRED IN TIER 1 FLOODPLAIN AREAS. NO TOPSOIL IS TO BE REPLACED IN TIER 2 FLOODPLAIN AREAS.
- 4. EXISTING VEGETATION ON STREAMBANKS BELOW PROPOSED FLOODPLAIN EXCAVATION ELEVATIONS SHOULD REMAIN UNDISTURBED TO THE MAXIMUM EXTENT POSSIBLE.
- 5. REFER TO DETAIL SHEET 35 FOR BANK STABILIZATION AREAS.












- 1. SEE SHEETS 2 4 FOR GENERAL NOTES.
- 2. PROPOSED GRADES SHOWN ON THE CROSS SECTIONS ARE FINISHED GRADE ELEVATIONS.
- 3. A MINIMUM OF 5" OF TOPSOIL IS REQUIRED IN TIER 1 FLOODPLAIN AREAS. NO TOPSOIL IS TO BE REPLACED IN TIER 2 FLOODPLAIN AREAS.
- 4. EXISTING VEGETATION ON STREAMBANKS BELOW PROPOSED FLOODPLAIN EXCAVATION ELEVATIONS SHOULD REMAIN UNDISTURBED TO THE MAXIMUM EXTENT POSSIBLE.
- 5. REFER TO DETAIL SHEET 35 FOR BANK STABILIZATION AREAS.





PARKS


METRO PA


SUMMIT VIEW PH


> Summit@ Metro Parks
















- 1. SEE SHEETS 2 4 FOR GENERAL NOTES.
- 2. PROPOSED GRADES SHOWN ON THE CROSS SECTIONS ARE FINISHED GRADE ELEVATIONS.
- 3. A MINIMUM OF 5" OF TOPSOIL IS REQUIRED IN TIER 1 FLOODPLAIN AREAS. NO TOPSOIL IS TO BE REPLACED IN TIER 2 FLOODPLAIN AREAS.
- 4. EXISTING VEGETATION ON STREAMBANKS BELOW PROPOSED FLOODPLAIN EXCAVATION ELEVATIONS SHOULD REMAIN UNDISTURBED TO THE MAXIMUM EXTENT POSSIBLE.
- 5. REFER TO DETAIL SHEET 35 FOR BANK STABILIZATION AREAS.











20 40

GRAPHIC SCALE IN FEET
HORIZONTAL & VERTICAL


SCALE: 1"=20'-0" CROSS SECTIONS
DATE: 03/23/20 SHEET: 29 OF 44


D BY: ADH REFERENCES: N/A
BY: AW REVISIONS: 1


SUMMIT METRO PARKS VIEW PH 2 RESTORATION DESIG


O) 867-5511 VALLEY

Summit@ etro Parks











GRAPHIC SCALE IN FEET VERTICAL

- 1. SEE SHEETS 2 4 FOR GENERAL NOTES AND SPECIFICATIONS.
- 2. SEE SHEET 4 FOR LEGEND.
- 3. SEE TYPICAL ROAD SECTION DETAIL, SHEET 30.


# PROPOSED ACCESS ROAD-B: CENTERLINE CONSTRUCTION HORIZONTAL CURVE DATA

- (C1) P.I. STA. 100+61.90  $\Delta = 42^{\circ} 06' 27"$  $Dc = 51^{\circ} 30' 33"$ 
  - R = 111.23'T = 42.82'
  - L = 81.75
  - E = 7.96
- $\langle C2 \rangle$  P.I. STA. 101+75.27  $\Delta = 15^{\circ} 07' 24''$
- $Dc = 25^{\circ} 53' 57"$ R = 221.23'
- T = 29.37'L = 58.39
- E = 1.94'
- (C3) P.I. STA. 102+54.36  $\Delta = 15^{\circ} 36' 28''$  $Dc = 31^{\circ} 25' 32''$
- R = 182.32'T = 24.99'
- L = 49.67'E = 1.70'
- (C4) P.I. STA. 103+41.68  $\Delta = 53^{\circ} 31' 54''$ Dc = 63° 08' 11"
  - R = 90.75'
  - T = 45.77
  - L = 84.79'

SUMMIT VIEW PH

Summit@ letro Parks


E = 10.89



# INSTALL HABITAT TREE WITH FLOW DIRECTION SUCH THAT BRANCHES DO NOT IMPEDE FLOW. PLACE LOG AT TOE OR NEAR TOE OF STREAM. EXCAVATE SPACE SUCH THAT THE LOG IS FULLY SUBMERGED OR THE TOP OF THE LOG IS EQUAL TO BASE WATER LEVEL. LOG CAN HAVE BRANCHES OR BE A TRUNK WITHOUT BRANCHES BUT MUST BE SUBMERGED. THESE STRUCTURES PROVIDE NEAR BANK HABITAT IN RUN, POOLS AND DEEP GLIDE AREAS. STREAM BANK BANK HEIGHT VARIABLE BASE FLOW WATER SURFACE BURY HABITAT TREE $\frac{1}{3}$ TO 1 DIMENSION INTO STREAM BED SIZE LOGS APPROPRIATELY INSTALL SMALL, SMALL-MEDIUM, MEDIUM FOR STREAM SIZES FOUNDATION OF HABITAT TREE BOULDERS PLACEMENT AROUND HABITAT TREE ASSUME 8 PER TREE HABITAT TREE **WOODY HABITAT #2**

SHALLOW BANK LOG HABITAT

PROJECT TOTAL: 11



THE INTENT OF THIS HABITAT TYPE IS TO INTRODUCE MORE VARIABILITY INTO THE BASE FLOW CHANNEL USING SMALL PIECES OF WOOD. WOOD CAN RANGE FROM 5-10FT IN LENGTH BUT LESS THAN 12 INCHES IN DIAMETER. WOOD SHOULD BE PLACED IN POSITIONS THAT ACCENT THE BASE FLOW CHANNEL, CREATE SMALL LOCALIZED SCOUR, FLOW VARIABILITY, CAPTURE SEDIMENT ETC. WOOD SHALL BE PARTIALLY BURIED INTO SUBGRADE WITH SUBSTRATE AND BOULDERS INSTALLED AROUND OR AFTER FINISH GRADE IS INSTALLED. SCOUR POOLS SHALL BE EXCAVATED AT THE TIME OF INSTALLATION. POOL DEPTH SHALL BE AT LEAST 1X DIAMETER OF WOOD IN DEPTH BUT SHALL NOT EXCEED 2X DIAMETER. POOL DEPTH SHALL BE MEASURED FROM ADJACENT EXISTING STREAMBED SUBSTRATE ELEVATION. WOOD SHALL BE SECURED WITH WOODY PINS AND PARTIALLY BURIED. WOOD SHALL BE INSTALL AT AN ANGLE UPSTREAM OR PARALLEL WITH FLOW. WOOD SHALL NOT BE INSTALLED SUCH THAT IT CAUSE CURRENTS TO FLOW TOWARDS THE STREAMBANK. WOOD SHALL BE INSTALLED IN THE NEARBANK AREAS AND NOT EXCEED 25FT AWAY FROM THE NEAREST BANK. WOOD SHALL BE BURIED/INSTALLED SUCH THAT IT IS FULLY OR 80% SUBMERGED AT BASEFLOW. MULTI-STEM OR MULTIPLE PIECES OF WOOD ARE ENCOURAGED TO BE INSTALLED TO ADD VARIABILITY TO THE HABITAT.

# WOODY HABITAT #3 STREAMBED SMALL LOG DEBRIS PROJECT TOTAL: 18


# WOODY HABITAT #1 OUTSIDE MEANDER LOG/BRANCH HABITAT PROJECT TOTAL: 44

HABITAT TREE SPECIFICATIONS
TREE LENGTH 10 - 30 FT DIAMETER 6-18 INCHES HABITAT TREE SPECIFICATIONS TREE LENGTH 1 — 5X BANKFULL WIDTH WOODY PINS SECURE TREE WM SIZED BOULDERS DIAMETER 6-14 INCHES THE UPSTREAM AND WNSTREAM SIDE OF TO GROUND ON THE BOTH SIDES OF LOG (IF NECESSARY) INSTALL HABITAT TREE IN FLOODPLAIN TO BANKFULL CHANNEL MIMIC DEADFALL. PLACE AT ANGLE OR WITH DIRECTION OF FLOW. DO NOT PLACE IN A MANNER WHICH JEOPARDIZES STREAM STABILITY OR OBSTRUCTS FLOW. SECURE INSTALL HABITAT TREE IN WETLAND TO MIMIC BY ONE OF THE FOLLOWING METHODS: DEADFALL. SECURE BY ONE OF THE FOLLOWING BOULDER PLACEMENT, METHODS: CROSS STAKING, OR CROSS STAKING, OR PARTIALLY BURÝ. WOODY PINS SECURE 2. PARTIALLY BURY. TREE TO GROUND ON THE UPSTREAM AND DOWNSTREAM SIDE OF  $(\mathbf{2})$  EXCAVATE A SMALL DEPRESSION IN SUBSOIL FLOODPLAIN JUST LARGE ENOUGH TO FIT APPROXIMATELY PLAN VIEW 1/3 TO 1/2 THE LOG AND LIMBS. BACK FILL TO WOODY HABITAT ORIENTATION PARTIALLY BURY THE LOG AND TAMP LOG AND BURY HABITAT TREE  $\frac{1}{3}$ SOIL WITH EXCAVATOR BUCKET TO SECURE TO 1 DIAMETER INTO FLOODPLAIN SOIL INTO GROUND. CROSS SECTION CROSS SECTION

HABITAT TREE SPECIFICATIONS
TREE LENGTH 10 - 30 FT DIAMETER 12-24 INCHES (1) PREPARE HOLE FOR PLACEMENT OF STANDING DEAD TREE USING A EXCAVATOR OR AUGER ATTACHMENT. THE DIAMETER OF THE HOLE WILL VARY, AND THE DEPTH SHALL BE 4 - 5 FT. (2) INSTALL TREE INTO HOLE AND BACKFILL WITH SUBSOIL. COMPACT SUBSOIL USING MACHINE BUCKET, SKID PLATE TAMPER, MACHINÉ TRACKS OR COMBINATION. 4-5 FT **WOODY HABITAT #5** 

STANDING DEAD

PROJECT TOTAL: 23



# PLAN VIEW

# BANK PROFILE

THE INTENT OF THIS HABITAT TYPE IS TO CREATE MINOR SCOUR POOLS FOR BASE FLOW HABITAT VARIABILITY. WOODY DEBRIS SHOULD BE FUNCTIONAL AT BASE FLOW 100-300 CFS. SCOUR POOL MUST BE EXCAVATED WITH THE INSTALLATION. TREE SHALL CONSIST OF SOLID RECENTLY CUT OR HARD WOOD AT LENGTH OF 25-30FT WITH 10-14" DIAMETER. HABITAT TREE SHALL HAVE BRANCHES OR OTHER UNIQUE CHARACTERISTICS FOR FLOW VARIABILITY. TREE SHALL NOT BE COMPLETELY SMOOTH OR "POLE-LIKE". ROOTWAD CAN REMAIN ON THE TREE AND BE BURIED INTO THE BANK AS ADDITIONAL ANCHORING. THE SLOPE OF THE VANE SHALL BE 3-5% FROM TIP OF THE BURIED END IN THE STREAM TO WHERE IT INTERSECTS THE STREAMBANK. SLOPE IS TO BE CALCULATED AND CHECK BY SURVEY ELEVATION IN THE FIELD PER LOCATION. SLOPE OF THE VANE IS IMPORTANT FOR PROPER FUNCTION. ONCE TRENCH IS EXCAVATED AND TREE INSTALLED AT APPROPRIATE SLOPE, BACKFILL THE UPSTREAM SIDE OF THE LOG TO THE TOP OF THE TREE. THIS IS SO THE FLOW IS BREAKING ON A UNIFORM PLANE. LARGER DIAMETER MATERIAL MAY BE NECESSARY ON THE UPSTREAM SIDE OF TREE TO RETAIN SMALLER SAND AND GRAVELS. BRANCHES MAY ALSO BE USED IN CONJUNCTION WITH LARGER DIAMETER MATERIAL.

EXCAVATE A SCOUR POOL 2X THE DIAMETER THE TREE. (I.E. TREE=1FT DIAMETER, SCOUR POOL DEPTH= 2FT. THE POOL DEPTH IS MEASURED FROM BASE FLOW WATER ELEVATION. PLACE BOULDERS ON THE DOWNSTREAM SIDE OF TREE WHERE VELOCITIES WILL BE GREATEST AND IN THE SCOUR POOL.

WOODY HABITAT #6
STREAMBED LOG/BOULDER HABITAT
PROJECT TOTAL: 1


# WOODY HABITAT #4 DEADFALL AND FLOODPLAIN TREE

PROJECT TOTAL: 20

METRO PA


SUMMIT VIEW PH






# RIFFLE, RUN, GLIDE BOULDER HABITAT STREAMBED PROTRUSION DETAIL

NOTE: ALL BOULDER HABITAT TYPES SHALL BE FULLY SUBMERGED 1.5 FT MINIMUM BELOW WATER SURFACE ELEVATION IN POOL AREAS.





# **BOULDER HABITATS (1-10)**

BOULDERS HABITATS ARE TO BE PLACED PER PLAN AND AT THE DISCRETION OF THE CONSTRUCTION REPRESENTATIVE. BOULDERS SHALL BE PLACED SUCH THAT THEIR PROTRUSION HEIGHT IS LESS THAN 1/3 BANKFULL HEIGHT IN A RIFFLE. BOULDERS PLACED INTO POOL HABITATS SHALL NOT PROTRUDE MORE THAN 1FT FROM FINISH GRADE ELEVATION UNLESS OTHERWISE DIRECTED. FLAT OR ANGULAR BOULDERS ARE PREFERRED TO ROUNDED BOULDERS. BOULDERS SHALL NOT BE PLACED IN A POSITION THAT CAUSES LATERAL SCOUR INTO A STREAMBANK. BOULDERS PLACED NEAR STREAMBANKS SHALL BE AT LEAST 1.5 BOULDER DIAMETER OF EXPOSED SURFACE FROM STREAMBANK.



# **ROCK SPUR DETAIL**






WOODY PINS SHALL BE USED TO SECURE WOODY HABITATS INTO STREAMBED, STREAMBANKS AND FLOODPLAINS. AN EXCAVATOR BUCKET IS USED TO DRIVE PINS INTO KEY LOCATIONS ON THE WOODY HABITAT TO LOCK INTO PLACE. THIS COULD INCLUDE -Y'S-, BENDS OR CURVES BUT A SECOND PIN AT A MINIMUM SHOULD ALWAYS BE INSTALLED IN THE OPPOSITE DIRECTION OR ANGLE TO COUNTERACT THE FIRST PIN. IF WOODY HABITAT IS SUBJECT TO LIFTING FORCES THEN PINS PLACED HORIZONTALLY WILL HELP STABILIZE. TYPICALLY A MINIMUM OF FOUR PINS INSTALLED IN AN -X- PATTERN ARE PLACED ON A WOODY HABITAT PER 8-10FT. PINS SHALL BE INSTALLED ON PARTIALLY BURIED OR WOODY HABITATS THAT ARE TRENCHED IN PRIOR TO BEING BACKFILLED.

PINS SHALL BE MADE FROM DURABLE, RECENTLY CUT OR HARDENED WOOD. ROTTEN WOOD IS NOT PERMITTED AND TYPICALLY WILL BREAK UNDER PRESSURE OF THE MACHINE. PINS SHALL BE CUT INTO 3-6FT LENGTHS DEPENDING ON SPECIFIC NEEDS. COMMON DIAMETER OF MATERIAL IS 3-8 INCHES. A SHARPENED POINT SHALL BE CUT AT ONE END USING ONE OR MULTIPLE ANGLED CUTS. ABSOLUTELY NO PROCESSED WOOD OR LUMBER 2X4'S CUT WITH POINTS ARE PERMITTED.

\*\*\*PINS CUT FROM CERTAIN SPECIES PRESENT OPPORTUNITY TO CREATE MODIFIED LIVE STAKE POSTS. GENUS AND SPECIES IN THE FOLLOWING INCLUDING SYCAMORE, ELM, BIRCH, WILLOW, BOX ELDER AND COTTONWOOD SHOULD BE PROCESSED SUCH THAT THEPOINTED END OF THE WOODY PIN IS FACING DOWNWARD IN THE DIRECTION OF ROOT GROWTH. THIS WOULD GENERALLY MEAN THE THICKER END OF THE PIN RECEIVED THE ANGLED

# WOODY PIN DETAIL





# INSTALLATION SPECIFICATIONS


- LIVE STAKES SHALL RANGE FROM 1/2" TO 1" IN DIAMETER AND BE FROM 2 TO 3 FT IN LENGTH
- 2. CARE SHALL BE TAKEN NOT TO DAMAGE THE LIVE STAKES DURING INSTALLATION.
- 3. A PILOT HOLE WILL BE REQUIRED TO ENSURE THAT THE LIVE STAKE IS NOT DAMAGED WHEN DRIVEN THROUGH THE SUBSOIL. PILOT HOLE SHALL BE MADE THROUGH THE USE OF A STEEL SPIKE, REBAR, OR SIMILAR TOOL TO WORK AN OPENING THROUGH THE SUBSOIL.
- 4. LIVE STAKES SHALL BE CUT TO A POINT ON THE BASAL END FOR INSERTION IN THE GROUND.
- 5. SEE CONTRACT DOCUMENTS FOR SPECIES, SIZE, SPACING, LOCATION, AND FINAL DETERMINATION ON USE OF LIVE STAKES.
- 6. USE A DEAD BLOW HAMMER TO DRIVE LIVE STAKES INTO THE
- PILOT HOLE. 7. LEAVE BETWEEN 4" AND 8" OF LIVE STAKE EXPOSED ABOVE FINISH
- 8. TAMP SOIL AROUND LIVE STAKES.

GRADE.









# LEGEND:

÷ ÷ ;

WETLAND FOREST

FLOODPLAIN FOREST - TIER 1 & SLOPE TO TIER 2

(OR TO EXISTING GRADE IF NO TIER 2)

TIER 2 & SLOPES TO EXISTING GRADE

FLOODPLAIN FOREST - TIER 2 & SLOPES TO EXISTING GRADE
UPLAND FOREST

---- 1 FT. O.C. LIVE STAKES

- - 2 FT. O.C. LIVE STAKES

— 3 FT. O.C. LIVE STAKES

GRAPHIC SCALE IN FEET

O.C. LIVE STAKES

# NOTES:

- 1. TREES ARE TO BE PLANTED AT 10'-15' O.C. SEE DETAIL ON SHEET 35 FOR TREE PLANTING AND STAKING.
- 2. EACH AREA IS TO BE PLANTED AT A MINIMUM DENSITY OF 200 TREES PER ACRE.
- 3. THE CONTRACTOR SHALL BE RESPONSIBLE FOR A 1—YEAR REPLACEMENT WARRANTY OF ALL TREES PLANTED.
- 4. LIVE STAKES ALONG STREAMBANKS ARE TO BE INSTALLED AT 3 FT. O.C. IN THE STREAM BED WITH THE EXCEPTION OF AREAS IDENTIFIED ON THE PLANS TO BE INSTALLED AT A 1 FT. O.C.
- 5. LIVING DIKE LIVE STAKES ARE TO BE INSTALLED AT A 2 FT. O.C.
- 6. NO TREES ARE TO BE PLANTED WITHIN THE OVERHEAD POWER LINE EASEMENT (100 FT).
- 7. LIVESTAKES INSTALLED IN BANK STABILIZATION ROCK SHALL HAVE TWO ROWS OF 1 FT. O.C. LIVE STAKES. THE FIRST ROW SHALL BE LOCATED 1 FT. ABOVE BASE FLOW WATER SURFACE, AND THE SECOND ROW LOCATED AT THE BANKFULL ELEVATION. SEE DETAIL, SHEET 34.

NOF	RTH

ı	AO!	<b>≺</b> I	П	
	10	0		200


PLA	3.	
	SHEET:	
l"=100'-0"	5/20	
1"=10	03/23/20	
:SCALE:	DATE:	

	]		
N/A	1		
	REVISIONS:		

		ı
	DESIGN	
METRO PARKS	RESTORATION	
$\geq$	7	
1MIT	ЬН	
SUMMIT	VIEW	

975 TREATY LINE ROAD AKRON, OHIO 44313 (330) 867—5511

Summit Summit



			LEGEND:
NATIVE EMERGENT WETLAND/ MARSH SEED MI	NATIVE UPLAND MEADOW/ SAVANNAH SEED MIX	NOTES:	
PERCENT COMMON NAME SCIENTIFIC NAME	PERCENT COMMON NAME SCIENTIFIC NAME	1. EACH SPECIES MUST BE INDIGENOUS TO THE NORTHEASTERN UNITED	NATIVE EMERGENT WETLAND/ MARSH SEED MIX: APPLICATION RATE = 15 LBS/ACRE
1.00% BLUE JOINT GRASS CALAMAGROSTIS CANADEI 10.00% AMERICAN MANNA GRASS GLYCERIA GRANDIS	1.30% YELLOW GIANT HYSSOP AGASTACHENEPETOIDES 2.59% COLUMBINE AQUILEGIA CANADENSIS	STATES.	
10.00% AMERICAN MANNA GRASS GLYCERIA GRANDIS 4.00% FOWL MANNA GRASS GLYCERIA STRIATA	0.65% YELLOW FALSE FOXGLOVE AUREOLARIA GRANDIFLORA	2. EACH MIX MUST BE DESIGNED FOR THE APPROPRIATE HABITAT FOR	TIER 1 (INCLUDING SLOPE TO TIER 2 OR EXISTING GRADE) –  NATIVE FLOODPLAIN/ RIPARIAN SEED MIX: APPLICATION RATE = 15 LBS/ACRE
5.00% RICE CUT GRASS LEERSIA ORYZOIDES	0.65% HAIRY WOOD MINT BLEPHILIA HIRSUTA	WHICH IT WILL BE APPLIED AS PER PLAN (E.G. FLOODPLAIN,	NORTH   z
8.00% BOTTLEBRUSH SEDGE CAREX COMOSA	1.94% TALL BELLFLOWER CAMPANULA AMERICANA  1.30% MIDLAND SHOOTING STAR DODECATHEON MEADIA	EMERGENT WETLAND AND/ OR UPLAND MEADOW, RESPECTIVELY) AND CONTAIN A MINIMUM OF 20 DIFFERENT SPECIES, WITH AN EXCEPTION	TIER 2 (INCLUDING SLOPE TO EXISTING GRADE) –  NATIVE FLOODPLAIN/ REFORESTATION SEED MIX: APPLICATION RATE = 10 LBS/ACRE
8.00% PORCUPINE SEDGE CAREX HYSTERICINA	2.82% PURPLE CONEFLOWER ECHINACEA PURPUREA	IN THE NATIVE FLOODPLAIN/ REFORESTATION MIX.	NATIVE FLOODPLAIN/ REFORESTATION SEED MIX: APPLICATION RATE = 10 LBS/ACRE  GRAPHIC SCALE IN FEET
0.80% LAKE SEDGE CAREX LACUSTRIS	0.65% GRASS-LEAVED GOLDENROD EUTHAMIA GRAMINIFOLIA	<b>7</b>	NATIVE UPLAND MEADOW/ SAVANNAH SEED MIX: APPLICATION RATE = 10 LBS/ACRE
4.80% BROWN FOX SEDGE CAREX VULPINOIDEA  0.40% BALD SPIKE RUSH ELEOCHARIS ERYTHROPOL	A 200/ OPEAN CENTIANI OFNITIANIA FLAVIDA	3. ALL SEED QUANTITIES MUST CONTAIN A MINIMUM DENSITY OF 75 PURE	
0.40% GREAT SPIKE RUSH ELEOCHARIS PALUSTRIS	5.19% SOLOMON'S PLUME MAIANTHEMUM RACEMOSUM	LIVE SEED (PLS) PER SQUARE—FOOT OF SURFACE AREA TO BE APPLIED, EXCEPT FOR TIER 2 WHICH SHALL BE 25 PLS.	
0.80% COMMON RUSH JUNCUS EFFUSES	1.30% FOXGLOVE BEARDTONGUE PENSTEMON DIGITALIS	4. SUMMIT METRO PARKS SHALL APPROVE ALL SEED MIXES PRIOR TO	
0.60% GREEN BULRUSH SCIRPUS ATROVIRENS	1.30% HAIRY BEARDTONGUE PENSTEMON HIRSUTUS  1.30% WOODLAND KNOTWEED PERSICARIA VIRGINIANA	ORDERING AND INSTALLATION.	
0.20% WOOLGRASS SCIRPUS CYPERINUS	1.94% JACOB'S LADDER POLEMONIUM REPTANS	5. ONLY SEED AREAS THAT ARE DISTURBED. CONTRACTOR SHALL MINIMIZE	
9.60% RIVER BULRUSH SCIRPUS FLUVIATIIS 6.40% SOFTSTEM BULRUSH SCIRPUS VALIDUS	5.19% SOLOMON'S SEAL POLYGONATUM BIFLORUM	AREAS OF DISTURBANCE TO MAXIMUM EXTENT POSSIBLE. IF AN AREA IS DISTURBED, INSTALL NATIVE SEED MIX PER PLAN. MEASURE	
6.40% SOFTSTEM BULRUSH SCIRPUS VALIDUS 8.00% SWEET FLAG ACORUS AMERICANUS	1.30% HAIRY MOUNTAIN MINT PYCNANTHEMUM VERTICILLATUM 3.24% BLACK-EYED SUSAN RUDBECKIA HIRTA	IS DISTURBED, INSTALL NATIVE SEED MIX PER PLAN. MEASURE DISTURBED AREA, CALCULATE SQUARE FOOTAGE AND APPLY AT	
2.00% WATER PLANTAIN ALISMA TRIVALE	3.24% BLACK-EYED SUSAN RUDBECKIA HIRTA  1.94% BROWN-EYED SUSAN RUDBECKIA TRILOBA	DESIGNATED LBS/AC RATE PER SEED MIX.	
5.60% SWAMP MILKWEED ASCLEPIAS INCARNATA	1.30% EARLY FIGWORT SCROPHULARIA LANCEOLATA		
0.80% JOE PYE WEED EUPATORUM MACULATUM	1.41% STARRY CAMPION SILENE STELLATA	6. DRILL SEEDING, IF CHOSEN BY THE CONTRACTOR, IS TO OCCUR AFTER FIRST FROST THROUGH SPRING.	
0.40% BONESET EUPATORIUM PERFOLIATU	0.65% CROOKED-STEMMED ASTER SYMPHYOTRICHUM PRENANTHOIDES		
2.00% SNEEZEWEED HELENIUM AUTUMNALE	1.94% MEADOW PARSNIP THASPIUM TRIFOLIATUM FLAVUM	7. ALL ROCKED BANK STABILIZATION AREAS, AT BANKFULL ELEVATION  (TIER 1 FLOODPLAIN FLEVATION) AND AROVE SHALL BE SEEDED WITH	
10.00% SOUTHERN BLUE FLAG IRIS IRIS VIRGINICA  0.40% MONKEY FLOWER MIMULUS RINGENS	3.89% GOLDEN ALEXANDERS ZIZIA AUREA	TIER 1 FLOODPLAIN ELEVATION) AND ABOVE SHALL BE SEEDED WITH TIER 1 NATIVE FLOODPLAIN/ RIPARIAN SEED MIX.	
1.20% COMMON ARROWHEAD SAGITTARIA LATIFOLIA	0.65% VIRGIN'S BOWER CLEMATIS VIRGINIANA 1.94% EARLY WILD ROSE ROSA BLANDA		
8.00% GIANT BUR REED SPARGANIUM EURYCARPU		<del>-</del>	$\mathcal{B}_{\parallel}$
1.60% BLUE VERVAIN VERBENA HASTATA	1.30% WOOD GRAY SEDGE CAREX GRISEA		
	2.59% FIELD OVAL SEDGE CAREX MOLESTA	$\dashv$	
TIER 1 - NATIVE FLOODPLAIN/ RIPARIAN SEED M	1.30% LONG-BEAKED SEDGE CAREX SPRENGELII 5.19% BEAK GRASS DIARRHENA OBOVATA	$\dashv$	CONTINUED FROM SHEET 38; 7.5 AC (ALONG SPOIL AREAS/FUTURE PARK)
PERCENT COMMON NAME SCIENTIFIC NAME 23.00% FOX SEDGE CAREX VULPINOIDEA	5.19% BOTTLEBRUSH GRASS ELYMUS HYSTRIX	<del>-</del>	ROADWAY)
20.50% POX SEDGE CAREX VOLFINOIDEA  20.50% DEERTONGUE PANICUM CLANDESTIUM	10.37% SILKY WILD RYE ELYMUS VILLOSUS		
20.00% VIRGINIA WILDRYE ELYMUS VIRGINICUS	10.37% VIRGINIA WILD RYE ELYMUS VIRGINICUS	$\perp$	
10.00% BIG BLUESTEM ANDROPOGON GERARDII	5.65% LITTLE BLUESTEM SCHIZACHYRIUM SCOPARIUM		
4.20% HOP SEDGE CAREX LUPULINA			
4.00% LURID SEDGE CAREX LUIDA 4.00% BLUNT BROOM SEDGE CAREX SCOPARIA		OFF OUFFT 70	
3.00% SOFT RUSH JUNCUS EFFUSUS	MAICHLINE	- SEE SHEET 38	
3.00% BLUE VERVAIN VERBENA HASTATA			
2.00% OXEYE SUNFLOWER HELIOPSIS HELANTHIODE			
1.00% SWAMP MILKWEED ASCLEOPIAS INCARNATA 1.00% WOOD REEDGRASS CINNA ARUNDINACEA			
0.60% BONESET EUPATORIUM PERFOLIATION			
0.40% NEW ENGLAND ASTER ASTER NOVAE-ANGLIAE			
0.40% FLAT TOPPED WHITE ASTER ASTER UMBELLATUS			
0.30%MUD PLANTAINALISMA SUBCORDATUM0.30%COMMON SNEEZEWEEDHELENIUM AUTUMNALE			
0.30% WILD BERGAMONT MONARDA FISTULOSA			
0.30% SENSITIVE FERN ONOCLEA SENSIBILIS			
0.30% NARROWLEAF PYCNANTHEMUM TENUIFOLIUM		CONTINUED FROM	
0.30% GREEN BULLRUSH SCIRPUS ATROVIRENS		SHEET 38; 4.64 AC	
0.30% WOOLGRASS SCIRPUS CYPERINUS			
0.20% TURTLEHEAD CHELONE GLABRA			
0.20%DITCH STONECROPPENTHORUM SEDOIDES0.10%WRINKLELEAF GOLDENRODSOLIDAGO RUGOSA			
0.10% TUSSOCK SEDGE CAREX STRICTA			
0.10% GREAT BLUE LOBELIA LOBELIA SIPHILITICA			0.53 AC
TIER 2 - NATIVE FLOODPLAIN/ REFORESTATION			
SEED MIX			
PERCENT COMMON NAME SCIENTIFIC NAME 23.00% FOX SEDGE CAREX VULPINOIDEA	SEED INITIAL 10' OF STREAMBANK		
23.00% FOX SEDGE CAREX VULPINOIDEA 20.00% LITTLE BLUESTEM SCHIZACHYRIUM SCOPARIUI	WITH TIER 1 NATIVE FLOODPLAIN/ RIPARIAN MIX, THEN CONTINUE		0.57 AC —
8.40% HOP SEDGE CAREX LUPULINA	WITH NATIVE UPLAND MIX AS		
18.00% BLUNT BROOM SEDGE CAREX SCOPARIA	SHOWN.	0.70 AC 0.36 AC	0.69 AC
3.00% SOFT RUSH JUNCUS EFFUSUS			
3.00% BLUE VERVAIN VERBENA HASTATA 2.00% OXEYE SUNFLOWER HELIOPSIS HELANTHIODES			
1.00% SWAMP MILKWEED ASCLEOPIAS INCARNATA		OHE OHE	
1.00% WOOD REEDGRASS CINNA ARUNDINACEA	50000000000000000000000000000000000000	OLIF OHE	
0.60% BONESET EUPATORIUM PERFOLIATUM			OHE OHE OHE OHE
0.30% MUD PLANTAIN ALISMA SUBCORDATUM			
0.30% COMMON SNEEZEWEED HELENIUM AUTUMNALE 0.30% WILD BERGAMONT MONARDA FISTULOSA		+ + + + + + + + + + + + + + + + + + + +	
0.30% WILD BERGAWONT WONARDA FISTOLOSA  0.10% GREAT BLUE LOBELIA LOBELIA SIPHILITICA		55 56	
19.00% YELLOW NUTSEDGE CYPERACEAE		57 52 53	
	• • • • • • • • • • • • • • • • • • • •		
		0.27 AC →	

EROSION AND STABILIZATION NOTES

THE VALLEY VIEW PHASE 2 RESTORATION PROJECT IS PRIMARILY AN EARTHMOVING AND GRADING PROJECT. EARTH MATERIALS WILL BE EXCAVATED, STOCKPILED AND RE-USED ON SITE TO CREATE NEW FLOODPLAINS AND WETLAND AREAS ADJACENT TO THE CUYAHOGA RIVER. EARTHWORK ALSO INCLUDES FILLING TWO EXISTING PONDS AND SPOILING MATERIAL ALONG A FUTURE PROPOSED PARK ROADWAY. NO EARTH MATERIAL IS PLANNED TO BE REMOVED FROM THE SITE.

FOLLOWING CONSTRUCTION OF FLOODPLAINS AND WETLANDS, OTHER REMAINING STORM SEWERS, UNDERDRAINS AND OTHER DRAINAGE STRUCTURES WILL BE REMOVED OR ABANDONED AS SHOWN IN THE DEMOLITION PLAN AND AS DIRECTED BY SUMMIT METRO PARKS.

EACH EARTHWORK AREA IS TO BE STABILIZED BY THE CONTRACTOR PRIOR TO BEGINNING EARTH MOVING ACTIVITIES ON THE NEXT AREA. TO THE EXTENT POSSIBLE.

### TYPE OF CONSTRUCTION ACTIVITY

- 1. EARTHWORK ACTIVITIES SHALL BE CONDUCTED IN ACCORDANCE WITH THE SUMMIT COUNTY SOIL AND WATER CONSERVATION DISTRICT. EROSION AND SEDIMENT CONTROL BEST MANAGEMENT PRACTICES (BMP'S) SHALL BE CONDUCTED PER THIS STORMWATER POLLUTION PREVENTION PLAN (SWPPP) AND IN ACCORDANCE WITH OHIO EPA REQUIREMENTS. THE SWPPP SHALL BE AVAILABLE AT THE PROJECT SITE FOR REFERENCE TO BMP ACTIVITY. THE VARIABILITY OF EROSION AND SEDIMENT CONTROL BMP'S MAY BE MODIFIED AS APPROPRIATE TO COMPLETE THE NECESSARY RESTORATION ACTIVITIES.
- 2. TOTAL AREA OF DISTURBANCE: 57 AC. THE MAJORITY OF THE DISTURBANCE IS RELATED TO EARTH MOVING ACTIVITIES.
- 3. THE CUYAHOGA RIVER IS THE RECEIVING STREAM FOR ALL PROJECT RUNOFF.
- 4. RUNOFF COEFFICIENTS/IMPERVIOUS AREA: THERE WILL BE NO INCREASE IN IMPERVIOUS AREA UPON COMPLETION OF THE PROJECT.
- 5. DESCRIPTION OF HCS SOILS: SOILS WITHIN THE PROJECT AREA ARE Ck, CHAGRIN SILT LOAM, ALKALINE; CnB, CHILI LOAM, 2 TO 6 PERCENT SLOPES; CuB, CHILI-URBAN LAND COMPLEX, UNDULATING; CuC, CHILI-URBAN LAND COMPLEX, ROLLING; Hy, HOLLY SILT LOAM, ALKALINE; OsB, OSHTEMO SANDY LOAM, 2 TO 6 PERCENT SLOPES; Od, OLMSTED LOAM; Tq, TIOGA LOAM.
- 6. FOR DISTURBANCE AREAS REMAINING DORMANT FOR OVER 14 DAYS WITHIN 50 FEET OF A STREAM, TEMPORARY EROSION CONTROLS SHALL BE APPLIED WITHIN 2 DAYS OF DISTURBANCE. FOR DISTURBED AREAS GREATER THAN 50 FEET FROM A STREAM AND REMAINING DORMANT FOR OVER 14 DAYS, TEMPORARY EROSION CONTROLS SHALL BE APPLIED WITHIN 7-DAYS OF DISTURBANCE. ALL DISTURBED AND ERODED EARTH SHALL BE REGRADED AND SEEDED, AS DESCRIBED IN THESE PLANS, TO ESTABLISH STABILITY AND PROVIDE SEDIMENT CONTROL WHERE NECESSARY.
- 7. FOR DISTURBED AREAS WHICH HAVE REACHED FINAL GRADE WITHIN 50 FEET OF A STREAM, PERMANENT VEGETATION SHALL BE INSTALLED WITHIN 2 DAYS OF FINAL GRADE WORK. WEATHER PERMITTING.
- 8. VEGETATIVE BUFFER— WHERE POSSIBLE, BUFFER STRIPS WILL BE LEFT BETWEEN TILLING AREAS AND EXISTING DRAINAGE WAYS TO USE NON—STRUCTURAL CONTROLS AND PRESERVE EXISTING VEGETATION BUFFERING.
- 9. CONTRACTOR SHALL INSPECT ALL SWPPP MEASURES WEEKLY AND WITHIN 24 HOURS AFTER A RAIN EVENT OF 0.5 INCHES OR GREATER AND REPAIR SWPPP MEASURES AS NECESSARY TO PREVENT EROSION. SILTATION SHALL BE REMOVED FROM AREAS WHERE FAILURES HAVE OCCURRED AND CORRECTIVE ACTION TAKEN WITHIN 24 HOURS TO MAINTAIN ALL SWPP ITEMS. THE SITE SHALL BE INSPECTED PRIOR TO A FORECASTED RAIN EVENT OF 0.25 INCHES OR GREATER.
- 10. CONSTRUCTION ENTRANCES, AND SWPPP ITEMS SHALL REMAIN IN PLACE UNTIL EARTHWORK AND RESTORATION OPERATIONS ARE COMPLETE AND THE SITE IS STABLE. THE SITE IS CONSIDERED STABLE WHEN 75% VEGETATIVE COVER HAS BEEN ESTABLISHED WITHIN 60 DAYS OF INITIAL SEEDING AND 90% COVERAGE AFTER ONE YEAR ON ALL DISTURBED AREAS. CONTRACTOR SHALL KEEP SILT FROM ENTERING ANY STORM DRAINAGE SYSTEM.
- 11.IF AT ANY TIME UTILITY COMPANIES ARE REQUIRED TO PARTICIPATE IN CONSTRUCTION, UTILITY COMPANIES MUST COMPLY WITH ALL STORM WATER POLLUTION PREVENTION MEASURES AS DEFINED ON THE STORM WATER POLLUTION PREVENTION PLANS, DETAILS AND NOTES.
- 12.IT IS THE CONTRACTOR'S RESPONSIBILITY TO MAINTAIN ALL SEDIMENTATION AND STORM WATER POLLUTION PREVENTION ITEMS AT ALL TIMES.
- 13.NO SOLID (OTHER THAN SEDIMENT) OR LIQUID WASTE, INCLUDING BUILDING MATERIALS, SHALL BE DISCHARGED IN STORM WATER RUNOFF. PROPERLY DISPOSE OF ANY LIQUID IN A CONCRETE WASHOUT THAT HAS NOT EVAPORATED.
- 14. THERE WILL BE NO OPEN BURNING.
- 15. PERIMETER CONTROLS SHALL BE INSTALLED/IMPLEMENTED WITHIN 7 DAYS OF GRUBBING ACTIVITIES AND PER THE CONSTRUCTION SEQUENCE IN THIS PLAN SET (AS REQUIRED). IN AREAS WHERE THE PLANS DO NOT SPECIFY, OR AREAS WHICH ARE IN ADDITION TO PLAN SPECIFICATIONS, PERIMETER CONTROLS SHALL BE INSTALLED/IMPLEMENTED WITHIN 7 DAYS OF GRUBBING ACTIVITIES AND PRIOR TO GRADING OF THE AREA THEY WILL CONTROL.
- 16. TRACKING OF SEDIMENTS BY VEHICLES WILL BE MINIMIZED BY UTILIZING THE CONSTRUCTION ENTRANCE AS THE ONLY ENTRANCE FOR VEHICLES. LOCATIONS WHERE VEHICLES ENTER OR EXIT THE SITE SHALL BE INSPECTED FOR EVIDENCE OF OFF—SITE VEHICLE TRACKING. SEDIMENT/SOIL TRACKED OFF—SITE SHALL BE REMOVED BY CONTRACTOR AND PROPERLY DISPOSED OF.
- 17. THE SWPPP SHALL BE KEPT ONSITE AT ALL TIMES DURING CONSTRUCTION. IT IS THE CONTRACTORS RESPONSIBILITY TO MARK (IN A DOMINANT COLOR) DAILY ANY MINOR

MODIFICATIONS MADE TO THE APPROVED SWPPP SO AS TO KEEP RECORD OF THE MODIFICATIONS MADE IN THE FIELD.

- 18. ALL SOIL DISTURBING ACTIVITIES AT THE SITE ARE TO RECEIVE A COMPLETE AND A UNIFORM PERENNIAL VEGETATIVE COVER (E.G., EVENLY DISTRIBUTED, WITHOUT LARGE BARE AREAS) WITH A DENSITY OF AT LEAST 75% VEGETATIVE COVER TO BE ESTABLISHED WITHIN 60 DAYS OF INITIAL SEEDING AND 90% COVERAGE AFTER ONE YEAR. FOLLOWING SITE STABILIZATION, ALL TEMPORARY EROSION AND SEDIMENT CONTROL PRACTICES SHALL BE REMOVED AND DISPOSED. ALL TRAPPED SEDIMENT SHALL BE PERMANENTLY STABILIZED TO PREVENT FURTHER EROSION.
- 19. ALL FUEL TANKS SHALL BE STAGED WITHIN THE DESIGNATED EQUIPMENT STAGING AREAS AS SHOWN ON THE PLANS. FUELING ACTIVITIES SHALL BE VISUALLY MONITORED AT ALL TIMES TO MANAGE ACCIDENTAL SPILLAGE. IDLE EQUIPMENT, PETROCHEMICALS AND TOXIC/HAZARDOUS MATERIALS SHALL NOT BE STORED IN THE FLOODPLAIN OR NEAR DRAINAGE WAYS OR STREAMS THAT COULD CONVEY SUCH MATERIALS TO THE STREAM. PETROCHEMICALS AND TOXIC/HAZARDOUS MATERIALS SHALL NOT BE DISCHARGED INTO THE STREAM, ITS FLOODPLAIN OR ANY DRAINAGE WAYS/DITCHES. REFUELING OF EQUIPMENT SHALL NOT OCCUR IN THE FLOODPLAIN OR NEAR ANY DRAINAGE WAYS, DITCHES OR WITHIN 50 FEET OF STREAMS. FUEL TANKS SHALL BE CONTAINED OR DIKED. VISUAL MONITORING WOULD NOT BE SUFFICIENT IN THE EVENT OF A SPILL. SUBSTANCES SUCH AS OIL, DIESEL FUEL, HYDRAULIC FLUID, ANTIFREEZE, ETC. THAT IS SPILLED, LEAKED, OR RELEASED ONTO THE SOIL SHALL BE IMMEDIATELY CONTAINED USING SOIL BERMS AND/OR ABSORBENT PADS/SOCKS.
- A) SPILL REQUIREMENTS IN THE EVENT OF SMALL RELEASE (<25 GALLONS): IMPACTED SOIL SHALL BE DUG UP AND FREE LIQUIDS SHALL BE COLLECTED FOR DISPOSAL AT A LICENSED SANITARY LANDFILL OR OTHER APPROVED PETROLEUM CONTAMINATED SOIL REMEDIATION FACILITY (NOT A CONSTRUCTION/DEMOLITION DEBRIS LANDFILL).
- B) SPILL REQUIREMENTS IN THE EVENT OF LARGER RELEASE (>25 GALLONS): SPILLS OF 25 GALLONS OR MORE OF PETROLEUM PRODUCTS SHALL BE REPORTED TO THE OHIO EPA (1-800-282-9378) WITHIN 30 MINUTES OF THE DISCOVERY OF THE RELEASE.
- C) ALL SPILLS WHICH RESULT IN CONTACT WITH WATERS OF THE STATE MUST BE REPORTED TO THE OHIO EPA HOTLINE (1-800-282-9378).
- 20.HAZARDOUS OR TOXIC WASTES SHOULD NOT BE STORED ON SITE, HOWEVER, IF THEY ARE. THE FOLLOWING PROCEDURE SHALL BE FOLLOWED:
- A) ALL HAZARDOUS WASTES SUCH AS OIL FILTERS, PETROLEUM PRODUCTS, PAINT, FERTILIZERS, AND EQUIPMENT MAINTENANCE FLUIDS WILL BE STORED IN STRUCTURALLY SOUND AND SEALED STORAGE CONTAINERS, WITHIN A HAZARDOUS MATERIALS STORAGE AREA IN THE STAGING AREA. HAZARDOUS WASTE MATERIALS SHALL BE STORED IN APPROPRIATE AND CLEARLY MARKED CONTAINERS AND SEGREGATED FROM OTHER NON-HAZARDOUS MATERIALS. SECONDARY CONTAINMENT WILL BE PROVIDED FOR ALL WASTE MATERIALS IN THE HAZARDOUS MATERIALS STORAGE AREA. ADDITIONALLY, ALL HAZARDOUS WASTES SHALL BE DISPOSED OF IN ACCORDANCE WITH FEDERAL, STATE, AND MUNICIPAL REGULATIONS.
- B) ALL WASTE MATERIALS WILL BE COLLECTED AND DISPOSED OF INTO A METAL TRASH DUMPSTER. THE DUMPSTER SHALL HAVE A WATERTIGHT LID AND BE PLACED AWAY FROM STORMWATER DRAINS OR CONVEYANCES AND MEET ALL FEDERAL, STATE, AND MUNICIPAL REGULATIONS. ONLY TRASH AND CONSTRUCTION DEBRIS FROM THE SITE SHALL BE DEPOSITED IN THE DUMPSTER. NO CONSTRUCTION MATERIALS SHALL BE BURIED ON—SITE.

# <u>PERMITS</u>

WORK WITHIN PROJECT SITE/LIMITS IS SUBJECT TO U.S. ARMY CORPS OF ENGINEERS (USACE) REGULATORY JURISDICTION (I.E., JURISDICTIONAL WATERS OF THE U.S.). ANY IMPACTS AND PLACEMENT OF FILL TO JURISDICTIONAL WATERS OUTSIDE OF THE PROJECT LIMITS IS PROHIBITED. THE FOLLOWING PERMITS APPLY TO THIS PROJECT:

OHIO EPA NPDES CONSTRUCTION SITE STORM WATER DISCHARGE GENERAL PERMIT, NO. 3GC09618\*AG.

FLOODPLAIN PERMIT, CITY OF AKRON

USACE NATIONWIDE 27 PERMIT

STORMWATER POLLUTION PREVENTION PLAN (SWPPP) APPROVED BY SCSWCD

# INSPECTION REQUIREMENTS

- 1. FOLLOWING EACH INSPECTION A CHECKLIST MUST BE COMPLETED AND SIGNED BY THE QUALIFIED INSPECTION PERSONNEL REPRESENTATIVE. AT A MINIMUM, THE INSPECTION REPORT MUST INCLUDE:
- a) THE INSPECTION DATE
- b) NAMES, TITLES, AND QUALIFICATIONS OF PERSONNEL MAKING THE INSPECTION
- c) WEATHER INFORMATION FOR THE PERIOD SINCE THE LAST INSPECTION (OR SINCE COMMENCEMENT OF CONSTRUCTION ACTIVITY IF THE FIRST INSPECTION) INCLUDING A BEST ESTIMATE OF THE BEGINNING OF EACH STORM EVENT, DURATION OF EACH STORM EVENT, APPROXIMATE AMOUNT OF RAINFALL FOR EACH STORM EVENT (IN INCHES), AND WHETHER ANY DISCHARGES OCCURRED;
- d) WEATHER INFORMATION AND A DESCRIPTION OF ANY DISCHARGES OCCURRING AT THE TIME OF THE INSPECTION
- e) LOCATION(S) OF DISCHARGES OF SEDIMENT OR OTHER POLLUTANTS FROM THE SITE f) LOCATION(S) OF BMPS THAT NEED TO 0E MAINTAINED
- g) LOCATION(S) OF BMPS THAT FAILED TO OPERATE AS DESIGNED OR PROVED INADEQUATE FOR A PARTICULAR LOCATION
- h) LOCATION(S) WHERE ADDITIONAL BMPS ARE NEEDED THAT DID NOT EXIST AT THE TIME OF THE INSPECTION
- i) CORRECTIVE ACTION REQUIRED INCLUDING ANY CHANGES TO THE SWPPP NECESSARY AND IMPLEMENTATION DATES.
- 2. DISTURBED AREAS AND AREAS USED FOR STORAGE OF MATERIALS THAT ARE EXPOSED TO PRECIPITATION SHALL BE INSPECTED FOR EVIDENCE OF OR THE POTENTIAL FOR POLLUTANTS ENTERING THE DRAINAGE SYSTEM. EROSION AND SEDIMENT CONTROL MEASURES IDENTIFIED IN THE SWPPP SHALL BE OBSERVED TO ENSURE THAT THOSE ARE OPERATING CORRECTLY. DISCHARGE LOCATIONS SHALL BE INSPECTED TO ASCERTAIN WHETHER EROSION AND SEDIMENT CONTROL MEASURES ARE EFFECTIVE IN PREVENTING SIGNIFICANT IMPACTS TO THE RECEIVING WATERS. LOCATIONS WHERE VEHICLES ENTER OR EXIT THE SITE SHALL BE INSPECTED FOR EVIDENCE OF OFF—SITE VEHICLE TRACKING. ALL SEDIMENT/SOIL TRACKED OFF—SITE SHALL BE REMOVED AND DISPOSED OF BY THE CONTRACTOR.

- 3. INSPECTION: AT A MINIMUM, ALL CONTROLS ON THE SITE WILL BE INSPECTED AT LEAST ONCE EVERY SEVEN CALENDAR DAYS, PRIOR TO ANY FORECASTED RAIN EVENT OF 0.25 INCHES OR GREATER. AND WITHIN 24 HOURS AFTER ANY STORM EVENT GREATER THAN ONE-HALF INCH OF RAIN PER 24HOUR PERIOD. THE INSPECTION FREQUENCY MAY BE REDUCED TO AT LEAST ONCE EVERY MONTH IF THE ENTIRE SITE IS TEMPORARILY STABILIZED OR RUNOFF IS UNLIKELY DUE TO WEATHER CONDITIONS (E.G., SITE IS COVERED WITH SNOW, ICE, OR THE GROUND IS FROZEN). A WAIVER OF INSPECTION REQUIREMENTS IS AVAILABLE UNTIL ONE MONTH BEFORE THAWING CONDITIONS ARE EXPECTED TO RESULT IN A DISCHARGE IF ALL OF THE FOLLOWING CONDITIONS ARE MET: THE PROJECT IS LOCATED IN AN AREA WHERE FROZEN CONDITIONS ARE ANTICIPATED TO CONTINUE FOR EXTENDED PERIODS OF TIME (I.E., MORE THAN ONE MONTH); LAND DISTURBANCE ACTIVITIES HAVE BEEN SUSPENDED; AND THE BEGINNING AND ENDING DATES OF THE WAIVER PERIOD ARE DOCUMENTED IN THE SWPPP. ONCE A DEFINABLE AREA IS FINALLY STABILIZED, THE AREA MAY BE MARKED ON THE SWPPP AND NO FURTHER INSPECTION REQUIREMENTS APPLY TO THAT PORTION OF THE SITE. THE PERMITTEE SHALL ASSIGN "QUALIFIED INSPECTION PERSONNEL" TO CONDUCT THESE INSPECTIONS TO ENSURE THAT THE CONTROL PRACTICES ARE FUNCTIONAL AND TO EVALUATE WHETHER THE SWPPP IS ADEQUATE AND PROPERLY IMPLEMENTED IN ACCORDANCE WITH THE SCHEDULE PROPOSED IN PART III.G.1.H OF THIS PERMIT OR WHETHER ADDITIONAL CONTROL MEASURES ARE REQUIRED.
- 4. ALL DISCHARGERS REGULATED UNDER THE GENERAL PERMIT MUST COMPLY, EXCEPT THOSE EXEMPTED UNDER STATE LAW, WITH THE LAWFUL REQUIREMENTS OF MUNICIPALITIES, COUNTIES AND OTHER LOCAL AGENCIES REGARDING DISCHARGES OF STORM WATER.

# SUGGESTED GENERAL SEQUENCE OF CONSTRUCTION

CONSTRUCTION SHALL NOT BEGIN UNTIL ALL SEDIMENT AND EROSION CONTROL MEASURES HAVE BEEN INSTALLED. THE CONTRACTOR SHALL MINIMIZE DISTURBANCE WITHIN THE WORKING AREA WHEREVER POSSIBLE.

- SECURE NECESSARY PERMITS
- MOBILIZE;
- INSTALL EROSION AND SEDIMENT CONTROLS;
- CONSTRUCT TEMPORARY ACCESS ROADS AND STAGING AREAS; INSTALL PERIMETER SEDIMENT CONTROLS AROUND STAGING AREA;
- TREE AND VEGETATION CLEARING AND GRUBBING; VEGETATION WILL BE CLEARED DURING APPROPRIATE TIMEFRAME FROM OCTOBER 1ST TO MARCH 31ST;
- SITE LAYOUT;
- INITIATE WATER CONTROL PROCEDURES AS NECESSARY; ANY DEWATERING REQUIRED MUST BE COMPLETED IN ACCORDANCE WITH OEPA GUIDELINES FOR CONSTRUCTION STORMWATER DISCHARGE;
- STRIP AND STOCKPILE TOPSOIL TO AREAS DESIGNATED ON PLAN ONLY
- INSTALL EROSION AND SEDIMENT CONTROLS AS AREAS BECOME DISTURBED;
- BEGIN EARTHMOVING CUT AND FILL ACTIVITIES ON WETLAND AND FLOODPLAIN AREAS TO ACHIEVE SUBGRADE;
- IMPORT ROCK MATERIAL AND INSTALLATION TO ACHIEVE FINISH GRADES;
- INCORPORATE WOODY AND BOULDER HABITATS, BRUSH LAYERING, STANDING DEADWOOD, ETC. INTO PROJECT COMPONENTS;
- PLACE AND RESPREAD TOPSOIL TO FINISH GRADE;
- CONDUCT MILESTONE WALK THROUGH (SEE NOTE THIS SHEET);
- SEED (TEMPORARY AND FINAL), STABILIZE, AND INSTALL EROSION CONTROL FABRIC AND SWPPP BMP'S AS AREAS REACH FINAL GRADE OR REMAIN UNWORKED:
- INSTALL PLANTINGS AT APPROPRIATE SEASONAL TIMEFRAME;
- REMOVE TEMPORARY EROSION AND SEDIMENT CONTROLS ONCE 70% STABILIZATION OF DISTURBED AREAS HAS BEEN ACHIEVED;
- DEMOBILIZE FOLLOWING SITE APPROVAL BY METRO PARKS
- FILE NOTICE OF TERMINATION

# DUST CONTROL

- 1. VEGETATIVE COVER AND MULCH APPLY TEMPORARY OR PERMANENT SEEDING AND MULCH TO AREA THAT WILL REMAIN IDLE FOR OVER 21 DAYS. TO THE EXTENT POSSIBLE, EXISTING TREES AND LARGE SHRUBS SHALL REMAIN IN PLACE TO REDUCE SOIL AND AIR MOVEMENT ACROSS DISTURBED AREAS. SEE TEMPORARY SEEDING, PERMANENT SEEDING, AND MULCHING PRACTICES.
- 2. WATERING SPRAY SITE WITH WATER UNTIL THE SURFACE IS WET BEFORE AND DURING GRADING AND REPEAT AS NEEDED TO PREVENT GENERATION OF VISIBLE AIRBORNE DUST. ESPECIALLY ON HAUL ROADS AND OTHER HEAVY TRAFFIC ROUTES. WATERING SHALL BE DONE AT A RATE THAT PREVENTS

DUST BUT DOES NOT CAUSE SOIL EROSION. WETTING AGENTS SHALL BE UTILIZED ACCORDING TO MANUFACTURERS INSTRUCTIONS. CHEMICAL AND ORGANIC AGENTS SHOULD NOT BE APPLIED UNDER FROZEN CONDITIONS, RAINY CONDITIONS, OR WHEN THE TEMPERATURE IS BELOW 40° F. THESE AGENTS WILL NOT BE USED IN THE FLOODPLAIN.

- 3. STONE GRADED ROADWAYS AND OTHER SUITABLE AREAS WILL BE STABILIZED USING CRUSHED STONE OR COARSE GRAVEL AS SOON AS PRACTICAL AFTER REACHING AN INTERIM OR FINAL GRADE. CRUSHED STONE OR COARSE GRAVEL CAN BE USED AS A PERMANENT COVER TO PROVIDE CONTROL OF SOIL EMISSIONS.
- 4. BARRIERS EXISTING WINDBREAK VEGETATION SHALL BE MARKED AND PRESERVED. SNOW FENCING OR OTHER SUITABLE BARRIER MAY BE PLACED PERPENDICULAR TO PREVAILING AIR CURRENTS AT INTERVALS OF ABOUT 15 TIMES THE BARRIER HEIGHT TO CONTROL AIR CURRENTS AND BLOWING SOIL. THIS MATERIAL WILL NOT BE USED IN THE FLOODPLAIN.
- 5. CALCIUM CHLORIDE THIS CHEMICAL MAY BE APPLIED BY MECHANICAL SPREADER AS LOOSE, DRY GRANULES OR FLAKES AT A RATE THAT KEEPS THE SURFACE MOIST BUT NOT SO HIGH AS TO CAUSE WATER POLLUTION OR PLANT DAMAGE. APPLICATION RATES SHOULD BE STRICTLY IN ACCORDANCE WITH SUPPLIERS SPECIFIED RATES. THIS MATERIAL WILL NOT BE USED IN THE FLOODPLAIN.

N/A

DE

METRO 2 REST(

SUMMIT VIEW PH

A 4 4

Summit © etro Parks

6. OPERATION AND MAINTENANCE — SITE SHALL BE CONTINUOUSLY MONITORED TO VERIFY EFFECTIVENESS OF DUST CONTROL MEASURES. WHEN TEMPORARY DUST CONTROL MEASURES ARE USED, REPETITIVE TREATMENT SHOULD BE APPLIED AS NEEDED TO ACCOMPLISH CONTROL.


# TEMPORARY STABILIZATION AND NATIVE SEED INSTALLATION


GRAIN RYE (Secale cereale) OR OATS (Avena sativa) AT A RATE OF 30 LBS PER ACRE SHALL BE INSTALLED TO ALL DISTURBED AREAS. NATIVE SEED MIXES ARE TO BE INSTALLED AT THE SPECIFIED RATE IN THE APPROPRIATE AREAS (REFER TO THE PLANTING PLAN SHEETS 36 THROUGH 39). ALL NATIVE SEED IS TO BE INSTALLED BY HAND SEEDING METHOD DUE TO VARIABILITY OF SEEDS WITHIN MIX. CONTRACTOR IS TO ESTIMATE SEEDING AREA AND WEIGH SEED IN APPROPRIATE QUANTITIES TO ENSURE APPLICATION AT THE CORRECT RATE. A STARTER FERTILIZER IS NOT REQUIRED UNLESS SITE—SPECIFIC SOIL TESTS DEEM A DEFICIENCY IN ONE OR MORE SOIL COMPONENTS. AT THAT TIME, A FERTILIZER RATE WILL BE APPLIED AS NECESSARY TO PROMOTE A HEALTHY NATIVE COMMUNITY. FOLLOWING TEMPORARY AND NATIVE SEED INSTALLATION, SEED IS TO BE LIGHTLY RAKED INTO SOIL. COVER SOIL WITH APPROPRIATE EROSION PROTECTION PER AREA.

# INSPECTION CHECKLIST

INSPECTIONS SHALL BE MADE ONCE EVERY SEVEN (7) CALENDAR DAYS, PRIOR TO ANY FORECASTED RAIN EVENT OF 0.25 INCHES OR GREATER, AND WITHIN 24 HOURS AFTER ANY STORM EVENT GREATER THAN ONE—HALF INCH OF RAIN PER 24 HOUR PERIOD.

Date	Inspector	Weather Conditions	Rainfall Amount	Sediment Discharge	Discharge Location	BMPs Failed	Additional BMPS Needed	Correction Made





# **SPECIFICATIONS FOR SILT FENCE**

- 1. SILT FENCE SHALL BE CONSTRUCTED BEFORE UPSLOPE LAND DISTURBANCE BEGINS.
- ALL SILT FENCE SHALL BE PLACED AS CLOSE TOTHE CONTOUR AS POSSIBLE SO THAT WATER WILL NOT CONCENTRATE AT LOW POINTS IN THE FENCE AND SO THAT SMALL SWALES OR DEPRESSIONS THAT MAY CARRY SMALL CONCENTRATED FLOWS TO THE SILT FENCE ARE DISSIPATED ALONG ITS LENGTH.
- B. ENDS OF THE SILT FENCES SHALL BE BROUGHT UPSLOPE SLIGHTLY SO THAT WATER PONDED BY THE SILT FENCE WILL BE PREVENTED FROM FLOWING AROUND THE ENDS.
- 4. SILT FENCE SHALL BE PLACED ON THE FLATTEST AREA AVAILABLE
- WHERE POSSIBLE, VEGETATION SHALL BE PRESERVED FOR 5 FEET (OR AS MUCH AS POSSIBLE) UPSLOPE FROM THE SILT FENCE. IF VEGETATION IS REMOVED. IT SHALL BE REESTABLISHED WITHIN 7 DAYS FROM THE INSTALLATION OF THE SILT FENCE.
- 6. THE HEIGHT OF THE SILT FENCE SHALL BE A MINIMUM OF 16 INCHES ABOVE THE ORIGINAL GROUND SURFACE.
- THE SILT FENCE SHALL BE PLACED IN AN EXCAVATED OR SLICED TRENCH CUT A MINIMUM OF 6 INCHES DEEP. THE TRENCH SHALL BE MADE WITH A TRENCHER, CABLE LAYING MACHINE, SLICING MACHINE, OR OTHER SUITABLE DEVICE THAT WILL ENSURE AN ADEQUATELY UNIFORM TRENCH
- 8. THE SILT FENCE SHALL BE PLACED WITH THE STAKES ON THE DOWNSLOPE SIDE OF THE GEOTEXTILE. A MINIMUM OF 8 INCHES OF GEOTEXTILE MUST BE BELOW THE GROUND SURFACE. EXCESS MATERIAL SHALL LAY ON THE BOTTOM OF THE 6-INCH DEEP TRENCH. THE TRENCH SHALL BE BACKFILLED AND COMPACTED ON BOTH SIDES OF THE FABRIC.
- 9. SEAMS BETWEEN SECTIONS OF SILT FENCE SHALL BE SPLICED TOGETHER ONLY AT A SUPPORT POST WITH A MINIMUM OF 6-IN. OVERLAP PRIOR TO DRIVING INTO THE GROUND, (SEE DETAILS).
- 10. MAINTENANCE-SILT FENCE SHALL ALLOW RUNOFF TO PASS ONLY AS DIFFUSE FLOW THROUGH THE GEOTEXTILE. IF RUNOFF OVER-TOPS THE SILT FENCE, FLOWS UNDER THE FABRIC OR AROUND THE FENCE ENDS, OR IN ANY OTHER WAY ALLOWS A CONCENTRATED FLOW DISCHARGE, ONE OF THE FOLLOWING SHALL BE PERFORMED, AS APPROPRIATE: 1) THE LAYOUT OF THE SILT FENCE SHALL BE CHANGED, 2) ACCUMULATED SEDIMENT SHALL BE REMOVED, OR 3) OTHER PRACTICES SHALL BE INSTALLED.

SEDIMENT DEPOSITS SHALL BE ROUTINELY REMOVED WHEN THE DEPOSIT REACHES APPROXIMATELY ONE-HALF OF THE HEIGHT OF THE SILT FENCE.

SILT FENCES SHALL BE INSPECTED AFTER EACH RAINFALL AND AT LEAST DAILY DURING A PROLONGED RAINFALL. THE LOCATION OF EXISTING SILT FENCE SHALL BE REVIEWED DAILY TO ENSURE ITS PROPER LOCATION AND EFFECTIVENESS. IF DAMAGED, THE SILT FENCE SHALL BE REPAIRED IMMEDIATELY.

# CRITERIA FOR SILT FENCE MATERIALS

11. FENCE POST - THE LENGTH SHALL BE A MINIMUM OF 32 INCHES. WOOD POSTS WILL BE 2-BY-2-IN. NOMINAL DIMENSIONED HARDWOOD OF SOUND QUALITY. THEY SHALL BE FREE OF KNOTS, SPLITS AND OTHER VISIBLE IMPERFECTIONS, THAT WILL WEAKEN THE POSTS. THE MAXIMUM SPACING BETWEEN POSTS SHALL BE 10FT. POSTS SHALL BE DRIVEN A MINIMUM 16 INCHES INTO THE GROUND, WHERE POSSIBLE. IF NOT POSSIBLE, THE POSTS SHALL BE ADEQUATELY SECURED TO PREVENT OVERTURNING OF THE FENCE DUE TO SEDIMENT/WATER

## 12. SILT FENCE FABRIC - SEE CHART BELOW.

TABLE 6.3.2 MINIMUM CRITERIA FOR SILT FENCE FABRIC (ODOT. 2002)

TABLE 0.3.2 MINIMUM CRITERIA FOR SILT FENCE FABRIC (ODOT, 2002)					
FABRIC PROPERTIES	VALUES	TEST METHOD			
MINIMUM TENSILE STRENGTH	120 LBS. (535 N)	ASTM D 4632			
MAXIMUM ELONGATION AT 60 LBS	50%	ASTM D 4632			
MINIMUM PUNCTURE STRENGTH	50 LBS (220 N)	ASTM D 4833			
MINIMUM TEAR STRENGTH	40 LBS (180 N)	ASTM D 4533			
APPARENT OPENING SIZE	≤ 0.84 mm	ASTM D 4751			
MINIMUM PERMITVITY	1X10-2 SEC, -1	ASTM D 4491			
UV EXPOSURE STRENGTH RETENTION	70%	ASTM D 4355			

# SILT FENCE AND DIVERSIONS:

SHEET FLOW RUNOFF FROM DENUDED AREAS SHALL BE INTERCEPTED BY SILT FENCE OR DIVERSIONS TO PROTECT ADJACENT PROPERTIES, WATER RESOURCES, AND WETLANDS FROM SEDIMENT TRANSPORTED VIA SHEET FLOW. WHERE INTENDED TO PROVIDE SEDIMENT CONTROL, SILT FENCE SHALL BE PLACED ON A LEVEL CONTOUR AND SHALL BE CAPABLE OF TEMPORARILY PONDING RUNOFF. THE RELATIONSHIP BETWEEN THE MAXIMUM DRAINAGE AREA TO SILT FENCE FOR A PARTICULAR SLOPE RANGE IS SHOWN IN TABLE 3 BELOW. STORM WATER DIVERSION PRACTICES SHALL BE USED TO KEEP RUNOFF AWAY FROM DISTURBED AREAS AND STEEP SLOPES. SUCH DEVICES, WHICH INCLUDE SWALES, DIKES OR BERMS, MAY RECEIVE STORM WATER RUNOFF FROM AREAS UP TO 10 ACRES. PLACING SILT FENCE IN PARALLEL DOES NOT EXTEND THE PERMISSIBLE DRAINAGE AREA WHICH IS SERVED BY THE SILT FENCE.

# MAXIMUM DRAINAGE AREA TO SILT FENCE

MAXIMUM DRAINAGE AREA (ACRES) TO 100 LINEAR FEET OF SILT FENCE	RANGE OF SLOPE FOR A DRAINAGE AREA (%)
0.5	<2%
0.5	<270
0.25	>2% BUT <20%
0.125	>20% BUT <50%

# SALVAGING AND STOCKPILING

1.DETERMINE THE DEPTH AND SUITABILITY OF TOPSOIL AT THE SITE. REFER TO THE COUNTY SOIL SURVEY REPORT OR CONTACT LOCAL SWCD.


- 2.PRIOR TO STRIPPING TOPSOIL, INSTALL APPROPRIATE DOWNSLOPE EROSION AND SEDIMENTATION CONTROLS SUCH AS SEDIMENT TRAPS AND BASINS.
- 3. REMOVE THE SOIL MATERIAL NO DEEPER THAN WHAT THE COUNTY SOIL SURVEY DESCRIBES AS 'SURFACE SOIL' (IE. A OR AP HORIZON)
- 4. CONSTRUCT STOCKPILES IN ACCESSIBLE LOCATIONS THAT DO NOT INTERFERE WITH NATURAL DRAINAGE. INSTALL APPROPRIATE SEDIMENT CONTROLS TO TRAP SEDIMENT SUCH AS SILT FENCE IMMEDIATELY ADJACENT TO THE STOCKPILE OR SEDIMENT TRAPS OR BASINS DOWNSTREAM OF THE STOCKPILE. STOCKPILE SIDE SLOPES SHALL NOT EXCEED A RATION OF 2:1.
- 5. IF TOPSOIL IS STORED FOR MORE THAN 21 DAYS, IT SHOULD BE TEMPORARY SEEDED, OR COVERED WITH A TARP.

# SPREADING THE TOPSOIL

WITH SUBSOIL.

1.PRIOR TO APPLYING TOPSOIL, THE TOPSOIL SHOULD BE PULVERIZED.

2.TO ENSURE BONDING, GRADE THE SUBSOIL AND ROUGHEN THE TOP 3-4 INCHES BY DISKING.




# FILTER SOCK PROFILE

- 1. MATERIAL-COMPOST USED FOR FILTER SOCKS SHALL BE WEED, PATHOGEN AND INSECT FREE AND FREE OF ANY REFUSE, CONTAMINANTS OR OTHER MATERIALS TOXIC TO PLANT GROWTH. THEY SHALL BE DERIVED FROM A WELL-DECOMPOSEDSOURCE OF ORGANIC MATTER AND CONSIST OF PARTICLES RANGING ROM 3 / 8" TO 2"
- 2. FILTER SOCKS SHALL BE 3 OR 5 MIL CONTINUOUS, TUBULAR, HDPE 3 / 8" KNITTED MESH NETTING MATERIAL, FILLED WITH COMPOST PASSING THE ABOVE SPECIFICATIONS FOR

- THE BASE OF THE SLOPE OR OTHER AFFECTED AREA. ON SLOPES APPROACHING 2:1 ADDITIONAL SOCKS SHALL BE PROVIDED AT THE TOP AND AS NEEDED MID-SLOPE
- 4. FILTER SOCKS INTENDED TO BE LEFT AS A PERMANENT FILTER OR PART OF THE NATURAL LANDSCAPE, SHALL BE SEEDED AT THE TIME OF INSTALLATION FOR ESTABLISHED OR PERMANENT VEGETATION.
- 5. FILTER SOCKS ARE NOT TO BE USED IN CONCENTRATED FLOW SITUATIONS OR IN RUNOFF
- 6. ROUTINELY INSPECT FILTER SOCKS AFTER EACH SIGNIFICANT RAIN, MAINTAINING FILTER SOCKS IN A FUNCTIONAL CONDITION AT ALL TIMES.


# FILTER SOCK DETAIL



# SILT FENCE NOT TO SCALE

# 3. DO NOT APPLY WHEN SITE IS WET, MUDDY, OR FROZEN, BECAUSE IT MAKES SPREADING DIFFICULT, CAUSES COMPACTION PROBLEMS, AND INHIBITS BONDING

- 4. APPLY TOPSOIL EVENLY TO A DEPTH OF AT LEAST 4 INCHES AND COMPACT SLIGHTLY TO IMPROVE CONTACT AND SUBSOIL.
- 5. AFTER SPREADING, GRADE AND STABILIZE WITH SEEDING OR APPROPRIATE VEGETATION. **TOPSOILING**



# **SECTION**


# COMPOST PRODUCTS.


# FILTER SOCKS WILL BE PLACED ON A LEVEL LINE ACROSS SLOPES, GENERALLY PARALLEL TO

- CHANNELS.


- 7. REMOVE SEDIMENTS COLLECTED AT THE BASE OF THE FILTER SOCKS WHEN THEY REACH 1 / 3 OF THE EXPOSED HEIGHT OF THE PRACTICE.
- 8. WHERE THE FILTER SOCK DETERIORATES OR FAILS, IT WILL BE REPAIRED OR REPLACED WITH A MORE EFFICIENT ALTERNATIVE.
- 9. REMOVAL FILTER SOCKS WILL BE DISPERSED ON SITE WHEN NO LONGER REQUIRED IN SUCH A WAY AS TO FACILITATE AND NOT OBSTRUCT SEEDINGS.

# NOT TO SCALE





CHECK DAM CROSS SECTION



# CHECK DAM PROFILE

- 1. THE CHECK DAM SHALL BE CONSTRUCTED OF 4-8 INCH DIAMETER STONE, PLACED SO THAT IT COMPLETELY COVERS THE WIDTH OF THE CHANNEL. ODOT TYPE D STONE IS ACCEPTABLE, BUT SHOULD BE UNDERLAIN WITH A GRAVEL FILTER CONSISTING OF ODOT NO. 3 OR 4 OR SUITABLE FILTER FABRIC
- 2. MAXIMUM HEIGHT OF CHECK DAM SHALL NOT EXEED 3.0 FEET
- 3. THE MIDPOINT OF THE ROCK CHECK DAM SHALL BE A MINIMUM OF 6 INCHES LOWER THAN THE SIDES IN ORDER TO DIRECT ACROSS THE CENTER AND AWAY FROM THE CHANNEL SIDES
- 4. THE BASE OF THE CHECK DAM SHALL BE ENTRENCHED APPROXIMATELY 6 INCHES
- SPACING OF CHECK DAMS SHALL BE IN A MANNER SUCH THAT THE TOE OF THE UPSTREAM DAM IS AT THE SAME ELEVATION AS THE TOP OF THE DOWNSTREAM DAM.
- 6. A SPLASH APRON SHALL BE CONSTRUCTED WHERE CHECK DAMS ARE EXPECTED TO BE IN USE FOR AN EXTENDED PERIOD OF TIME, A STONE APRON SHALL BE CONSTRUCTED IMMEDIATELY DOWNSTREAM OF THE CHECK DAM TO PREVENT FLOWS FORM UNDERCUTTING THE STRUCTURE. THE APRON SHOULD BE 6 IN. THICK AND ITS LENGTH TWO TIMES THE EIGHT OF THE DAM.
- STONE PLACEMENT SHALL BE PERFORMED EITHER BY HAND OR MECHANICALLY AS LONG AS THE CENTER OF CHECK DAM IS LOWER THAN THE SIDES AND EXTENDS ACROSS ENTIRE CHANNEL.
- 8. SIDE SLOPES SHALL BE A MINIMUM OF 2:1


CHECK DAM SPACING					
DAM HEIGHT	CHANNEL SLOPE				
(FT)	<5% 5 - 10% 10 - 15% 15 - 20%				
1	65 FT	30 FT	20 FT	15 FT	
2	130 FT	65 FT	40 FT	30 FT	
3	200 FT	100 FT	65 FT	50 FT	

# ROCK CHECK DAM NOT TO SCALE

# TEMPORARY SEEDING SPECIES SELECTION

SEEDING DATES	SPECIES	LB/1000 FT. <sup>2</sup>	LB/ACRE
MARCH 1 TO AUGUST 15	OATS	3	4 BUSHEL
AUGUST 16 TO NOVEMBER 1	WHEAT	3	2 BUSHEL
NOVEMBER 1 TO FEBRUARY 29	USE MULCH ONLY OR DORMA	NT SEEDING	

NOTE: OTHER APPROVED SEED SPECIES MAY BE SUBSTITUTED.



- 1. ALL TREES, BRUSH, STUMPS, AND OTHER UNSUITABLE MATERIAL SHALL BE REMOVED FROM
- 2. THE CHANNEL SHALL BE EXCAVATED AND SHAPED TO THE PROPER GRADE AND CROSS
- 3. FILL MATERIAL USED IN THE CONSTRUCTION OF THE CHANNEL SHALL BE WELL COMPACTED IN UNIFORM LAYERS NOT EXCEEDING 9 INCHES USING THE WHEEL TREADS OR TRACKS OF THE CONSTRUCTION EQUIPMENT TO PREVENT UNEQUAL SETTLEMENT.
- 4. EXCESS EARTH SHALL BE GRADED OR DISPOSED OF SO THAT IT WILL NOT RESTRICT FLOW TO THE CHANNEL OR INTERFERE WITH ITS FUNCTIONING.
- 5. STABILIZATION SHALL BE DONE ACCORDING TO THE APPROPRIATE SPECIFICATIONS FOR PERMANENT SEEDING, VEGETATIVE PRACTICES, SODDING AND MATTING.
- CONSTRUCTION SHALL BE SEQUENCED SO THAT NEWLY CONSTRUCTED CHANNELS ARE STABILIZED PRIOR TO BECOMING OPERATIONAL. TO AID IN THE ESTABLISHMENT OF VEGETATION, SURFACE WATER MAY BE PREVENTED FROM ENTERING THE NEWLY CONSTRUCTED CHANNEL THROUGH THE ESTABLISHMENT PERIOD.
- GULLIES THAT MAY FORM IN THE CHANNEL OR OTHER EROSION DAMAGE THAT OCCURS BEFORE THE GRASS LINING BECOMES ESTABLISHED SHALL BE REPAIRED WITHOUT DELAY.

# GRASS SWALE DETAIL

## TEMPORARY SEEDING (CON'T)

- 1. STRUCTURAL EROSION AND SEDIMENT CONTROL PRACTICES SUCH AS DIVERSIONS AND SEDIMENT TRAPS SHALL BE INSTALLED AND STABILIZED WITH TEMPORARY SEEDING PRIOR TO GRADING THE REST OF THE CONSTRUCTION-SITE.
- 2. TEMPORARY SEED SHALL BE APPLIED BETWEEN CONSTRUCTION OPERATIONS ON SOIL THAT WILL NOT BE GRADED OR REWORKED FOR 21 DAYS OR GREATER. THESE IDLE AREAS SHALL BE SEEDED WITHIN 7 DAYS AFTER GRADING. SEVERAL APPLICATIONS OF TEMPORARY SEEDING ARE NECESSARY ON TYPICAL CONSTRUCTION PROJECTS.
- 3. THE SEEDBED SHALL BE PULVERIZED AND LOOSE TO ENSURE THE SUCCESS OF ESTABLISHING VEGETATION. TEMPORARY SEEDING SHALL NOT BE POSTPONED IF IDEAL SEEDBED PREPARATION IS NOT POSSIBLE.
- 5. SEEDING METHOD--SEED SHALL BE APPLIED UNIFORMLY WITH A CYCLONE SPREADER, DRILL CULTIPACKER SEEDER, OR HYDROSEEDER, WHEN FEASIBLE, SEED THAT HAS BEEN BROADCAST SHALL BE COVERED BY RAKING OR DRAGGING AND THEN LIGHTLY TAMPED INTO PLACE USING A ROLLER OR CULTIPACKER. IF HYDROSEEDING IS USED, THE SEED AND FERTILIZER WILL BE MIXED ON-SITE AND THE SEEDING SHALL BE DONE IMMEDIATELY AND WITHOUT INTERRUPTION.

# MULCHING TEMPORARY SEEDING:

1. APPLICATIONS OF TEMPORARY SEEDING SHALL INCLUDE MULCH WHICH SHALL BE APPLIED DURING OR IMMEDIATELY AFTER SEEDING. SEEDINGS MADE DURING OPTIMUM SEEDING DATES ON FAVORABLE SOIL CONDITIONS AND ON VERY FLAT AREAS MAY NOT NEED MULCH TO ACHIEVE ADEQUATE STABILIZATION.

# 2. MATERIALS:

ANCHORING METHODS:

STRAW--IF STRAW IS USED, IT SHALL BE UNROTTED SMALL-GRAIN STRAW APPLIED AT 2 TONS/AC. OR 90 LB. / 1,000 SQ. FT. (TWO TO THREE BALES). THE MULCH SHALL BE SPREAD UNIFORMLY BY HAND OR MECHANICALLY SO THE SOIL SURFACE IS COVERED. FOR UNIFORM DISTRIBUTION OF HAND-SPREAD MULCH, DIVIDE AREA INTO APPROXIMATELY 1,000 SQ. FT. SECTIONS AND SPREAD TWO 45 LB. BALES OF STRAW IN EACH SECTION.

HYDROSEEDERS--IF WOOD CELLULOSE FIBER IS USED, IT SHALL BE USED AT 2,000 LB. / AC. OR 46 LB. /1,000 SQ. FT.

OTHER--OTHER ACCEPTABLE MULCHES INCLUDE MULCH MATTINGS APPLIED ACCORDING TO MANUFACTURER'S RECOMMENDATIONS OR WOOD CHIPS APPLIED AT 6 TONS / AC.

3. STRAW MULCH SHALL BE ANCHORED IMMEDIATELY TO MINIMIZE LOSS BY WIND OR WATER.

MECHANICAL--A DISK, CRIMPER OR SIMILAR TYPE TOOL SHALL BE SET STRAIGHT TO PUNCH OR ANCHOR THE MULCH MATERIAL INTO THE SOIL. STRAW MECHANICALLY ANCHORED SHALL NOT


MULCH NETTINGS--NETTINGS SHALL BE USED ACCORDING TO THE MANUFACTURER'S RECOMMENDATIONS. NETTING MAY BE NECESSARY TO HOLD MULCH IN PLACE IN AREAS OF CONCENTRATED RUNOFF AND ON CRITICAL SLOPES.

BE FINELY CHOPPED BUT, GENERALLY BE LEFT LONGER THAN 6 IN.

WOOD-CELLULOSE FIBER--WOOD-CELLULOSE FIBER BINDER SHALL BE APPLIED AT A NET DRY WEIGHT OF 750 LB. /AC. THE WOOD-CELLULOSE FIBER SHALL BE MIXED WITH WATER AND THE MIXTURE SHALL CONTAIN A MAXIMUM OF 50 LB. / 100 GAL.

**TEMPORARY SEEDING** 

SEE NOTE, SHEET 40.



## CONSTRUCTION ENTRANCE PROFILE NOT TO SCALE

- 1. STONE SIZE--ODOT #2 (1.5 2.5 INCH) STONE SHALL BE USED, OR RECYCLED CONCRETE
- 2. LENGTH--THE CONSTRUCTION ENTRANCE SHALL BE AS LONG AS REQUIRED TO STABILIZE HIGH TRAFFIC AREAS BUT NOT LESS THAN 70 FT. (EXCEPTION: APPLY 30 FT. MINIMUM TO SINGLE
- THICKNESS--THE STONE LAYER SHALL BE AT LEAST 6-IN. THICK FOR LIGHT DUTY ENTRANCES OR AT LEAST 10-IN. FOR HEAVY DUTY USE.
- 4. WIDTH--THE ENTRANCE SHALL BE AT LEAST 14-FT. WIDE, BUT LESS THAN THE FULL WIDTH AT POINTS WHERE INGRESS OR EGRESS OCCURS.
- 5. GEOTEXTILE--A GEOTEXTILE SHALL BE LAID OVER THE ENTIRE AREA PRIOR TO PLACING STONE. IT SHALL BE COMPOSED OF STRONG ROT-PROOF POLYMERIC FIBERS AND MEET THE FOLLOWING SPECIFICATIONS:

GEOTEXTILE SPEC. FOR CONSTRUCTION ENTRANCE				
MINIMUM TENSILE STRENGTH	200 LBS.			
MINIMUM PUNCTURE STRENGTH	80 PSI			
MINIMUM TEAR STRENGTH	50 LBS.			
MINIMUM BURST STRENGTH	320 PSI			
MINIMUM ELONGATION	20%			
EQUIVALENT OPENING SIZE	EOS < 0.60 mm			
PERMITTIVITY	1x10-3 CM/SEC			

- TIMING--THE CONSTRUCTION ENTRANCE SHALL BE INSTALLED AS SOON AS IS PRACTICABLE BEFORE MAJOR GRADING ACTIVITIES.
- 7. CULVERT--A PIPE OR CULVERT SHALL BE CONSTRUCTED UNDER THE ENTRANCE IF NEEDED TO PREVENT SURFACE WATER FLOWING ACROSS THE ENTRANCE OR TO PREVENT RUNOFF FROM BEING DIRECTED OUT ONTO PAVED SURFACES.

9. MAINTENANCE--TOP DRESSING OF ADDITIONAL STONE SHALL BE APPLIED AS CONDITIONS

- WATER BAR--A WATER BAR SHALL BE CONSTRUCTED AS PART OF THE CONSTRUCTION ENTRANCE IF NEEDED TO PREVENT SURFACE RUNOFF FROM FLOWING THE LENGTH OF THE CONSTRUCTION ENTRANCE AND OUT ONTO PAVED SURFACES.
- DEMAND. MUD SPILLED, DROPPED, WASHED OR TRACKED ONTO PUBLIC ROADS, OR ANY SURFACE WHERE RUNOFF IS NOT CHECK BY SEDIMENT CONTROLS, SHALL BE REMOVED IMMEDIATELY. REMOVAL SHALL BE ACCOMPLISHED BY SCRAPING OR SWEEPING. 10. CONSTRUCTION ENTRANCES SHALL NOT BE RELIED UPON TO REMOVE MUD FROM VEHICLES AND


PREVENT OFF-SITE TRACKING. VEHICLES THAT ENTER AND LEAVE THE CONSTRUCTION-SITE SHALL

- BE RESTRICTED FROM MUDDY AREAS. 11. REMOVAL--THE ENTRANCE SHALL REMAIN IN PLACE UNTIL THE DISTURBED AREA IS STABILIZED OR
- REPLACED WITH A PERMANENT ROADWAY OR ENTRANCE.


CONSTRUCTION ENTRANCE NOT TO SCALE

ETR RE


 $|\mathcal{S}|$ 



# PLAN VIEW



## CROSS SECTION B-B



3. TIMBER MAT IS TO REMAIN IN PLACE UNTIL COMPLETION OF FINAL RESTORATION.

THIS TYPE OF CROSSING IS GENERALLY USED FOR

SMALL STREAM CROSSINGS LESS THAN 30 FEET IN

BANKS AND RIPARIAN AREAS.

CROSSING.

WIDTH AND A PROPER STREAM BANK CONFIGURATION

2. TIMBER MAT WILL BE TEMPORARILY REMOVED

IF HIGH WATER RENDERS IT UNSAFE FOR


BANK, ON BOTH SIDES OF STREAM CROSSING IN

ORDER TO MINIMIZE DISTURBANCE OF STREAM


1. EXTEND TIMBER MAT 50 FEET, FROM TOP OF


- 4. A SKIRT FORMED OF SILT FENCE, GEOTEXTILE FABRIC, OR EQUIVALENT SHALL BE PLACED ON THE BOTTOM OF THE BRIDGE TO TRAP SEDIMENT AS NECESSARY.
- 5. INDIVIDUAL MATS SHALL BE ANCHORED AND BUTTED TIGHTLY TO MINIMIZE THE INTRODUCTION OF SEDIMENT TO THE WATERBODY.
- 6. HAY BALES WILL BE PLACED AT THE EDGE OF THE TIMBER MAT AT THE END OF EACH WORK DAY TO PREVENT EROSION, BUT WILL BE REMOVED DURING CONSTRUCTION ACTIVITY.
- 7. TEMPORARY STREAM CROSSING SHALL BE INSPECTED ON A DAILY BASIS.
- 8. DAMAGED CROSSING SHALL BE REPAIRED WITHIN 24 HOURS OF THE INSPECTION, AND BEFORE ANY SUBSEQUENT USE.
- 9. SEDIMENT DEPOSITS ON THE CROSSING OR ITS APPROACHES SHALL BE REMOVED WITHIN 24 HOURS OF INSPECTION.
- 10. ANCHOR TIMBER MAT TO A TREE, OR OTHER PERMANENT OBJECT WITH SUFFICIENT STRENGTH, USING STEEL CHAIN OR CABLE.





- 2. THE DE-WATERING PLAN SHALL INCLUDE ALL THE DEWATERING ACTIVITIES AND DESIGNATE AREAS FOR PLACEMENT OF PRACTICES. OUTLETS EITHER BY RIPRAP PROTECTION, FABRIC LINER, OR OTHER ACCEPTABLE METHOD OF OUTLET PROTECTION.
- 3. WATER THAT IS NOT DISCHARGED INTO A SETTLING/TREATMENT BASIN BUT DIRECTLY INTO WATERS OF THE STATE SHALL BE MONITORED HOURLY. DISCHARGED WATER SHALL BE WITHIN
- 4. SETTLING BASINS SHALL NOT BE GREATER THAN FOUR (4) FEET IN DEPTH. THE BASIN SHALL BE CONSTRUCTED FOR SEDIMENT STORAGE AS SOLIDS DO NOT RE-SUSPEND DURING THE DISCHARGE PROCESS. THE SETTLING BASIN SHALL BE CLEANED OUT WHEN THE STORAGE HAS BEEN REDUCED BY 50% OF ITS ORIGINAL CAPACITY.
- 5. ALL NECESSARY NATIONAL, STATE AND LOCAL PERMITS SHALL BE SECURED PRIOR TO DISCHARGING INTO WATERS OF THE STATE.






# **CROSS SECTION A-A**

- THIS TYPE OF CROSSING IS GENERALLY USED FOR UNDERGROUND UTILITY LINE CROSSINGS.
- 1. PLACE TIMBER MAT BASES 4 FEET MIN FROM UTILITY OR IRRIGATION LINE WITH AN 8 INCH MIN CLEARANCE FROM GROUND LEVEL OVER LINE.
- 2. TIMBER MAT BRIDGE SHALL BE PLACED WITH A 4 FEET MIN OVERLAP OF BASE TIMBER MATS.
- 3. TIMBER MAT IS TO REMAIN IN PLACE UNTIL COMPLETION OF FINAL RESTORATION.
- 4. INDIVIDUAL MATS SHALL BE ANCHORED AND BUTTED TIGHTLY TO MINIMIZE MOVEMENT OF MATS DURING EQUIPMENT CROSSINGS.
- 5. TEMPORARY CROSSINGS SHALL BE INSPECTED ON A DAILY BASIS.
- DAMAGED CROSSINGS SHALL BE REPAIRED WITHIN 24 HOURS OF THE INSPECTION, AND BEFORE ANY SUBSEQUENT USE.

TIMBER MAT UTILITY CROSSING N.T.S.



STAKE IN PLACE WITH —

ON CENTER

2"X2" STAKES PLACED 5'

A SPLASH APRON MAY BE

PROVIDED BY FIXING A

LENGTH OF EROSION

CONTROL OR TURF

REINFORCEMENT

MATTING

- COMPOST SOCK NETTING SHALL USE A KNITTED MESH FABRIC WITH 1/8-3/8 INCH OPENINGS, AND COMPOST MEDIA WITH PARTICLE SIZES 99% < 3 INCHES, AND 60% > 3/8 INCHES (CONFORMING TO MEDIA DESCRIBED IN THE RWLDM, CHAPTER 6 FILTER SOCK).
- COMPOST SOCK CHECK DAMS SHALL BE USED IN AREAS THAT DRAIN 5 ACRES OR LESS.
- SEDIMENT SHALL BE REMOVED FROM BEHIND THE SOCK WHEN IT REACHES 1/3 THE HEIGHT OF THE CHECK DAM.
- COMPOST SOCK CHECK DAMS SHALL BE CONSTRUCTED WITH 12, 18, OR 24 IN DIAMETER COMPOST SOCKS, AND SHALL COMPLETELY COVER THE WIDTH OF THE CHANNEL. THE MIDPOINT OF THE COMPOST SOCK CHECK DAM SHALL BE A MINIMUM OF 6 INCHES LOWER THAN THE SIDES IN ORDER TO DIRECT FLOW ACROSS THE CENTER AND AWAY FROM THE CHANNEL SIDES. FILTER SOCK CHECK DAMS SHALL BE FILLED TO A DENSITY SUCH THAT THEY SHALL REACH THEIR INTENDED HEIGHT (DIAMETER). AFTER INSTALLATION AND USE, THEY SHALL BE CONSIDERED UNSUITABLE AND IN NEED OF REPLACEMENT AFTER FALLING BELOW 80% OF THEIR MINIMUM REQUIRED HEIGHT (DIAMETER).
- ALTHOUGH NO TRENCHING IS NECESSARY, COMPOST SOCK CHECK DAMS SHALL BE PLACED ON A GRADED SURFACE WHERE CONSISTENT CONTACT WITH THE SOIL SURFACE IS MADE WITHOUT BRIDGING OVER GAPS, RILLS, GULLIES, STONES OR OTHER IRREGULARITIES.
- PLACE COMPOST SOCK CHECK DAMS SO THAT THE ENDS EXTEND TO THE TOP OF BANK. STAKING FOR COMPOST SOCK CHECK DAMS SHALL USE 2 INCH X 2 INCH WOODEN STAKES, PLACED 5 FOOT ON CENTER. STAKE LENGTH SHALL ALLOW THEM TO BE DRIVEN 12 INCHES INTO EXISTING SOIL AND ALLOW AT LEAST 2 INCHES ABOVE THE SOCK.
- 7. SPACE COMPOST SOCK CHECK DAMS SO THAT THE TOE OF THE UPSTREAM DAM IS AT THE SAME ELEVATION OR LOWER ELEVATION AS THE TOP OF THE DOWNSTREAM COMPOST SOCK CHECK DAM (AT THE CENTER OF THE CHANNEL). THIS WILL BE INFLUENCED BY THE HEIGHT OF THE SOCK AND GRADIENT OF THE WATERWAY.
- 8. A SPLASH APRON MAY BE NEEDED WHERE FLOWS OVER THE SOCK MAY ERODE THE CHANNEL AND UNDERCUT THE COMPOST SOCK CHECK DAM. CREATE THE APRON BY FIXING A LENGTH OF TEMPORARY ROLLED EROSION CONTROL PRODUCT (EROSION CONTROL MATTING) OR TURF REINFORCEMENT MATTING STARTING UPSTREAM OF THE SOCK A DISTANCE EQUAL TO THE SOCK HEIGHT AND EXTENDING A LENGTH TWO TIMES THE HEIGHT OF THE COMPOST SOCK CHECK DAM. MATERIALS USED SHOULD BE ABLE TO BE LEFT IN PLACE (E.G. BIODEDEGRADABLE/PHOTODEGRADABLE TRECP) WITHOUT CREATING PROBLEMS FOR FUTURE MOWING OR MAINTENANCE OF THE CHANNEL.

COMPOST SOCK CHECK DAM DETAIL

- 2. FENCE MATERIAL SHALL BE PLASTIC (SNOW FENCE).

PROTECTION FENCING

PUMP TO DOWNSTREAM— SKID MOUNTED — STABILIZED OUTLET SUCTION **ENERGY DISIPATER** PIPE/HOSE UPSTREAM FLOW GRAVEL — FROM DITCH LINED SUMP SOIL PLUG DAM — HDPE DISCHARGE PIPE — (HIGH DENSITY POLYETHYLENE)

\*NO BY-PASS PUMPING IS PROPOSED FOR THE CUYAHOGA RIVER. IF DEEMED NECESSARY BY THE CONTRACTOR AND SUMMIT METRO PARKS, BY-PASS PUMPING MAY BE USED FOR THE INSTALLATION OF THE BOX CULVERT AT THE EXISTING FORD LOCATION. WATER SHALL BE PUMPED INTO AN ADJACENT WETLAND OR AS DIRECTED BY SUMMIT METRO PARKS. WATER SHALL NOT BE DISCHARGED DIRECTLY INTO THE CUYHAOGA RIVER.\*


> BY-PASS PUMPING/STREAM FLOW **DIVERSION DETAIL**

ACTIVITIES BY CONTRACTOR.

PUMPS AND RELATED EQUIPMENT NECESSARY FOR FOR PRACTICES SHALL BE PROTECTED FROM SCOUR

+/- 5° F OF THE RECEIVING WATERS.

OUTLINED IN CHAPTER 6 OF THE ODNR RAINWATER & LAND DEVELOPMENT MANUAL. THE INLET AND OUTLET FOR THE BASIN SHALL BE LOCATED AT THE FURTHEST POINTS OF THE STORAGE. A FLOATING OUTLET SHALL BE USED TO ENSURE THAT SETTLED



# NOTE:

- 1. CONTRACTOR SHALL PLACE FENCING AROUND TREES TO BE SAVED OR OTHER SENSITIVE AREAS IDENTIFIED BY THE OWNER (WETLANDS). SEE THE SWPP PLANS FOR LOCATIONS OF FENCING.
- 3. FENCING AND POSTS SHALL BE REMOVED UPON PROJECT COMPLETION.